特快公屋編配計劃(2023年)暨重售青富苑及蝶翠苑綠表置居計劃單位

Express Flat Allocation Scheme (2023)-cum-Resale of Green Form Subsidised Home Ownership Scheme Flats of Ching Fu Court and Dip Tsui Court

青富苑
Ching Fu Court

售樓說明書 SALES BROCHURE

01 一手住宅物業買家須知

Notes to Purchasers of First-hand Residential Properties

你在購置青富苑綠表置居計劃(下稱「綠置居」)單位之前，應留意下列事項：

1 重要資訊

- 瀏覽一手住宅物業銷售資訊網(下稱「銷售資訊網」)(網址：www.srpe.gov.hk)，參考「銷售資訊網」內有關一手住宅物業的市場資料。
- 閱覽香港房屋委員會(下稱「房委會」)作為賣方就出售青富苑單位所指定的互聯網網站(下稱「指定網站」)(www.housingauthority.gov.hk/efas/2023/ChingFu)內的有關資訊，包括售樓說明書、價單及青富苑單位的成交紀錄冊。
- 青富苑的售樓說明書及有關價單，會在該項目的首個選購單位日期前向公眾發布。
- 在指定網站內載有青富苑單位成交資料的成交紀錄冊，以供查閱。

2 費用、按揭貸款和樓價

- 計算置業總開支，包括律師費、按揭費用、保險費，以及印花稅。
- 向銀行查詢可否取得所需的按揭貸款，然後選擇合適的還款方式，並小心計算按揭貸款金額，以確保貸款額沒有超出本身的負擔能力。
- 查閱同類物業最近的成交價格，以作比較。
- 向房委會綠置居銷售小組了解，你須付予房委會或青富苑管理人的預計的管理費、管理費上期金額(如有)、特別基金金額(如有)、補還的水、電力及氣體按金(如有)，以及/或清理廢料的費用(如有)。

3 價單、支付條款及按揭貸款安排

- 房委會會把價單所涵蓋的住宅物業悉數推售。
- 留意價單所載列的支付條款。
- 買方於綠置居銷售小組辦理簽署買賣協議手續時，須以銀行本票繳付不少於樓價的百分之五的定金，抬頭人為「香港房屋委員會」。
- 如你擬選用名列於房委會公布名單內的銀行或財務機構提供的各類按揭貸款計劃，在簽訂買賣協議前，應先細閱有關價單及其他銷售文件內列出的按揭貸款安排資料。如就按揭貸款計劃的詳情有任何疑問，應在簽訂買賣協議前，直接向有關銀行或財務機構查詢。
  - 按揭貸款安排的資料包括可獲得的按揭貸款金額上限、最長還款年期、最高按揭利率，須繳付的行政費以及買方所需的其他按揭貸款安排的相關批准(如適用)。

You are advised to take the following steps before purchasing Green Form Subsidised Home Ownership Scheme (GSH) flats in Ching Fu Court:

1 Important information

- Make reference to the materials available on the Sales of First-hand Residential Properties Electronic Platform (SRPE) (www.srpe.gov.hk) on the first-hand residential property market.
- Study the information on the website designated by the Hong Kong Housing Authority (HA) as vendor for the sale of flats in Ching Fu Court (designated website)(www.housingauthority.gov.hk/efas/2023/ChingFu), including the sales brochure, price list and the register of transactions of the flats in Ching Fu Court.
- Sales brochure and price list for Ching Fu Court will be made available to the general public before the first date of flat selection of the Development.
- Information on transactions of the flats in Ching Fu Court can be found on the register of transactions on the designated website.

2 Fees, mortgage loan and property price

- Calculate the total expenses of the purchase, such as solicitors' fees, mortgage charges, insurance fees and stamp duties.
- Check with banks to find out if you will be able to obtain the needed mortgage loan, select the appropriate payment method and calculate the amount of the mortgage loan to ensure it is within your repayment ability.
- Check recent transaction prices of comparable properties for comparison.
- Check with the HA GSH Sales Unit the estimated management fee, the amount of management fee payable in advance (if any), special fund payable (if any), the amount of reimbursement of the deposits for water, electricity and gas (if any), and/or the amount of debris removal fee (if any) you have to pay to the HA or the manager of Ching Fu Court.

3 Price list, payment terms and mortgage loan arrangement

- The HA will offer to sell all the residential properties that are covered in a price list.
- Pay attention to the terms of payment as set out in the price list.
- Purchaser must, at the time of signing the Agreement for Sale and Purchase (ASP) at the GSH Sales Unit, bring along with him/her cashier's order(s) in the sum of not less than 5% of the purchase price for paying the deposit.
- If you intend to opt for any mortgage plans offered by banks or financial institutions on the approved list provided by the HA, before entering into an ASP, you must study the details of various mortgage loan arrangement as set out in the price list and other sales documents concerned. If you have any questions about mortgage loan plans, you should check with the banks or financial institutions concerned direct before entering into an ASP.
  - The details of various mortgage loan arrangement include the loan limit, the maximum loan repayment period, mortgage interest rate, the payment of administrative fees and necessary approvals for other mortgage arrangement required by the purchaser (if applicable).

4 物業的面積及四周環境

- 留意載於售樓說明書和價單內的物業面積資料，以及載於價單內的每平方呎／每平方米售價。根據《一手住宅物業銷售條例》(第621章)(下稱「條例」)，賣方只可以實用面積表達住宅物業的面積和每平方呎及平方米的售價。就住宅物業而言，實用面積指該住宅物業的樓面面積，包括在構成該物業的一部分的範圍內的以下每一項目的樓面面積：(i)露台；(ii)工作平台；以及(iii)陽台。實用面積並不包括空調機房、窗台、閣樓、平台、花園、停車位、天台、梯屋、前庭及庭院的每一項目的面積，即使該些項目構成該物業的一部分的範圍。

- 售樓說明書必須顯示發展項目中所有住宅物業的樓面平面圖。在售樓說明書所載有關發展項目中住宅物業的每一份樓面平面圖，均須述明每個住宅物業的外部和內部尺寸。售樓說明書所提供有關住宅物業外部和內部的尺寸，不會把批盪和裝飾物料包括在內。買方收樓前如欲購置家具，應留意這點。

  - 根據條例附表1第1部第10(2)(d)條述明，售樓說明書內顯示的發展項目中的住宅物業的每一份樓面平面圖須述明以下各項：

    (i) 每個住宅物業的外部尺寸；
    (ii) 每個住宅物業的內部尺寸；
    (iii) 每個住宅物業的內部間隔的厚度；
    (iv) 每個住宅物業內個別分隔室的外部尺寸。

  - 根據條例附表1第1部第10(3)條，如有關發展項目的經批准的建築圖則，提供條例附表1第1部第10(2)(d)條所規定的資料，樓面平面圖須述明如此規定的該資料。

- 親臨發展項目的所在地實地視察，以了解有關物業的四周環境(包括交通和社區設施)；亦應查詢有否任何城市規劃方案和議決，會對有關的物業造成影響；參閱載於售樓說明書內的位置圖、鳥瞰照片、分區計劃大綱圖，以及橫截面圖。

5 售樓說明書

- 確保所取得的售樓說明書屬最新版本。根據條例，提供予公眾的售樓說明書必須是在之前的三個月之內印製或檢視、或檢視及修改。

- 如屬未落成發展項目，賣方在認為有需要時可改動建築圖則(如有的話)，因此應留意由賣方提供的任何經修改的售樓說明書，以了解有關未落成發展項目的最新資料。

- 閱覽售樓說明書，並須特別留意以下資訊：

  - 售樓說明書內有否關於「有關資料」的部分，列出賣方知悉但並非為一般公眾人士所知悉，關於相當可能對享用有關住宅物業造成重大影響的事宜的資料。請注意，已在土地註冊處註冊的文件，其內容不會被視為「有關資料」；
  - 橫截面圖會顯示有關建築物相對毗連該建築物的每條街道的橫截面，以及每條上述街道與已知基準面和該建築物最低的一層住宅樓層的水平相對的

4 Property area and its surroundings

- Pay attention to the area information in the sales brochure and price list, and price per square foot/metre in the price list. According to the Residential Properties (First-hand Sales) Ordinance (Cap. 621) (the Ordinance), vendors can only present the area and price per square foot and per square metre of a residential property using saleable area. Saleable area, in relation to a residential property, means the floor area of the residential property, and includes the floor area of every one of the following to the extent that it forms part of the residential property — (i) a balcony; (ii) a utility platform; and (iii) a verandah. The saleable area excludes the area of the following which forms part of the residential property — air-conditioning plant room; bay window; cockloft; flat roof; garden; parking space; roof; stairhood; terrace and yard.

- Floor plans of all residential properties in the development have to be shown in the sales brochure. In a sales brochure, floor plans of residential properties in the development must state the external and internal dimensions of each residential property. The external and internal dimensions of residential properties as provided in the sales brochure exclude plaster and finishes. You are advised to note this if you want to buy furniture before handing over of the residential property.

  - According to section 10(2)(d) in Part 1 of Schedule 1 to the Ordinance, each of the floor plans of the residential properties in the development in the sales brochure must state the following:

    (i) the external dimensions of each residential property;
    (ii) the internal dimensions of each residential property;
    (iii) the thickness of the internal partitions of each residential property;
    (iv) the external dimensions of individual compartments in each residential property.

  - According to section 10(3) in Part 1 of Schedule 1 to the Ordinance, if any information required by section 10(2)(d) in Part 1 of Schedule 1 to the Ordinance is provided in the approved building plans for the development, a floor plan must state the information as so provided.

- Visit the development site and get to know the surroundings of the property (including transportation and community facilities). Check town planning proposals and decisions which may affect the property. Take a look at the location plan, aerial photograph, outline zoning plan and cross-section plan that are provided in the sales brochure.

5 Sales brochure

- Ensure that the sales brochure obtained is the latest version. According to the Ordinance, the sales brochure made available to the public should be printed or examined, or examined and revised within the previous 3 months.

- In respect of an uncompleted development, the vendor may alter the building plans (if any) whenever the vendor considers necessary. To know the latest information of an uncompleted development, keep paying attention to any revised sales brochures made available by the vendor.

- Read through the sales brochure and in particular, check the following information in the sales brochure:

  - whether there is a section on "relevant information" in the sales brochure, under which information on any matter that is known to the vendor but is not known to the general public, and is likely to materially affect the enjoyment of a residential property will be set out. Please note that information contained in a document that has been registered with the Land Registry will not be regarded as "relevant information";
  - the cross-section plan showing a cross-section of the building in relation to every street adjacent to the building, and the level of every such street in relation to a known datum and to the level of the lowest

水平。橫截面圖能以圖解形式，顯示出建築物最低一層住宅樓層和街道水平的高低差距，不論該最低住宅樓層以何種方式命名；

- 室內和外部的裝置、裝修物料和設備；
- 管理費按甚麼基準分擔；
- 小業主有否責任或需要分擔管理、營運或維持有關發展項目以內或以外的公眾休憩用地或公共設施的開支，以及有關公眾休憩用地或公共設施的位置；以及
- 小業主是否須要負責維修斜坡。

6 政府批地文件和公契

- 閱覽政府批地文件和公契（或公契擬稿）。公契內載有天台和外牆業權等相關資料。房委會會在綠置居銷售小組提供政府批地文件和公契（或公契擬稿）的複本，供準買方免費閱覽。
- 留意政府批地文件內所訂明小業主是否須要負責支付地稅。
- 留意公契內訂明有關住宅物業內可否飼養動物。

7 售樓處內有關可供揀選住宅物業的資料

- 向綠置居銷售小組查詢清楚有那些一手住宅物業可供揀選。你可從綠置居銷售小組展示的「銷售情況表」得悉在每個銷售日的銷售進度資料，包括在該個銷售日內有那些住宅物業已獲揀選及售出。
- 切勿隨便相信有關發展項目銷情的傳言，倉卒簽立買賣協議。

8 成交紀錄冊

- 留意發展項目的成交紀錄冊。房委會須於買賣協議訂立後一個工作天內，披露該買賣協議的資料。你可透過成交紀錄冊得悉發展項目的銷售情況。

9 買賣協議

- 留意有關物業買賣交易所包括的裝置、裝修物料和設備，須在買賣協議上列明。
- 留意夾附於買賣協議的圖則。該圖則會顯示所有賣方售予你的物業面積，而該面積通常較該物業的實用面積為大。
- 留意賣方有權改動未落成發展項目的建築圖則(如有的話)。如屬未落成發展項目，物業的買賣合約會載有條文，列明如有關改動在任何方面對該物業造成影響，賣方須在改動獲房屋局常任秘書長辦公室的獨立審查組(前運輸及房屋局常任秘書長(房屋)辦公室的獨立審查組)批准後的14日內，將該項改動以書面通知買方。

residential floor of the building. This will help you visualise the difference in height between the lowest residential floor of a building and the street level, regardless of how that lowest residential floor is named;

- interior and exterior fittings and finishes and appliances;
- the basis on which management fees are shared;
- whether individual owners have obligations or need to share the expenses for managing, operating and maintaining the public open space or public facilities inside or outside the development, and the location of the public open space or public facilities; and
- whether individual owners have responsibility to maintain slopes.

6 Government land grant and deed of mutual covenant (DMC)

- Read the Government land grant and the DMC (or the draft DMC). Information such as ownership of the rooftop and external walls can be found in the DMC. The HA will provide copies of the Government land grant and the DMC (or the draft DMC) at the GSH Sales Unit for free inspection by prospective purchasers.
- Check the Government land grant on whether individual owners are liable to pay Government rent.
- Check the DMC on whether animals can be kept in the residential property.

7 Information on availability of residential properties for selection at sales office

- Check with the GSH Sales Unit which residential properties are available for selection. You may check from the status of sale of flats table displayed at the GSH Sales Unit on the progress of sale on a date of sale, including which residential properties have been selected and sold during that date of sale.
- Do not believe in rumours about the sales condition of the development and enter into an ASP rashly.

8 Register of transactions

- Pay attention to the register of transactions for a development. The HA must, within 1 working day after entering into an ASP, enter transaction information of the ASP in the register of transactions. Check the register of transactions for the concerned development to learn more about the sales condition of the development.

9 Agreement for sale and purchase

- Pay attention that fittings, finishes and appliances to be included in the sale and purchase of the property are inserted in the ASP.
- Pay attention to the floor plan annexed to the ASP which shows the total area which the vendor is selling to you. The total area which the vendor is selling to you is normally greater than the saleable area of the property.
- Pay attention to the vendor's right to alter the building plans (if any) for an uncompleted development. A provision is incorporated in an ASP for uncompleted development requiring the vendor to notify the purchaser in writing of such alteration if the same affects in any way the property within 14 days after its having been approved by the Independent Checking Unit of the Office of the Permanent Secretary for Housing (formerly, the Independent Checking Unit of the Office of the Permanent Secretary for Transport and Housing (Housing)).

- 於綠置居銷售小組簽署買賣協議時，你須向房委會繳付不少於樓價的百分之五作為定金(請參閱第一頁的第三項有關價單、支付條款及按揭貸款安排)。
- 若你要求撤銷買賣協議，且獲房委會同意，房委會有權保留一筆相等於樓價百分之五的款額，作為同意撤銷買賣協議買方應付的代價。此外，你須向房委會支付或償付與撤銷買賣協議有關或其引致的一切法律費用、收費及代付費用(如有印花稅，此項亦包括在內)。
- 買方只可將該物業作私人住宅用途，及受制於《房屋條例》(第283章)、「限制轉讓條款」、「政府批地書」及其任何修訂條文或變更的規定，並確保該物業將由其本人及名列公屋申請內的全部家庭成員居住。任何家庭成員(包括買方本人在內)倘事前未得房委會的書面同意，不再實際或永久居於該物業，則不論原因為何，房委會有權要求買方把該物業轉讓回房委會，而買方在收到房委會的書面通知後，須立即把該物業轉讓回房委會，有關費用及支出概由買方負責。

10 委聘律師

- 你應在參與選購單位前，自行聘請你屬意的律師行，代表你處理買樓交易。如你自行聘請律師行代表你處理買樓交易，該律師行便能夠在購樓交易的每個階段向你提供獨立意見。如你選擇委聘房委會的代表律師行代表你辦理買賣交易，有關律師行將同時代表你及房委會，倘發生利益衝突，未必能夠保障你的最大利益。
- 你須注意你會在房委會職員面前簽署買賣協議，有關職員只會向你詮釋買賣協議內容及見證你簽署買賣協議，他們不會就買賣協議或與交易有關的任何其他事宜，向你提供任何法律意見。
- 如所購青富苑單位的售價為一百萬元以上，你必須自行委聘屬意的律師行代表你辦理購買單位事宜。該律師行不可以是房委會為有關單位所委聘的律師行。
- 如所購青富苑單位的售價不超逾一百萬元，你可：
  (i) 自行委聘屬意的律師行代表你辦理購買單位事宜；或
  (ii) 委聘房委會的代表律師行代表你辦理購買單位事宜。
- 比較不同律師的收費。
  (請參閱第92頁的對買方的警告)

適用於一手未落成住宅物業

11 預計關鍵日期及收樓日期

- 查閱售樓說明書中青富苑的預計關鍵日期。
  - 「關鍵日期」指該項目在遵照經批准的建築圖則的情況下在各方面均屬完成的日期。有關「關鍵日期」的定義的詳情，請參閱條例第2條。
  - 售樓說明書中青富苑的預計關鍵日期並不等同買方的「收樓日期」。
- 青富苑的收樓日期：
  - 房委會須於青富苑在遵照經批准的建築圖則的情況下在各方面均屬完成後的14日內，以書面為該項目申請佔用文件(即佔用許可證)。
  - 房委會須在佔用文件(即佔用許可證)發出後的六個月內，就其有能力有效地轉讓有關物業一事，以書面通知買方。

- At the time of signing the ASP at the GSH Sales Unit, a deposit of not less than 5% of the purchase price is payable by you to the HA (Please refer to item 3 on page 1 regarding price list, payment terms and mortgage loan arrangement).
- If you request for cancelling the ASP where the HA agrees to the same, the HA shall be entitled to retain a sum equivalent to 5% of the purchase price as consideration for his agreeing to cancel the ASP. Besides, you are required to pay or reimburse the HA for all legal costs, charges and disbursements (including stamp duty, if any) in connection with or arising from the cancellation of the ASP.
- The purchaser shall use the property for private residential purposes only, and subject to the Housing Ordinance (Cap.283), the Restriction on Alienation Clause, the Government Grant and any amendments or modifications thereto, shall ensure that the property shall be occupied by himself and all the members of his family listed in the application for public rental housing. If, without the prior written consent of the HA, any family member, including the purchaser, does not or ceases to actually or permanently live in the property for whatsoever reason(s), the HA has the right to require the purchaser to assign the property back to the HA. The purchaser shall forthwith upon the written notice of the HA assign the property back to the HA at the costs and expenses of the purchaser.

10 Appointment of solicitor

- Before attending flat selection, you are urged to engage a separate firm of solicitors of your choice to act for you in relation to the transaction. If you appoint a separate firm of solicitors to act for you in relation to the transaction, that firm of solicitors will be able to give independent advice to you at every stage of the purchase. If you appoint the HA's solicitors to act for you in relation to the transaction, the solicitors will be acting jointly for the HA and you, and they may not be able to protect your best interests in the event of a conflict of interest.
- It should be noted that the ASP shall be signed by you before the staff of the HA who will only interpret the contents of the ASP to you and attest your signing of the ASP. The staff will not give you any legal advice on the ASP or any other matters in connection with the transaction.
- If the price of the flat in Ching Fu Court is over one million dollars, you must appoint a separate firm of solicitors of your choice to act for you in relation to the transaction. Such firm of solicitors should not be the firm of solicitors appointed by the HA for the concerned flat.
- If the price of the flat in Ching Fu Court does not exceed one million dollars, you may either:
  (i) appoint a separate firm of solicitors of your choice to act for you in relation to the transaction; or
  (ii) appoint the HA's solicitors to act for you in relation to the transaction.
- Compare the charges of different solicitors.
  (Please refer to Warning to Purchasers on page 92).

For first-hand uncompleted residential properties

11 Estimated material date and handing over date

- Check the estimated material date for Ching Fu Court in the sales brochure.
  - "Material date" means the date on which the Development is completed in all respects in compliance with the approved building plans. For details of the definition of "material date", please refer to section 2 of the Ordinance.
  - The estimated material date for Ching Fu Court in the sales brochure is not the same as the date on which a residential property is handed over to purchaser.
- Handing over date for Ching Fu Court:
  - The HA shall apply in writing for an occupation document (i.e. Occupation Permit) in respect of Ching Fu Court within 14 days after its having completed the Development in all respects in compliance with the approved building plans.
  - The HA shall notify the purchaser in writing that it is in a position validly to assign the property within 6 months after the issue of the occupation document (i.e. Occupation Permit).

- 有關物業的買賣須於房委會發出上述通知的日期的14日內完成。有關物業的買賣完成後，房委會將安排買方收樓事宜。

- 委任建築師可批予在預計關鍵日期之後完成青富苑。
  - 房委會有權獲得委任建築師在顧及純粹由以下一個或多於一個原因所導致的延遲後，批予在預計關鍵日期之後，完成發展項目：
    - 工人罷工或封閉工地；
    - 暴動或內亂；
    - 不可抗力或天災；
    - 火警或其他房委會所不能控制的意外；
    - 戰爭；或
    - 惡劣天氣。
  - 委任建築師可以按情況，多於一次批予延後預計關鍵日期以完成發展項目，即收樓日期可能延遲。
  - 房委會須於委任建築師批予延期後的14日內，向買方提供有關延期證明書的文本。
- 如對收樓日期有任何疑問，可向房委會查詢。

適用於一手已落成住宅物業

12 賣方資料表格

- 確保取得最近三個月內印製有關你擬購買的一手已落成住宅物業的「賣方資料表格」。

13 買方須注意的其他事項

- 有關青富苑綠置居單位的轉讓限制，請參閱第133頁至134頁。
- 本銷售計劃下出售的青富苑綠置居單位的使用、佔用及轉讓限制(包括業權轉讓或出租限制)是受制於政府租契、買賣協議及轉讓契據所載的條款、契諾、條件和相關規定。

其他相關聯絡資料

	電話	傳真	網址/電郵
一手住宅物業銷售監管局	2817 3313	2219 2220	www.srpa.gov.hk/ enquiry_srpa@hd.gov.hk
消費者委員會	2929 2222	2856 3611	www.consumer.org.hk/ cc@consumer.org.hk
地產代理監管局	2111 2777	2598 9596	www.eaa.org.hk/ enquiry@eaa.org.hk
香港地產建設商會	2826 0111	2845 2521	–
稅務局	2594 3202	2519 6740	www.ird.gov.hk/ taxsdo@ird.gov.hk

- The sale and purchase shall be completed within 14 days after the date of the notification aforesaid. Upon completion of the sale and purchase, the HA shall arrange handover of the property to the purchaser.

- Appointed Architect may grant extension(s) of time for completion of Ching Fu Court beyond the estimated material date.
  - The HA is entitled to an extension of time for completion of the development beyond the estimated material date as granted by the Appointed Architect having regard to delays caused exclusively by any one or more of the following reasons:
    - strike or lock-out of workmen;
    - riots or civil commotion;
    - force majeure or Act of God;
    - fire or other accident beyond the HA's control;
    - war; or
    - inclement weather.
  - The Appointed Architect may grant more than once such an extension of time depending on the circumstances. That means handover of the property may be delayed.
  - The HA shall within 14 days after the issue of an extension of time granted by the Appointed Architect, furnish the purchaser with a copy of the relevant certificate of extension.
- Ask the HA if there are any questions on handing over date.

For first-hand completed residential properties

12 Vendor's information form

- Ensure that you obtain the "vendor's information form" printed within the previous 3 months in relation to the residential property you intend to purchase.

13 Other points to note

- For alienation restrictions of GSH flats in Ching Fu Court, please refer to 133 to page 134.
- The use, occupation and alienation restrictions (including restrictions on assignment or letting) of GSH flats in Ching Fu Court under the current sale exercise are subject to the terms, covenants, conditions and relevant requirements contained in the Government lease, the ASP and the Deed of Assignment.

Other useful contacts:

	Telephone	Fax	Website/Email
Sales of First-hand Residential Properties Authority	2817 3313	2219 2220	www.srpa.gov.hk/ enquiry_srpa@hd.gov.hk
Consumer Council	2929 2222	2856 3611	www.consumer.org.hk/ cc@consumer.org.hk
Estate Agents Authority	2111 2777	2598 9596	www.eaa.org.hk/ enquiry@eaa.org.hk
Real Estate Developers Association of Hong Kong	2826 0111	2845 2521	–
Inland Revenue Department	2594 3202	2519 6740	www.ird.gov.hk/ taxsdo@ird.gov.hk

02 發展項目的資料
Information on the Development

發展項目名稱	Name of the Development
青富苑	Ching Fu Court
街道名稱及門牌號數 青衣路18號	Name of street and street number 18 Tsing Yi Road
樓層總數 A座：43層（包括地下低層1樓、地下及天台） B座：43層（包括地下低層1樓、地下及天台）	Total number of storeys Block A: 43 storeys (including lower ground floor one, ground floor and roof) Block B: 43 storeys (including lower ground floor one, ground floor and roof)
樓層號數 A座：地下低層1樓、地下、1樓至40樓及天台 B座：地下低層1樓、地下、1樓至40樓及天台	Floor numbering Block A: LG1/F, G/F, 1/F to 40/F and roof Block B: LG1/F, G/F, 1/F to 40/F and roof
被略去的樓層號數 不適用	Omitted floor numbers Not applicable
庇護層 不適用	Refuge floor Not applicable

註： 青富苑已於2023年3月7日獲發佔用文件(即佔用許可證)。

Note: An occupation document (i.e. Occupation Permit) of Ching Fu Court was obtained on 7 March 2023.

03 賣方及有參與發展項目的其他人的資料
Information on Vendor and Others Involved in the Development

賣方	Vendor
香港房屋委員會	Hong Kong Housing Authority
委任建築師	**Appointed architect**
房屋署總建築師（六）	Chief Architect (6), Housing Department
承建商	**Building contractor**
中國建築工程(香港)有限公司	China State Construction Engineering (Hong Kong) Limited
代表賣方的律師事務所	**Firms of solicitors acting for the vendor**
中倫律師事務所有限法律責任合夥、薛馮鄺岑律師行、 何耀棣律師事務所、劉漢銓律師行、高李葉律師行、胡百全律師事務所	Zhong Lun Law Firm LLP; Sit, Fung, Kwong & Shum; Gallant; Chu & Lau; Kao, Lee & Yip; P. C. Woo & Co.
已為發展項目的建造提供貸款或已承諾為該項建造提供融資的認可機構	**Authorised institution that has made a loan, or has undertaken to provide finance, for the construction of the Development**
不適用	Not applicable
已為發展項目的建造提供貸款的任何其他人	**Any other person who has made a loan for the construction of the Development**
不適用	Not applicable

04 有參與發展項目的各方的關係

Relationship between Parties Involved in the Development

a	賣方或有關發展項目的承建商屬個人，並屬該項目的認可人士的家人；	不適用	the vendor or a building contractor for the Development is an individual, and that vendor or contractor is an immediate family member of an authorised person for the Development;	Not applicable
b	賣方或該項目的承建商屬合夥，而該賣方或承建商的合夥人屬上述認可人士的家人；	不適用	the vendor or a building contractor for the Development is a partnership, and a partner of that vendor or contractor is an immediate family member of such an authorised person;	Not applicable
c	賣方或該項目的承建商屬法團，而該賣方或承建商（或該賣方的控權公司）的董事或秘書屬上述認可人士的家人；	不適用	the vendor or a building contractor for the Development is a corporation, and a director or the secretary of that vendor or contractor (or a holding company of that vendor) is an immediate family member of such an authorised person;	Not applicable
d	賣方或該項目的承建商屬個人，並屬上述認可人士的有聯繫人士的家人；	不適用	the vendor or a building contractor for the Development is an individual, and that vendor or contractor is an immediate family member of an associate of such an authorised person;	Not applicable
e	賣方或該項目的承建商屬合夥，而該賣方或承建商的合夥人屬上述認可人士的有聯繫人士的家人；	不適用	the vendor or a building contractor for the Development is a partnership, and a partner of that vendor or contractor is an immediate family member of an associate of such an authorised person;	Not applicable
f	賣方或該項目的承建商屬法團，而該賣方或承建商（或該賣方的控權公司）的董事或秘書屬上述認可人士的有聯繫人士的家人；	不適用	the vendor or a building contractor for the Development is a corporation, and a director or the secretary of that vendor or contractor (or a holding company of that vendor) is an immediate family member of an associate of such an authorised person;	Not applicable
g	賣方或該項目的承建商屬個人，並屬就該項目內的住宅物業的出售代表擁有人行事的律師事務所行事的經營人的家人；	不適用	the vendor or a building contractor for the Development is an individual, and that vendor or contractor is an immediate family member of a proprietor of a firm of solicitors acting for the owner in relation to the sale of residential properties in the Development;	Not applicable
h	賣方或該項目的承建商屬合夥，而該賣方或承建商的合夥人屬就該項目內的住宅物業的出售代表擁有人行事的律師事務所行事的經營人的家人；	不適用	the vendor or a building contractor for the Development is a partnership, and a partner of that vendor or contractor is an immediate family member of a proprietor of a firm of solicitors acting for the owner in relation to the sale of residential properties in the Development;	Not applicable
i	賣方或該項目的承建商屬法團，而該賣方或承建商（或該賣方的控權公司）的董事或秘書屬上述律師事務所的經營人的家人；	不適用	the vendor or a building contractor for the Development is a corporation, and a director or the secretary of that vendor or contractor (or a holding company of that vendor) is an immediate family member of a proprietor of such a firm of solicitors;	Not applicable
j	賣方、賣方的控權公司或有關發展項目的承建商屬私人公司，而該項目的認可人士或該認可人士的有聯繫人士持有該賣方、控權公司或承建商最少10%的已發行股份；	不適用	the vendor, a holding company of the vendor, or a building contractor for the Development, is a private company, and an authorised person for the Development, or an associate of such an authorised person, holds at least 10% of the issued shares in that vendor, holding company or contractor;	Not applicable

k	賣方、賣方的控權公司或該項目的承建商屬上市公司，而上述認可人士或上述有聯繫人士持有該賣方、控權公司或承建商最少1%的已發行股份；	不適用	the vendor, a holding company of the vendor, or a building contractor for the Development, is a listed company, and such an authorised person, or such an associate, holds at least 1% of the issued shares in that vendor, holding company or contractor;	Not applicable
l	賣方或該項目的承建商屬法團，而上述認可人士或上述有聯繫人士屬該賣方、承建商或該賣方的控權公司的僱員、董事或秘書；	不適用	the vendor or a building contractor for the Development is a corporation, and such an authorised person, or such an associate, is an employee, director or secretary of that vendor or contractor or of a holding company of that vendor;	Not applicable
m	賣方或該項目的承建商屬合夥，而上述認可人士或上述有聯繫人士屬該賣方或承建商的僱員；	不適用	the vendor or a building contractor for the Development is a partnership, and such an authorised person, or such an associate, is an employee of that vendor or contractor;	Not applicable
n	賣方、賣方的控權公司或該項目的承建商屬私人公司，而就該項目中的住宅物業的出售而代表擁有人行事的律師事務所的經營人持有該賣方、控權公司或承建商最少10%的已發行股份；	不適用	the vendor, a holding company of the vendor, or a building contractor for the Development, is a private company, and a proprietor of a firm of solicitors acting for the owner in relation to the sale of residential properties in the Development holds at least 10% of the issued shares in that vendor, holding company or contractor;	Not applicable
o	賣方、賣方的控權公司或該項目的承建商屬上市公司，而上述律師事務所的經營人持有該賣方、控權公司或承建商最少1%的已發行股份；	不適用	the vendor, a holding company of the vendor, or a building contractor for the Development, is a listed company, and a proprietor of such a firm of solicitors holds at least 1% of the issued shares in that vendor, holding company or contractor;	Not applicable
p	賣方或該項目的承建商屬法團，而上述律師事務所的經營人屬該賣方或承建商或該賣方的控權公司的僱員、董事或秘書；	不適用	the vendor or a building contractor for the Development is a corporation, and a proprietor of such a firm of solicitors is an employee, director or secretary of that vendor or contractor or of a holding company of that vendor;	Not applicable
q	賣方或該項目的承建商屬合夥，而上述律師事務所的經營人屬該賣方或承建商的僱員；	不適用	the vendor or a building contractor for the Development is a partnership, and a proprietor of such a firm of solicitors is an employee of that vendor or contractor;	Not applicable
r	賣方或該項目的承建商屬法團，而該項目的認可人士以其專業身分擔任董事或僱員的法團為該賣方或承建商或該賣方的控權公司的有聯繫法團；	不適用	the vendor or a building contractor for the Development is a corporation, and the corporation of which an authorised person for the Development is a director or employee in his or her professional capacity is an associate corporation of that vendor or contractor or of a holding company of that vendor;	Not applicable
s	賣方或該項目的承建商屬法團，而該承建商屬該賣方或該賣方的控權公司的有聯繫法團。	不適用	the vendor or a building contractor for the Development is a corporation, and that contractor is an associate corporation of that vendor or of a holding company of that vendor.	Not applicable

05 發展項目的設計的資料
Information on Design of the Development

發展項目將會有構成圍封牆的一部分的非結構的預製外牆。

非結構的預製外牆的厚度範圍：

A座：150毫米-270毫米
B座：150毫米-200毫米

每個住宅物業的非結構的預製外牆的總面積：

There will be non-structural prefabricated external walls forming part of the enclosing walls of the Development.

Range of thickness of the non-structural prefabricated external walls:

Block A : 150mm - 270mm
Block B : 150mm - 200mm

Total area of the non-structural prefabricated external walls of each residential property:

座數 Block	樓層 Floor	單位 Flat	每個住宅物業的非結構的預製外牆的總面積（平方米） Total area of the non-structural prefabricated external walls of each residential property (sq.m.)
A	1樓 – 40樓 1/F – 40/F	1, 2, 3, 7, 10, 14, 15, 16, 26, 29, 32, 35	0.553
		4, 5, 6, 11, 13	0.717
		8, 9, 20, 28, 33, 34	0.760
		12, 25, 30, 31, 36	1.096
		17, 18	0.997
		19	0.590
		21, 27	0.936
		22	0.862
		23, 24	1.810
B	1樓 – 40樓 1/F – 40/F	1, 3, 6, 8, 9, 10, 11, 22, 23, 24, 26, 29, 32, 35	0.553
		2, 12, 20, 21	0.717
		4, 5, 27, 28, 33, 34	0.760
		7, 13, 25, 30, 31, 36	1.096
	3樓 – 40樓 3/F – 40/F	15, 18	0.553
		14, 19	0.717
		16, 17	0.760

構成圍封牆的一部分的幕牆：不適用


Curtain walls forming part of the enclosing walls: Not applicable

06 物業管理的資料
Information on Property Management

根據公契在售樓說明書的印製日期的最新擬稿獲委任的該發展項目的管理人	The Manager of the Development appointed under the latest draft Deed of Mutual Covenant as at the date on which the sales brochure is printed
香港房屋委員會	Hong Kong Housing Authority

07 發展項目的所在位置圖

Location Plan of the Development



比例尺 SCALE: 0 50 100 150 200 250 (米) (m)

N

青富苑
Ching Fu Court

圖例 NOTATION

污水處理廠及設施 Sewage Treatment Works and Facilities	社會福利設施(包括老人中心及弱智人士護理院) Social Welfare Facilities (including an Elderly Centre and a Home for the Mentally Disabled)
市場(包括濕貨市場及批發市場) A Market (including a Wet Market and a Wholesale Market)	體育設施(包括運動場及游泳池) Sports Facilities (including a Sports Ground and a Swimming Pool)
發電廠(包括電力分站) A Power Plant (including Electricity Sub-stations)	公園 A Public Park
公眾停車場(包括貨車停泊處) A Public Carpark (including a Lorry Park)	公共交通總站(包括鐵路車站) A Public Transport Terminal (including a Rail Station)
學校(包括幼稚園) A School (including a Kindergarten)	公用事業設施裝置 A Public Utility Installation
油站 A Petrol Filling Station	貨物裝卸區 A Cargo Working Area

此位置圖參考日期為2024年1月4日之測繪圖(編號為T10-NE-B)製作,有需要處經修正處理。
地圖由香港地理數據站提供,香港特別行政區政府為知識產權擁有人。

The Location Plan is prepared with reference to Survey Sheet No. T10-NE-B dated 4 January 2024, with adjustments where necessary.

The map is provided by the Hong Kong GeoData Store and intellectual property rights are owned by the Government of the HKSAR.


註:

1. 賣方建議買方到該發展項目作實地考察,以對該發展項目、其周邊地區環境及附近的公共設施有較佳的了解。
2. 由於該發展項目的邊界不規則的技術原因,此位置圖所顯示的範圍可能超過《一手住宅物業銷售條例》所要求顯示的範圍。

Notes :

1. The Vendor advises purchasers to conduct on-site visit for a better understanding of the Development, its surrounding environment and the public facilities nearby.
2. The plan may show more than the area required under the Residential Properties (First-hand Sales) Ordinance due to the technical reason that the boundary of the Development is irregular.

08 發展項目的鳥瞰照片
Aerial Photograph of the Development



N

● 青富苑
Ching Fu Court

摘錄自地政總署測繪處於2022年12月10日在6,900呎飛行高度拍攝之鳥瞰照片，照片編號為E172136C。
照片由香港地理數據站提供，香港特別行政區政府為知識產權擁有人。

Adopted from part of the aerial photograph taken by the Survey and Mapping Office of the Lands Department at a flying height of 6,900 feet, photo no. E172136C, dated 10 December 2022.

The photo is provided by the Hong Kong GeoData Store and intellectual property rights are owned by the Government of the HKSAR.


註：

1. 該發展項目的鳥瞰照片之副本可於房委會綠置居銷售小組辦事處開放時間內免費查閱。
2. 由於該發展項目的邊界不規則的技術原因，此鳥瞰照片所顯示的範圍可能超過《一手住宅物業銷售條例》所要求顯示的範圍。

Notes :

1. Copy of the aerial photograph of the Development is available for free inspection during opening hours at the office of the Green Form Subsidised Home Ownership Scheme Sales Unit of the HA.
2. The aerial photograph may show more than the area required under the Residential Properties (First-hand Sales) Ordinance due to the technical reason that the boundary of the Development is irregular.

發展項目的鳥瞰照片
Aerial Photograph of the Development



N

● 青富苑
Ching Fu Court

摘錄自地政總署測繪處於2022年12月10日在6,900呎飛行高度拍攝之鳥瞰照片，照片編號為E172134C。
照片由香港地理數據站提供，香港特別行政區政府為知識產權擁有人。

Adopted from part of the aerial photograph taken by the Survey and Mapping Office of the Lands Department at a flying height of 6,900 feet, photo no. E172134C, dated 10 December 2022.

The photo is provided by the Hong Kong GeoData Store and intellectual property rights are owned by the Government of the HKSAR.

註：


1. 該發展項目的鳥瞰照片之副本可於房委會綠置居銷售小組辦事處開放時間內免費查閱。
2. 由於該發展項目的邊界不規則的技術原因，此鳥瞰照片所顯示的範圍可能超過《一手住宅物業銷售條例》所要求顯示的範圍。

Notes :

1. Copy of the aerial photograph of the Development is available for free inspection during opening hours at the office of the Green Form Subsidised Home Ownership Scheme Sales Unit of the HA.
2. The aerial photograph may show more than the area required under the Residential Properties (First-hand Sales) Ordinance due to the technical reason that the boundary of the Development is irregular.

09 關乎發展項目的分區計劃大綱圖

Outline Zoning Plan Relating to the Development



N

青富苑
Ching Fu Court

圖例 NOTATION

地帶 ZONES					
C	商業	Commercial	G/IC	政府、機構或社區	Government, Institution or Community
R(A)	住宅(甲類)	Residential (Group A)	O	休憩用地	Open Space
R(B)	住宅(乙類)	Residential (Group B)	OU	其他指定用途	Other Specified Uses
V	鄉村式發展	Village Type Development	GB	綠化地帶	Green Belt
I	工業	Industrial	SSSI	具特殊科學價值地點	Site of Special Scientific Interest

交通 COMMUNICATIONS				
車站 Station	鐵路及車站	Railway and Station	主要道路及路口	Major Road and Junction
車站 Station	鐵路及車站(地下)	Railway and Station (Underground)	高架道路	Elevated Road
車站 Station	鐵路及車站(高架)	Railway and Station (Elevated)		

其他 MISCELLANEOUS				
1	規劃區編號	Planning Area Number	200 最高建築物高度(在主水平基準上若干米)	Maximum Building Height (in metres above Principal Datum)
PFS	加油站	Petrol Filling Station		

摘錄自2022年10月28日刊憲之青衣分區計劃大綱核准圖，圖則編號為S/TY/32。

Adopted from part of the approved Tsing Yi Outline Zoning Plan No. S/TY/32 gazetted on 28 October 2022.

註：


1. 賣方建議買方到該發展項目作實地考察，以對該發展項目、其周邊地區環境及附近的公共設施有較佳的了解。
2. 由於該發展項目的邊界不規則的技術原因，此圖所顯示的範圍可能超過《一手住宅物業銷售條例》所要求顯示的範圍。
3. 政府可根據《城市規劃條例》，隨時更改分區計劃大綱圖。
4. 在售樓說明書印製日期適用的最新版本的分區計劃大綱圖可於房委會綠置居銷售小組辦事處開放時間內免費查閱。

Notes :

1. The Vendor advises purchasers to conduct on-site visit for a better understanding of the Development, its surrounding environment and the public facilities nearby.
2. The plan may show more than the area required under the Residential Properties (First-hand Sales) Ordinance due to the technical reason that the boundary of the Development is irregular.
3. The Government may revise the Outline Zoning Plan in accordance with the Town Planning Ordinance as and when necessary.
4. The latest version of Outline Zoning Plan as at the date of printing of the sales brochure is available for free inspection during opening hours at the office of the Green Form Subsidised Home Ownership Scheme Sales Unit of the HA.

10 發展項目的布局圖

Layout Plan of the Development



圖例 NOTATION

——·——·——	地界	Lot Boundary	CP	露天汽車停車位	Open Car Parking Spaces
①	A座1樓至40樓單位室號	Block A Flat Number on 1/F-40/F	L/UL	露天上落客貨停車位	Open Parking, Loading/Unloading Spaces
	B座3樓至40樓單位室號	Block B Flat Number on 3/F-40/F	GP	露天輕型貨車停車位	Open Light Goods Vehicle Parking Spaces
P	花槽	Planter			

11 發展項目的住宅物業的樓面平面圖

Floor Plans of Residential Properties in the Development

A 座 1 樓平面圖
Block A 1/F Floor Plan



圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	簷篷/平台	Canopy/Flat Roof
	罩屋	Dog House

1. 每個住宅物業的層與層之間的高度為2.75米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)


註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

A 座 1樓平面圖
Block A 1/F Floor Plan





比例尺SCALE: 0 5(米) (m)

圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	簷篷/平台	Canopy/Flat Roof
	罩屋	Dog House


1. 每個住宅物業的層與層之間的高度為2.75米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)


註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

A 座 2樓-40樓平面圖
Block A 2/F-40/F Floor Plan





比例尺 SCALE: 0 5(米) (m)

圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room

1. 每個住宅物業的層與層之間的高度為2.75米(40樓除外)。40樓每個住宅物業的層與層之間的高度為2.80米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米(40樓除外)。40樓每個住宅物業的樓板(不包括灰泥)的厚度為200毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)

註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m (except 40/F). The floor-to-floor height of each residential property on 40/F is 2.80m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm (except 40/F). The thickness of the floor slab (excluding plaster) of each residential property on 40/F is 200mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

A 座 2樓-40樓平面圖
Block A 2/F-40/F Floor Plan



圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room

1. 每個住宅物業的層與層之間的高度為2.75米(40樓除外)。40樓每個住宅物業的層與層之間的高度為2.80米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米(40樓除外)。40樓每個住宅物業的樓板(不包括灰泥)的厚度為200毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)


註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m (except 40/F). The floor-to-floor height of each residential property on 40/F is 2.80m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm (except 40/F). The thickness of the floor slab (excluding plaster) of each residential property on 40/F is 200mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

B 座 1樓平面圖
Block B 1/F Floor Plan





比例尺 SCALE: 0 5(米) (m)

圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	簷篷/平台	Canopy/Flat Roof
	罩屋	Dog House

1. 每個住宅物業的層與層之間的高度為2.75米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)

註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

B 座 1樓平面圖
Block B 1/F Floor Plan



圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	簷篷/平台	Canopy/Flat Roof
	罩屋	Dog House

1. 每個住宅物業的層與層之間的高度為2.75米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)

註：平面圖所列之數字為以毫米標示之建築結構尺寸。


1. The floor-to-floor height of each residential property is 2.75m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

B 座 2樓平面圖
Block B 2/F Floor Plan



比例尺SCALE: 0 5(米) (m)



圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room


1. 每個住宅物業的層與層之間的高度為2.75米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)


註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

B 座 2樓平面圖
Block B 2/F Floor Plan





圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room

1. 每個住宅物業的層與層之間的高度為2.75米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)


註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

B 座 3樓-40樓平面圖
Block B 3/F-40/F Floor Plan





圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room


1. 每個住宅物業的層與層之間的高度為2.75米(40樓除外)。40樓每個住宅物業的層與層之間的高度為2.80米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米(40樓除外)。40樓每個住宅物業的樓板(不包括灰泥)的厚度為200毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)


註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m (except 40/F). The floor-to-floor height of each residential property on 40/F is 2.80m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm (except 40/F). The thickness of the floor slab (excluding plaster) of each residential property on 40/F is 200mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)


Note: The dimensions on the floor plan are all structural dimensions in millimetre.


B 座 3樓-40樓平面圖
Block B 3/F-40/F Floor Plan





3樓部分平面圖
PART PLAN AT 3/F





圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	簷篷/平台	Canopy/Flat Roof
	罩屋	Dog House

1. 每個住宅物業的層與層之間的高度為2.75米(40樓除外)。40樓每個住宅物業的層與層之間的高度為2.80米。
2. 每個住宅物業的樓板(不包括灰泥)的厚度為160毫米及215毫米(40樓除外)。40樓每個住宅物業的樓板(不包括灰泥)的厚度為200毫米。
3. 因住宅物業的較高樓層的結構牆的厚度遞減，較高樓層的內部面積，一般比較低樓層的內部面積稍大。(不適用於該發展項目)

註：平面圖所列之數字為以毫米標示之建築結構尺寸。

1. The floor-to-floor height of each residential property is 2.75m (except 40/F). The floor-to-floor height of each residential property on 40/F is 2.80m.
2. The thicknesses of the floor slabs (excluding plaster) of each residential property are 160mm and 215mm (except 40/F). The thickness of the floor slab (excluding plaster) of each residential property on 40/F is 200mm.
3. The internal areas of the residential properties on the upper floors will generally be slightly larger than those on the lower floors because of the reducing thickness of the structural walls on the upper floors. (Not applicable to the Development)

Note: The dimensions on the floor plan are all structural dimensions in millimetre.

12 發展項目中的住宅物業的面積
Area of Residential Properties in the Development

物業的描述 Description of Residential Property			實用面積(包括露台、工作平台及陽台(如有))平方米(平方呎) Saleable Area (including balcony, utility platform and verandah, if any) sq.m. (sq.ft.)	其他指明項目的面積(不計算入實用面積)平方米(平方呎) Area of other specified items (Not included in the Saleable Area) sq.m. (sq.ft.)									
大廈名稱 Block Name	樓層 Floor	單位 Unit		空調機房 Air-conditioning plant room	窗台 Bay window	閣樓 Cockloft	平台 Flat roof	花園 Garden	停車位 Parking space	天台 Roof	梯屋 Stairhood	前庭 Terrace	庭院 Yard
A座 Block A	1樓 – 40樓 1/F – 40/F	1, 16, 19	26.3 (283) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		2, 3, 14, 15	25.9 (279) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		4, 13	35.3 (380) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		5	36.9 (397) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		6, 18	36.6 (394) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		7, 10	26.6 (286) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		8, 9	17.5 (188) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		11	36.1 (389) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–

上述每個住宅物業的實用面積是按照《一手住宅物業銷售條例》第8條計算得出。

The saleable area of each residential property listed above is calculated in accordance with section 8 of the Residential Properties (First-hand Sales) Ordinance.

註： 上述以平方呎列明之面積是以1平方米=10.764平方呎換算，並四捨五入至整數平方呎。

Note: The areas as specified above in square feet are converted at a rate of 1 square metre = 10.764 square feet and rounded to the nearest whole square foot.

物業的描述 Description of Residential Property			實用面積(包括露台、工作平台及陽台(如有)) 平方米(平方呎) Saleable Area (including balcony, utility platform and verandah, if any) sq.m. (sq.ft.)	其他指明項目的面積(不計算入實用面積) 平方米(平方呎) Area of other specified items (Not included in the Saleable Area) sq.m. (sq.ft.)									
大廈名稱 Block Name	樓層 Floor	單位 Unit		空調機房 Air-conditioning plant room	窗台 Bay window	閣樓 Cockloft	平台 Flat roof	花園 Garden	停車位 Parking space	天台 Roof	梯屋 Stairhood	前庭 Terrace	庭院 Yard
A座 Block A	1樓 – 40樓 1/F – 40/F	12	43.3 (466) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		17	37.0 (398) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		20, 28, 33, 34	17.4 (187) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		21, 27	17.6 (189) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		22, 26, 29, 32, 35	26.4 (284) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		23	36.8 (396) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		24	37.2 (400) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		25, 30, 31, 36	42.6 (459) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–

上述每個住宅物業的實用面積是按照《一手住宅物業銷售條例》第8條計算得出。
The saleable area of each residential property listed above is calculated in accordance with section 8 of the Residential Properties (First-hand Sales) Ordinance.

註： 上述以平方呎列明之面積是以1平方米=10.764平方呎換算，並四捨五入至整數平方呎。
Note: The areas as specified above in square feet are converted at a rate of 1 square metre = 10.764 square feet and rounded to the nearest whole square foot.

發展項目中的住宅物業的面積
Area of Residential Properties in the Development

物業的描述 Description of Residential Property			實用面積(包括露台、工作平台及陽台(如有))平方米(平方呎) Saleable Area (including balcony, utility platform and verandah, if any) sq.m. (sq.ft.)	其他指明項目的面積(不計算入實用面積) 平方米(平方呎) Area of other specified items (Not included in the Saleable Area) sq.m. (sq.ft.)									
大廈名稱 Block Name	樓層 Floor	單位 Unit		空調機房 Air-conditioning plant room	窗台 Bay window	閣樓 Cockloft	平台 Flat roof	花園 Garden	停車位 Parking space	天台 Roof	梯屋 Stairhood	前庭 Terrace	庭院 Yard
B座 Block B	1樓 – 40樓 1/F – 40/F	1	27.5 (296) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		2	35.9 (386) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		3, 6, 26, 29, 32, 35	26.4 (284) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		4, 5, 27, 28, 33, 34	17.4 (187) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		7	42.3 (455) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		8	27.1 (292) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		9, 24	26.3 (283) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		10, 11, 22, 23	25.9 (279) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		12, 21	35.3 (380) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–

上述每個住宅物業的實用面積是按照《一手住宅物業銷售條例》第8條計算得出。

The saleable area of each residential property listed above is calculated in accordance with section 8 of the Residential Properties (First-hand Sales) Ordinance.

註： 上述以平方呎列明之面積是以1平方米=10.764平方呎換算，並四捨五入至整數平方呎。

Note: The areas as specified above in square feet are converted at a rate of 1 square metre = 10.764 square feet and rounded to the nearest whole square foot.

物業的描述 Description of Residential Property			實用面積(包括露台、工作平台及陽台(如有))平方米(平方呎) Saleable Area (including balcony, utility platform and verandah, if any) sq.m. (sq.ft.)	其他指明項目的面積(不計算入實用面積)平方米(平方呎) Area of other specified items (Not included in the Saleable Area) sq.m. (sq.ft.)									
大廈名稱 Block Name	樓層 Floor	單位 Unit		空調機房 Air-conditioning plant room	窗台 Bay window	閣樓 Cockloft	平台 Flat roof	花園 Garden	停車位 Parking space	天台 Roof	梯屋 Stairhood	前庭 Terrace	庭院 Yard
B座 Block B	1樓 – 40樓 1/F – 40/F	20	36.9 (397) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		25, 30, 31, 36	42.6 (459) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
	1樓 – 2樓 1/F – 2/F	13	43.8 (471) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
	3樓 – 40樓 3/F – 40/F	13	43.3 (466) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		14	36.1 (389) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		15, 18	26.6 (286) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		16, 17	17.5 (188) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–
		19	36.6 (394) 露台 Balcony: – 工作平台 Utility Platform: – 陽台 Verandah: –	–	–	–	–	–	–	–	–	–	–


上述每個住宅物業的實用面積是按照《一手住宅物業銷售條例》第8條計算得出。
The saleable area of each residential property listed above is calculated in accordance with section 8 of the Residential Properties (First-hand Sales) Ordinance.

註： 上述以平方呎列明之面積是以1平方米=10.764平方呎換算，並四捨五入至整數平方呎。
Note: The areas as specified above in square feet are converted at a rate of 1 square metre = 10.764 square feet and rounded to the nearest whole square foot.


13 發展項目中的停車位的樓面平面圖

Floor Plan of Parking Spaces in the Development

地下停車位平面圖
Floor Plan of Parking Spaces on Ground Floor



地下低層1樓停車位平面圖
Floor Plan of Parking Spaces on Lower Ground Floor 1



指示圖 KEY PLAN



發展項目中的停車位的樓面平面圖
Floor Plan of Parking Spaces in the Development

圖例 NOTATION

——·——·——	地界	Lot Boundary
P	花槽	Planter

停車位類別 Category of Parking Space		數目 Number	每個停車位的尺寸(長x寬)(米) Dimensions of Each Parking Space (L x W)(m.)	每個停車位的面積(平方米) Area of Each Parking Space (sq.m.)
	露天汽車停車位 Open Car Parking Spaces	16	5.0 X 2.5	12.50
	有蓋汽車停車位 Covered Car Parking Spaces	101	5.0 X 2.5	12.50
	有蓋汽車停車位(暢通易達停車位) Covered Car Parking Spaces (Accessible Parking Spaces)	3	5.0 X 3.5	17.50
	有蓋電單車停車位 Covered Motorcycle Parking Spaces	40	2.4 X 1.0	2.40
	露天輕型貨車停車位 Open Light Goods Vehicles Parking Spaces	12	7.0 X 3.5	24.50
	露天上落客貨停車位 Open Parking, Loading / Unloading Spaces	4	11.0 X 3.5	38.50
	露天上落客貨停車位(特殊幼兒中心及嚴重肢體傷殘人士綜合支援服務中心) Open Parking, Loading / Unloading Spaces (Special Child Care Centre and Integrated Support Service Centre for Persons with Severe Physical Disabilities)	2	8.0 X 3.0	24.00
	有蓋垃圾車專用車位 Covered Loading / Unloading Space Reserved for Refuse Collection Vehicle	1	12.0 x 5.0	60.00

14 臨時買賣合約的摘要

Summary of Preliminary Agreement for Sale and Purchase

不適用　Not applicable

15 公契的摘要
Summary of Deed of Mutual Covenant

處理以下各項的條文的摘要：

除在售樓説明書另有定義外，下述用詞的意義將等同於「公契」內該用詞的意義。請參閱「公契」。

A 發展項目的公用部分

「公用地方與設施」指全部或任何一項（視乎上下文意而定）：(i)「屋苑公用地方與設施」；(ii)「住宅大廈公用地方與設施」；及(iii)所有根據「公契」或「副公契」（如有者）之條款指定為公用地方與設施的「屋苑」的部分與其設施。如情況適用，所有「公用地方與設施」均包括《建築物管理條例》（第344章）附表1指定的恰當及相關公用部分。

「屋苑公用地方與設施」指擬供「屋苑」整體而非其中任何個別部分公用與共享的「該土地」及「屋苑」的地方、系統、裝置與設施，包括但不限於「該租契」條款第3.17(a)條所指的露天空間（構成「住宅大廈公用地方與設施」之部分除外）、「該租契」條款第3.18條所指的園景區（構成「住宅大廈公用地方與設施」之部分除外）、外牆（構成「住宅大廈公用地方與設施」之部分及構成「房屋委員會樓宇」之部分除外）（為免存疑，外牆包括「政府房舍」的外牆及位於「低層地下樓層」的外牆）、柵欄、主車輛入口、車輛入口、有蓋自動梯、綠化天台、「綠化區域」（構成「住宅大廈公用地方與設施」之部分除外）、車輛通道/緊急車輛通道、緊急車輛通道、有蓋園景區、簷篷下的有蓋區域、氣體調壓室、花灑泵房、維修用走廊、走廊、電訊及廣播設備室、電錶房、食水及沖廁水水缸及泵房、檢測儀錶櫃、升降機大堂、升降機、升降機槽、樓梯、消防泵房、消防水缸、發電機房、總電掣房、電纜管道房、煤氣總掣房、消防入水掣、管道槽、管道槽房、花灑控制閥及花灑入水掣、總水錶房、變壓器房、花灑入水掣及消防入水掣、花灑控制閥、技工工場、潔淨服務承辦商辦事處、儲物室、吊機房、水錶櫃、屋苑管理處、業主立案法團辦事處、消防檢測儀錶櫃、街道消防栓水缸、食水水缸、平台、沖廁水水缸、垃圾及物料回收房、垃圾車專用停車位、垃圾收集站、物料回收房、應急發電機房、花槽、控制閥、有蓋行人通道、有蓋行人通道及樓梯的上蓋、有蓋行人通道及自動梯的上蓋、綠化斜坡、斜坡、「該等項目」以及在「屋苑」內提供或安裝並擬為「屋苑」整體而

Summary of Provisions that Deal with the Following Matters:

Unless otherwise defined in this sales brochure, capitalised and other terms used in the following shall have the same meaning of such terms used in the Deed of Mutual Covenant ("DMC"). Please refer to the DMC for reference.

A The Common Parts of the Development

"Common Areas and Facilities" shall mean (as the context may require) all or any of (i) the Estate Common Areas and Facilities; (ii) the Residential Blocks Common Areas and Facilities and (iii) all those parts and such of the facilities of the Estate designated as common areas and facilities in accordance with the provisions of the DMC or Sub-DMC (if any), each of which Common Areas and Facilities shall, where applicable, include those appropriate and relevant common parts specified in Schedule 1 to the Building Management Ordinance (Cap.344).

"Estate Common Areas and Facilities" shall mean the areas, systems, devices and facilities of the said land and the Estate intended for the common use and benefit of the Estate as a whole and not just any particular part thereof, and shall include, but not limited to, the open space referred to in Clause 3.17(a) of the said lease (other than open space forming part of the Residential Blocks Common Areas and Facilities), landscaped areas referred to in Clause 3.18 of the said lease (other than those forming part of the Residential Blocks Common Areas and Facilities), external walls (other than those forming part of the Residential Blocks Common Areas and Facilities and those forming part of the HA Accommodation) (for the avoidance of doubt, external walls include the external walls of the Government Accommodation and the external walls located on Lower Ground Levels), drop gate, main vehicular entrance, vehicular entrance, covered escalator, green roof, the Greenery Area (excluding those forming part of the Residential Blocks Common Areas and Facilities), vehicular access/emergency vehicular access, emergency vehicular access, covered landscaped areas, covered area(s) under canopy above, gas kiosk, sprinkler pump room, service corridors, corridors, telecommunications and broadcasting equipment rooms, electrical meter rooms, fresh & flush water tank & pump rooms, check meter cabinets, lift lobbies, lifts, lift shafts, staircases, fire services pump rooms, fire services water tanks, generator rooms, main switch rooms, cable duct rooms, gas compartment room, fire services inlets, pipe ducts, pipe duct rooms, sprinkler control valve & sprinkler inlet, master water meter room, transformer room, sprinkler inlets & fire service inlets, sprinkler control valves, artisans' workshop, cleansing contractor's office, store room, hoist room, water meter cupboards, estate management office, owners' corporation office, fire services check meter cabinets, street fire hydrant water tanks, fresh water tanks, flat roofs, flush water tanks, refuse storage & material recovery chambers, loading and unloading space reserved for refuse collection vehicle, refuse collection point, material recovery chamber, emergency generator rooms, planters, control valve, Covered Walkway, roof of covered walkway and staircase, roof of covered walkway and escalator, green slopes, slopes, the Items and such other areas and any other systems, devices and

非其中任何個別部分提供服務的其他地方與任何其他系統、裝置與設施，即現於「公契」所夾附圖則以橙色、橙色加黑交叉斜線、橙色加黑斜線及紅色顯示（只要該等地方、系統、裝置及設施可在圖則辨識）以資識別的範圍，以及香港房屋委員會（下稱「房委會」）可隨時按照「公契」及任何「副公契」（如有）之條款指定為「屋苑公用地方與設施」並且擬供「屋苑」整體而非其中任何個別部分公用與共享的「該土地」及「屋苑」的附加地方、系統、裝置及設施，但（「公契」另有明文定義及規定者除外）不包括「住宅大廈公用地方與設施」、屬於任何公用事業公司及電訊及廣播服務供應商的裝置和「屋苑」內由個別「業主」擁有獨有和專有權持有、使用、佔用與享用的地方和「屋苑」內只為任何個別「業主」提供服務的設施。

「住宅大廈公用地方與設施」指及包括但不限於附屬於「住宅大廈」的外牆（包括突出物如混凝土蓬頂）、繫樑、支撐牆的構件和外部、樑、柱、平台、「住宅大廈」的天台、上層天台及頂層天台、護牆、簷篷、入口大堂、升降機大堂、升降機、升降機槽、走廊、樓梯、花槽、「該租契」條款第3.17(a)條所指的露天空間（構成「屋苑公用地方與設施」之部分除外）、「該租契」條款第3.18條所指的園景區（構成「屋苑公用地方與設施」之部分除外）、上落客貨停車位、兒童遊樂場/遊樂區、羽毛球場、行人入口、管道槽、管道槽房、總電掣房、水錶櫃、電訊及廣播設備室、特低壓機房、變壓器房、保安員櫃位、洗手間、有蓋園景區、簷篷之下的有蓋區域、罩屋、電訊及特低壓機房、電錶房、消防喉轆、食水增壓泵房、電纜管道房、通風管道房、升降機機房、防風板、廢物收集站、隔聲鰭、建築鰭片、到達不到的空隙、供水務署(WSD)及渠務署(DSD)使用的維修車輛入口、垃圾及物料回收室、「綠化區域」（構成「屋苑公用地方與設施」之部分除外）以及在「住宅大廈」內提供或安裝並擬為「住宅大廈」整體提供服務的任何其他地方、系統、裝置與設施，即現於「公契」所夾附圖則以啡色、啡色加黑斜線、啡色加黑交叉斜線及黃色顯示（只要該等地方、系統、裝置及設施可辨識）以資識別的範圍，以及「房委會」可隨時按照「公契」及任何「副公契」（如有）指定為「住宅大廈公用地方與設施」的附加地方、系統、裝置與設施（在「訪客停車位」根據「公契」的規定被指定為額外的「住宅大廈公用地方與設施」之後，亦包括「訪客停車位」），但（「公契」另有明文

facilities provided or installed in the Estate and intended to serve the Estate as a whole and not just any particular part thereof which, for identification purpose only, are shown coloured orange, orange cross hatched black, orange hatched black and red (insofar as such areas, systems, devices and facilities are identifiable on such plans) on the plans annexed to the DMC and such additional areas, systems, devices and facilities of the said land and the Estate intended for the common use and benefit of the Estate as a whole and not just any particular part thereof as may at any time be designated as Estate Common Areas and Facilities by the Hong Kong Housing Authority (hereinafter referred to as "HA") in accordance with the provisions of the DMC and any Sub-DMC (if any) but (unless otherwise expressly defined and provided under the DMC) shall exclude the Residential Blocks Common Areas and Facilities, those installations belonging to any Utility Company and telecommunications and broadcasting services providers and such areas within the Estate in respect of which the exclusive right and privilege to hold, use, occupy and enjoy the same belongs to any particular Owner and such facilities within the Estate serving only any particular Owner.

"Residential Block Common Areas and Facilities" shall mean and include, but not limited to, the external walls pertaining to the Residential Blocks including projections such as concrete hoods, tie beams, the structures and exteriors of the supporting walls, beams, columns, flat roofs, roofs, upper roofs and top roofs of the Residential Blocks, parapet walls, canopies, entrance lobbies, lift lobbies, lifts, lift shafts, corridors, staircases, planters, open space referred to in Clause 3.17(a) of the said lease (other than open space forming part of the Estate Common Areas and Facilities), landscaped area(s) referred to in Clause 3.18 of the said lease (other than those forming part of the Estate Common Areas and Facilities), Parking, Loading and Unloading Spaces, children's playground/play area, badminton court, pedestrian entrances, pipe ducts, pipe duct room, main switch rooms, water meter cupboards, telecommunications and broadcasting equipment room, extra low voltage room, transformer rooms, guard counters, toilets, covered landscaped areas, covered area(s) under canopy above, dog houses, telecom & extra low voltage rooms, electrical meter rooms, hose reel, fresh water booster pump rooms, cable duct rooms, vent duct rooms, lift machine rooms, typhoon guards, junk collection point, acoustic fins, architectural fins, inaccessible voids, maintenance vehicular entrance for Water Supplies Department (WSD) & Drainage Services Department (DSD), refuse storage & material recovery rooms, and the Greenery Area (excluding those forming part of the Estate Common Areas and Facilities) and any other areas, systems, devices and facilities provided or installed in the Residential Blocks and intended to serve the Residential Blocks as a whole, which for identification purpose only, are shown coloured brown, brown hatched black, brown cross hatched black and yellow (insofar as such areas, systems, devices and facilities are identifiable) on the plans annexed to the DMC and such additional areas, systems, devices and facilities as may at any time be designated as the Residential Blocks Common Areas and Facilities by the HA (including the Visitors' Car Parking Spaces after the designation of the Visitors' Car Parking Spaces as additional Residential Blocks Common Areas and Facilities in accordance with the provisions of the DMC) in accordance with the DMC and any Sub-DMC (if any) but

定義及規定者除外）並不包括「屋苑公用地方與設施」、屬於任何公用事業公司及電訊及廣播服務供應商的裝置和「住宅大廈」內由個別「業主」擁有獨有和專有權持有、使用、佔用與享用的地方，以及「住宅大廈」內只為個別「業主」提供服務的設施。

B 分配予發展項目中的每個住宅物業的不分割份數的數目

(unless otherwise expressly defined and provided under the DMC) shall exclude the Estate Common Areas and Facilities, those installations belonging to any Utility Company and telecommunications and broadcasting services providers and such areas within any part of the Residential Blocks in respect of which the exclusive right and privilege to hold, use, occupy and enjoy the same belongs to any particular Owner and such facilities within any part of the Residential Blocks serving only any particular Owner.

B The Number of Undivided Shares Assigned to Each Residential Property in the Development

座數 Block	樓層 Floor	單位 Unit	每一單位佔整體業權之不分割份數 Undivided Shares for Each Unit
A	1樓 – 40樓 1/F – 40/F	1, 7, 10, 16, 19, 22, 26, 29, 32, 35	41 / 140,074
		2, 3, 14, 15	40 / 140,074
		4, 13	55 / 140,074
		17, 24	58 / 140,074
		5, 6, 18, 23	57 / 140,074
		8, 9, 20, 21, 27, 28, 33, 34	27 / 140,074
		11	56 / 140,074
		12	68 / 140,074
		25, 30, 31, 36	66 / 140,074
B	1樓 – 40樓 1/F – 40/F	1	43 / 140,074
		2	56 / 140,074
		3, 6, 9, 24, 26, 29, 32, 35	41 / 140,074
		4, 5, 27, 28, 33, 34	27 / 140,074
		7, 25, 30, 31, 36	66 / 140,074
		8	42 / 140,074
		10, 11, 22, 23	40 / 140,074
		12, 21	55 / 140,074
		13	68 / 140,074
		20	57 / 140,074
	3樓 – 40樓 3/F – 40/F	14	56 / 140,074
		15, 18	41 / 140,074
		16, 17	27 / 140,074
		19	57 / 140,074

C 發展項目的管理人的委任年期

除《建築物管理條例》(第344章)另有規定,「房委會」應負責「該土地」及「屋苑」之管理,首屆任期為「公契」生效日起計二十四(24)個曆月或直至「業主立案法團」成立為止(以較早者為準)及必須繼續擔任「經理人」,直至「房委會」的任命按照「公契」的條文終止為止。

D 發展項目中的住宅物業的擁有人之間分擔管理開支的基準

(1) 每名「業主」均須繳付「經理人」釐定的月費,以分擔管理「屋苑」所招致的必要及合理費用、收費及開支,攤付金額乃根據每名「業主」以專有權持有、使用、佔用和享用的「屋苑」部分之「管理份數」按比例計算,並由「經理人」根據「公契」條文制訂的周年財政預算訂定。

C The Term of Years for which the Manager of the Development is Appointed

Subject to the provisions of the Building Management Ordinance (Cap. 344), HA shall undertake the management of the said land and the Estate for an initial term expiring 24 calendar months from the date of the DMC or until an Owners' Corporation is formed, whichever is the earlier, and shall continue to be the Manager for such further period until the termination of HA's appointment in accordance with the provisions of the DMC.

D The Basis on which the Management Expenses are Shared Among the Owners of the Residential Properties in the Development

(1) Each of the Owners shall pay a monthly sum as determined by the Manager as being the due proportion of the costs, charges and expenses necessarily and reasonably incurred in the management of the Estate, in proportion to the number of Management Shares allocated to such part of the Estate of which he has the exclusive right to hold, use, occupy and enjoy. The amount of such monthly sum shall be determined by the Manager based on the annual budget made in accordance with the provisions of the DMC.

(2) 分配予發展項目中的每個住宅物業的「管理份數」的數目：

(2) The number of Management Shares allocated to each residential property in the Development is as follows:

座數 Block	樓層 Floor	單位 Unit	每一單位佔整體管理份數 Management Shares for Each Unit
A	1樓 – 40樓 1/F – 40/F	1, 7, 10, 16, 19, 22, 26, 29, 32, 35	41 / 140,064
		2, 3, 14, 15	40 / 140,064
		4, 13	55 / 140,064
		17, 24	58 / 140,064
		5, 6, 18, 23	57 / 140,064
		8, 9, 20, 21, 27, 28, 33, 34	27 / 140,064
		11	56 / 140,064
		12	68 / 140,064
		25, 30, 31, 36	66 / 140,064
B	1樓 – 40樓 1/F – 40/F	1	43 / 140,064
		2	56 / 140,064
		3, 6, 9, 24, 26, 29, 32, 35	41 / 140,064
		4, 5, 27, 28, 33, 34	27 / 140,064
		7, 25, 30, 31, 36	66 / 140,064
		8	42 / 140,064
		10, 11, 22, 23	40 / 140,064
		12, 21	55 / 140,064
		13	68 / 140,064
		20	57 / 140,064
	3樓 – 40樓 3/F – 40/F	14	56 / 140,064
		15, 18	41 / 140,064
		16, 17	27 / 140,064
		19	57 / 140,064

E 計算管理費按金的基準

每「單位」的「業主」均須向「經理人」繳付一筆管理費按金，金額不超過「經理人」不時就每個「單位」根據「公契」條文制訂的周年財政預算訂定的「業主」應繳的管理月費的三倍。

F 賣方在發展項目中保留作自用的範圍

不適用。

E The Basis on which the Management Fee Deposit is Fixed

The amount of management fee deposit is a sum not exceeding 3 times the monthly management fee payable by the Owner in respect of each Unit as may be determined from time to time by the Manager based on the annual budget made in accordance with the provisions of the DMC.

F The Area in the Development Retained by the Vendor for the Vendor's Own Use

Not applicable.

註： 請查閱「公契」全文以了解上述條款及「公契」中其他條款的全部詳情。獲批准「公契」的全文可於觀塘開源道33號建生廣場一樓內之綠置居銷售小組開放時間內免費查閱，並可於房委會就出售青富苑所指定的互聯網網站內閱覽。

Note : For full details of the above provisions and other provisions in the DMC, please refer to the DMC. Full script of the approved form of DMC is available for inspection free of charge during opening hours at the GSH Sales Unit on 1/F., Pioneer Place, 33 Hoi Yuen Road, Kwun Tong and is also available on the website designated by the HA for the sale of Ching Fu Court.

16 批地文件的摘要
Summary of Land Grant

位於青衣市地段第194號之香港房屋委員會（下稱「承租人」，如語意容許，亦包括其繼承人或受讓人）之發展項目的政府租契（下稱「該租契」）日期為2019年11月6日。

1. **該發展項目位於青衣市地段第194號(下稱「該土地」)。**

2. **「該土地」的批租年期為50年，由2019年11月6日起計（下稱「批租年期」)。**

3. **「該租契」條款第3.3條訂明：**

「承租人」須不時及在此後的所有時間在每當有需要或情況要求時妥善及足夠地自費管理、修理、維護、支持、保養、鋪設、清洗、刷淨、清潔、清空、改動及保持「該土地」及現有或其後任何時間位於「該土地」的樓宇或物業單位及所有其他架設物及建築物，所有「該土地」內的山坡上，擋土結構和護土牆，及所有屬於和以任何形式屬於或附屬於「該土地」或任何位於其上之樓宇、物業單位、架設物及建築物的牆、堤岸、路塹、籬笆、溝渠、路軌、電燈、行人道、水廁、洗滌槽、排水渠及水道，並且全面執行需要及必須的所有修葺、清洗及修改工程，一切必須達致令地政總署署長（下稱「署長」）滿意為止。

4. **「該租契」條款第3.7條訂明：**

「承租人」須在「批租年期」內每當有需要時承擔、支付及容許製造、建築、維修及修改「該土地」或其任何部分所需或在「該土地」內或屬於「該土地」並與其他附近或毗鄰的樓宇共用的所有或任何道路、巷道、行人道、溝渠、籬笆及公用牆、化糞池、私人或公共污水渠及排水渠的成本及費用的合理份數及部分。該份數及部分將由「署長」指定及決定（其決定為最終決定及對「承租人」具約束力）及將由「署長」以未付之地租形式徵收。

5. **「該租契」條款第3.13條訂明：**

除「該租契」的條款及契諾另有規定外，「承租人」不得使用或准許或容許他人使用「該土地」或其任何部分或任何已建或擬建於「該土地」的建築物或其任何部分作私人住宅及「該租契」條款第3.14(d)條和第3.14(e)條所述的該等樓宇及

The government lease governing the Development entered into by The Hong Kong Housing Authority ("the Lessee" which expression shall where the context so admits include its successors and assigns) in respect of Tsing Yi Town Lot No.194 ("the said lease") is dated the 6th day of November 2019.

1. **The Development is situated on Tsing Yi Town Lot No.194 ("the said land").**

2. **The said land is granted for a term of 50 years commencing from the 6th day of November 2019 ("Lease Term").**

3. **Clause No. 3.3 of the said lease stipulates that:**

The Lessee shall from time to time and at all times after the date of the said lease, when where and as often as need or occasion shall require, at the Lessee's own proper costs and charges well and sufficiently manage, repair, uphold, support, maintain, pave, purge, scour, cleanse, empty, amend and keep the said land and the messuage or tenement, messuages or tenements and all other erections and buildings now or which may at any time after the date of the said lease be standing upon the said land, all the slopes, earth-retaining structures and retaining walls within the said land and all the walls, banks, cuttings, hedges, ditches, rails, lights, pavements, privies, sinks, drains and watercourses thereunto belonging and which shall in any-wise belong or appertain unto the said land or any of the said messuages, tenements, erections and buildings in, by and with all and all manner of needful and necessary reparations, cleansings and amendments whatsoever the whole to be done to the satisfaction of the Director of Lands ("the Director").

4. **Clause No. 3.7 of the said lease stipulates that:**

The Lessee shall during the Lease Term as often as need shall require bear, pay and allow a reasonable share and proportion for and towards the costs and charges of making, building, repairing and amending all or any roads, lanes, pavements, channels, fences and party walls, cesspools, private or public sewers and drains requisite for or in or belonging to the said land or any part thereof in common with other premises near or adjoining thereto. Such share and proportion shall be fixed and determined by the Director (whose determination shall be final and binding on the Lessee) and shall be recoverable by the Director in the nature of rent in arrears.

5. **Clause No. 3.13 of the said lease stipulates that:**

Subject to the terms and covenants contained in the said lease, the Lessee shall not use or permit or suffer to be used the said land or any part thereof or any building or buildings erected or to be erected thereon or any part of such building or buildings for any purpose other than for private residential

其他設施，以及「該租契」所述的附屬設施以外的用途。特此說明，已建或擬建於「該土地」的建築物內的任何住宅單位不得用作私人住宅用途以外的任何其他用途。

6 **「該租契」條款第3.15條訂明：**

「承租人」須自費以令「署長」及食物環境衞生署署長滿意的方式於「該土地」建築、提供及維持完整的垃圾收集系統。

7 **「該租契」條款第3.16條訂明：**

「承租人」未經「署長」事先書面同意，不得移除或干擾生長於「該土地」或相鄰範圍的樹木。「署長」發出有關書面同意時，可在其認為合適的情況下，施加有關移植、補償性環境美化工程或種植的條件。

8 **「該租契」條款第3.17條訂明：**

(a) 「承租人」須在「該土地」內以令「署長」滿意的方式，自費提供及維持面積不少於6,945平方米的休憩空間，且不得使用、准許或容許他人使用「休憩空間」作供「該土地」已建或擬建的建築物的住客及佔用人及其真正賓客和訪客使用及享用的動態及靜態康樂用途以外的任何其他用途。「署長」就何謂休憩空間作出的決定為最終決定，並對「承租人」具約束力。

(b) 根據「該租契」條款第3.17(a)條提供的休憩空間，須被指定為「該租契」條款第3.22(a)(vi)條所指的「公用地方」並成為其中一部分。

9 **「該租契」條款第3.18條訂明：**

「承租人」須在「該土地」或平台（如有）未有建築之任何部分，自費進行環境美化工程及種植樹木和灌木，其後須以令「署長」滿意的方式保養及使其維持在安全、潔淨、整齊、井然而健壯的狀態。

purposes together with such accommodations and other facilities as referred to in Clauses Nos. 3.14(d) and 3.14(e) of the said lease and ancillary facilities as referred to in the said lease and in particular, any residential flats in the building or buildings erected or to be erected on the said land shall not be used for any purpose other than for private residential purposes.

6 **Clause No. 3.15 of the said lease stipulates that:**

The Lessee shall at its own expense and to the satisfaction of the Director and the Director of Food and Environmental Hygiene construct, provide and maintain within the said land a comprehensive system of refuse collection.

7 **Clause No. 3.16 of the said lease stipulates that:**

No tree growing on the said land or adjacent thereto shall be removed or interfered with without the prior written consent of the Director who may, in granting consent, impose such conditions as to transplanting, compensatory landscaping or replanting as he may deem appropriate.

8 **Clause No. 3.17 of the said lease stipulates that:**

(a) The Lessee shall at its own expense provide and maintain within the said land to the satisfaction of the Director open space of not less than 6,945 square metres in area and shall not use, permit or suffer to be used the said open space for any purpose other than for active and passive recreational purposes for the use and enjoyment by the residents and occupiers of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors. The decision of the Director as to what constitutes open space shall be final and binding on the Lessee.

(b) The open space provided in accordance with the Clause No. 3.17(a) of the said lease shall be designated as and form part of the Common Areas referred to in Clause No. 3.22(a)(vi) of the said lease.

9 **Clause No. 3.18 of the said lease stipulates that:**

The Lessee shall at its own expense landscape and plant with trees and shrubs any portion of the said land and podium (if any) not built upon and thereafter maintain and keep the same in a safe, clean, neat, tidy and healthy condition all to the satisfaction of the Director.

10 「該租契」條款第3.20條訂明：

(a) 除於「該租契」條款第3.20(b)條、第3.20(c)條及第3.20(d)條另有規定外，「業主」無論何時均不得出售、轉讓、讓與、轉易、按揭、押記、批租、分租、放棄管有或以其他方式處置其「住宅單位」或其任何部分或其中的任何權益（無論是以直接或間接保留、授予任何優先拒絕要約權、選擇權或授權書的方式或是以任何其他方法、安排或任何形式的文件）或就此等目的訂立任何協議。

(b) 「業主」可無須事先向「承租人」繳付「補價」，將轉讓予他的「住宅單位」按揭或押記，惟前提是必須獲得房屋署署長的事先書面批准，而房屋署署長在授予該批准時可施加他認為合適的條款及條件，包括（除其他外）繳付行政費（如被要求時）及該按揭或押記須符合房屋署署長批准的格式並載有房屋署署長要求的條文。

(c) 「業主」無須事先向「承租人」繳付「補價」而有權就其「住宅單位」訂立任何臨時買賣協議、買賣協議及轉讓契據，惟前提是：

(i) 以買方身份訂立該臨時買賣協議的人士為「合資格買方」；

(ii) 以買方身份訂立買賣協議及轉讓契據的人士為「承租人」以其獨有及絕對酌情權提名購買該「住宅單位」的人士；

(iii) 已遵從及遵守「承租人」以其獨有及絕對酌情權施加的所有要求、條款及條件（包括繳付行政費（如被要求時））；

(iv) 每份根據「該租契」條款第3.20(c)條規定訂立的臨時買賣協議、買賣協議及轉讓契據須載有並受制於「承租人」以其獨有及絕對酌情權要求或授權的條款及條件，並須受「該租契」條款第3.20條所載的條款及條件限制；以及

(v) 倘若「業主」於「首次轉讓契據」日期起計兩年期間屆滿前訂立臨時買賣協議，則臨時買賣協議、買賣協議及轉讓契據中所訂立的售價不得多於「買價」。

10 Clause No. 3.20 of the said lease stipulates that:

(a) Except as provided in Clauses Nos. 3.20(b), 3.20(c) and 3.20(d) of the said lease, no owner shall at any time, sell, assign, alienate, convey, mortgage, charge, demise, underlet, part with possession of or otherwise dispose of his residential flat or any part thereof or any interest therein (whether by way of direct or indirect reservation, the grant of any right of first refusal, option or power of attorney, or any other method, arrangement or document of any description) or enter into any agreement so to do.

(b) An owner may, without first making payment of the Premium to the Lessee, mortgage or charge the residential flat assigned to him provided that the prior written approval of the Director of Housing shall be obtained who may, in granting such approval, impose such terms and conditions as he sees fit including, inter alia, payment of an administrative fee (if required) and that the mortgage or charge shall be in a form approved by the Director of Housing and shall contain such provisions as the Director of Housing may require.

(c) An owner shall be entitled to enter into any provisional agreement for sale and purchase, agreement for sale and purchase and assignment of his residential flat without first making payment of the Premium to the Lessee provided that:

(i) the person entering into the provisional agreement for sale and purchase as the purchaser is an eligible purchaser;

(ii) the person entering into the agreement for sale and purchase and the assignment as the purchaser is a person nominated by the Lessee in his sole and absolute discretion to buy such residential flat;

(iii) all requirements, terms and conditions (including the payment of administrative fees, if required) as may be imposed by the Lessee in his sole and absolute discretion are observed and complied with;

(iv) the provisional agreement for sale and purchase, agreement for sale and purchase and assignment entered into pursuant to the provisions of Clause No. 3.20(c) of the said lease shall each be subject to and contain such terms and conditions as may be required or authorized by the Lessee in his sole and absolute discretion and shall each be made subject to the terms and conditions contained in Clause No. 3.20 of the said lease; and

(v) in the event of the owner entering into the provisional agreement for sale and purchase before the expiry of two years from the date of the First Assignment, the sale price under the provisional agreement for sale and purchase, the agreement for sale and purchase and the assignment shall be at a price not more than the Purchase Price.

(d) 於「期間」屆滿後，

(i) 「業主」有權出售、轉讓、讓與、轉易、按揭、押記、批租、分租、放棄管有或以其認為適合的其他方式處置其「住宅單位」，惟前提是須向「承租人」繳付「補價」以及向房屋署署長繳付用作釐定「補價」的行政費（如被要求時）；以及

(ii) 在向「承租人」繳付「補價」前，「業主」可就其「住宅單位」訂立買賣協議，惟前提是該協議的條件須規定於轉讓「住宅單位」前及於該協議訂立日期的28日之內或房屋署署長可另行以書面批准的延長限期內向「承租人」繳付「補價」。

(e) 儘管「該租契」條款第3.20(a)條有所規定，「業主」可無須事先向「承租人」繳付「補價」，但須在遵照「承租人」施加的條款及條件（包括但不限於繳付行政費（如被要求時））的情況下，將其「住宅單位」或其中的任何權益轉讓予由「承租人」以其獨有及絕對酌情權以書面批准的該名或該等人士，或就此目的訂立任何協議。

(f) 在「業主」根據「該租契」條款第3.20(d)條向「承租人」繳付「補價」後，「該租契」條款第3.20條將不再適用於該「業主」的「住宅單位」，並對該「業主」的「住宅單位」失去效力。

(g) 就「該租契」條款第3.20條而言：

(i) 「合資格買方」指獲得「承租人」核證為符合資格購買「住宅單位」或其中任何權益的人士；

(ii) 「首次轉讓契據」指「承租人」向該「住宅單位」的首位「業主」轉讓「住宅單位」的首份轉讓契據；

(iii) 「承租人」一詞不包括其受讓人；

(iv) 「最初市值」指在「首次轉讓契據」中指明的「住宅單位」的市值；

(v) 「業主」指獲「承租人」根據「該租契」條款第3.19(a)條轉讓或同意轉讓「該土地」的不分割份數連同在「該土地」已建或擬建的建築物內之「住宅單位」的獨有管有權的人士；而就「該租契」條款第3.20條而言，包括其業權繼承人及「住宅單位」的承按人或承押記人；

(d) After the expiry of the Period,

(i) an owner shall be entitled to sell, assign, alienate, convey, mortgage, charge, demise, underlet, part with possession of or otherwise dispose of his residential flat as he sees fit subject to the payment of the Premium to the Lessee together with an administrative fee payable to the Director of Housing for determination of the Premium (if required); and

(ii) an owner may enter into an agreement for sale and purchase of his residential flat prior to the payment of the Premium to the Lessee provided that it is a condition of such agreement that the Premium shall be paid to the Lessee prior to the assignment of the residential flat and within 28 days of the date of the agreement or within such extended period as may otherwise be approved in writing by the Director of Housing.

(e) Notwithstanding Clause No. 3.20(a) of the said lease, an owner may, without first making payment of the Premium to the Lessee and in conformity with such terms and conditions as may be imposed by the Lessee (including but not limited to the payment of administrative fees, if required), assign his residential flat or any interest therein or enter into any agreement so to do to such person or persons as the Lessee may in its sole and absolute discretion approve in writing.

(f) Upon payment of the Premium by an owner to the Lessee in accordance with Clause No. 3.20(d) of the said lease, Clause No. 3.20 of the said lease shall no longer apply to and cease to have effect on the owner's residential flat.

(g) For the purposes of Clause No. 3.20 of the said lease:

(i) "eligible purchaser" means a person who has been certified by the Lessee to be eligible for the purchase of a residential flat or any interest therein;

(ii) "First Assignment" means the first assignment of a residential flat from the Lessee to the first owner of that residential flat;

(iii) the expression "Lessee" excludes its assigns;

(iv) "Initial Market Value" means the market value of the residential flat as specified in the First Assignment;

(v) "owner" means a person to whom the Lessee has assigned or agreed to assign an undivided share or undivided shares of and in the said land together with the right of exclusive possession of a residential flat in the building or buildings erected or to be erected on the said land under Clause No. 3.19(a) of the said lease; and for the purpose of Clause No. 3.20 of the said lease includes his successors-in-title and the mortgagee or chargee in respect of the residential flat;

(vi) 「期間」指「首次轉讓契據」的日期後起計的一段為期10年的期間；

(vii) 「補價」指由房屋署署長釐定的款額（其釐定為最終決定及對「住宅單位」的「業主」具約束力），該款額須根據以下公式計算 –

$$\text{「補價」} = \text{「現行市值」} \times \frac{(\text{「最初市值」} - \text{「買價」})}{\text{「最初市值」}}$$

就計算「補價」而言，「現行市值」指在「業主」繳付「補價」時由房屋署署長評估的「住宅單位」的市值；

(viii) 「買價」指於「首次轉讓契據」中指明之「承租人」向「業主」出售「住宅單位」的價錢；以及

(ix) 「住宅單位」指於「該土地」已建或擬建的建築物內並獲分配「該土地」的不分割份數的住宅單位。

(h) 儘管「該租契」條款第3.20(c)條、(e)條及(g)條有相反規定，「承租人」根據「該租契」條款第3.20條給予或作出任何批准、核證或提名或行使任何酌情權須受運輸及房屋局局長不時施加的條款及條件(如有)限制。

11 「該租契」條款第3.21(a)條及第3.21(i)條訂明：

(a) 除「該租契」條款第3.21(b)及3.21(c)條另有規定外，「承租人」須自費及以在所有方面使社會福利署署長滿意及良好的工作方式於「該土地」興建、建造、提供及保養由政府、機構及社區設施組成的以下項目：

(i) 一間總樓面面積為不少於390平方米的長者鄰舍中心；

(ii) 一間總樓面面積為不少於170平方米的嚴重肢體傷殘人士綜合支援服務中心及一個供根據《道路交通條例》及其下的規例及任何修訂法例獲發牌的汽車上落客貨及停泊用途的停車位。該停車位的尺寸最少須為3米寬及8米長而樓底高度最少須為3.3米；

(vi) "Period" means a period of 10 years after the date of the First Assignment;

(vii) "Premium" means an amount determined by the Director of Housing (whose determination shall be final and binding on the owner of the residential flat) which shall be calculated according to the following formula –

$$\text{Premium} = \text{Prevailing Market Value} \times \frac{(\text{Initial Market Value} - \text{Purchase Price})}{\text{Initial Market Value}}$$

whereas for the purpose of calculating the Premium, the Prevailing Market Value is the market value of the residential flat assessed by the Director of Housing as at the time when the owner pays the Premium;

(viii) "Purchase Price" means the price of the residential flat sold by the Lessee to the owner as specified in the First Assignment; and

(ix) "residential flat" means a residential flat in the building or buildings erected or to be erected on the said land and to which an undivided share or undivided shares of and in the said land has or have been allocated.

(h) Notwithstanding anything to the contrary contained in Clauses Nos. 3.20(c), (e) and (g) of the said lease, the giving or making of any approval, certification or nomination or the exercise of any discretion by the Lessee under Clause No. 3.20 of the said lease shall be subject to such terms and conditions (if any) as may be imposed from time to time by the Secretary for Transport and Housing.

11 Clauses Nos. 3.21(a) and 3.21(i) of the said lease stipulate that:

(a) Subject to Clauses Nos. 3.21(b) and 3.21(c) of the said lease, the Lessee shall at its own expense and in all respects to the satisfaction of the Director of Social Welfare erect, construct, provide and maintain on the said land in a good workmanlike manner government, institution and community facilities comprising:

(i) One neighbourhood elderly centre having a total gross floor area of not less than 390 square metres;

(ii) One integrated support service centre for persons with severe physical disabilities having a total gross floor area of not less than 170 square metres with one space for the parking, loading and unloading of a motor vehicle licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation. The said space shall have a minimum dimension of 3 metres in width and 8 metres in length with a minimum headroom of 3.3 metres;

(iii) 一間總樓面面積為不少於310平方米的特殊幼兒中心及一個供根據《道路交通條例》及其下的規例及任何修訂法例獲發牌的汽車上落客貨及停泊用途的停車位。該停車位的尺寸最少須為3米寬及8米長而樓底高度最少須為3.3米；以及

(iv) 一間總樓面面積為不少於330平方米的早期教育及訓練中心；

（該房舍（包括根據「該租契」條款第3.21(b)及3.21(c)條進行的更改、改動、加建、擴展或改善工程）連同其他由「署長」完全酌情決定（其決定為最終決定及對「承租人」具約束力）為該房舍專屬的任何地方、設施、服務設施及裝置，統稱「政府房舍」）。就「該租契」條款第3.21(a)條而言，如何構成一間長者鄰舍中心、嚴重肢體傷殘人士綜合支援服務中心、特殊幼兒中心及早期教育及訓練中心由社會福利署署長決定，其決定為最終決定及對「承租人」具約束力。根據「該租契」條款第3.21(a)(ii)條及第3.21(a)(iii)條提供的停車位須位於社會福利署署長以書面批准的位置及水平，並確保該設計和建造在所有方面能使社會福利署署長滿意。根據「該租契」條款第3.21(a)(ii)條及第3.21(a)(iii)條提供的停車位的總樓面面積須按照「該租契」條款第3.24(d)條計算。

(i) **(i)** 受限於「該租契」條款第3.22(a)(ii)(I)條所述財政司司長法團（即根據《財政司司長法團條例》、任何其下的規例和任何修訂條例成立的單一法團（下稱「該法團」；如語意容許，亦包括其繼承人及受讓人））的任何分擔，「承租人」在整個「批租年期」期間須自費保養以下項目（以下統稱「該等項目」），並在所有方面令「署長」滿意：

(I) 非獨立式的「政府房舍」的外部飾面，及所有牆、柱、橫樑、天花板、天台樓板、行車道或樓板，以及任何其他「政府房舍」的、以內、周圍、內部、上方及以下的其他結構性元素；

(II) 所有為「政府房舍」及「該土地」上的發展項目的餘下部分而設的升降機、自動梯及樓梯；

(iii) One special child care centre having a total gross floor area of not less than 310 square metres with one space for the parking, loading and unloading of a motor vehicle licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation. The said space shall have a minimum dimension of 3 metres in width and 8 metres in length with a minimum headroom of 3.3 metres; and

(iv) One early education and training centre having a total gross floor area of not less than 330 square metres;

(which accommodation (including such alterations, variations, additions, extensions or improvements thereto carried out pursuant to Clauses Nos. 3.21(b) and 3.21(c) of the said lease) together with any other areas, facilities, services and installations exclusive thereto as the Director may at his absolute discretion determine (whose determination shall be conclusive and binding on the Lessee) is collectively hereinafter referred to as the "Government Accommodation"). For the purpose of Clause No. 3.21(a) of the said lease, the decision of the Director of Social Welfare as to what constitutes a neighbourhood elderly centre, integrated support service centre for persons with severe physical disabilities, special child care centre and early education and training centre shall be final and binding on the Lessee. The spaces provided under Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease shall be located at such position and level as shall be approved in writing by the Director of Social Welfare and be designed and constructed in all respects to the satisfaction of the Director of Social Welfare. The total gross floor area of the spaces provided in accordance with Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease shall be calculated in accordance with Clause No. 3.24(d) of the said lease.

(i) **(i)** The Lessee shall throughout the Lease Term at its own expense but subject to any contribution by The Financial Secretary Incorporated, a corporation sole incorporated under and by virtue of the Financial Secretary Incorporation Ordinance, any regulations made thereunder and any amending legislation ("FSI" which expression shall if the context permits include its successors and assigns), as referred to in Clause No. 3.22(a)(ii)(I) of the said lease and in all respects to the satisfaction of the Director maintain the following items ("the Items"):

(I) the external finishes of the Government Accommodation which is not free standing and the structure of all walls, columns, beams, ceilings, roof slabs, carriageway or floor slabs and any other structural elements of, in, around, within, above and below the Government Accommodation;

(II) all lifts, escalators and stairways serving the Government Accommodation and the remainder of the development on the said land;

(III) 構成為「政府房舍」及「該土地」上的發展項目的餘下部分而設的系統的一部分的所有屋宇設施裝置、設備及裝備（包括但不限於可攜及不可攜的防火裝置裝備）；

(IV) 所有為「政府房舍」及「該土地」上的發展項目的餘下部分而設的公共部分及設施。

(ii) 「承租人」須就「承租人」未有保養「該等項目」所引致（不論是直接或間接引致的）或與「承租人」未有保養「該等項目」相關的一切責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何及如何引致）向政府及「該法團」作出彌償，並使政府及「該法團」持續得到彌償。

(iii) 僅就「該租契」條款第3.21(i)條而言，「承租人」一詞不包括「該法團」。

(iv) 就「該租契」條款第3.21(i)條而言，倘若「政府房舍」的興建及/或位置獨立於任何其他建築物、構築物或架設物，「政府房舍」須被視為獨立式。

(v) 倘若「承租人」及「該法團」沒有達成共識，「署長」就有關「政府房舍」是否獨立式的決定為最終決定及對「承租人」及「該法團」具約束力。

12 「該租契」條款第3.24(a)條、第3.24(b)條、第3.24(c)條、第3.24(d)條及第3.24(f)條訂明：

(a) 除了根據「該租契」條款第3.21(a)(ii)條及第3.21(a)(iii)條提供的兩個停車位外，「承租人」須在「該土地」內以令「署長」滿意的方式提供及維持：

(i) 供停泊根據《道路交通條例》及其下的規例或任何修訂法例獲發牌並屬於「該土地」已建或擬建的建築物的住客及其真正賓客和訪客的汽車（電單車和貨車除外）的停車位，除非另行獲得「署長」的書面同意，停車位的數目須為108而且除非另行獲得「署長」的書面同意，每個停車位的尺寸最少須為2.5米寬及5.0米長而樓底高度最少須為2.4米，根據「該租契」條款第3.24(a)(v)條保留及指定的停車位除外；

(III) all building services installations, plant and equipment (including but not limited to portable and non-portable fire services installation equipment) forming part of the system serving the Government Accommodation and the remainder of the development on the said land;

(IV) all other common parts and facilities serving the Government Accommodation and the remainder of the development on the said land.

(ii) The Lessee shall indemnify and keep indemnified the Government and FSI from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly or indirectly out of or in connection with the failure of the Lessee to maintain the Items.

(iii) For the purpose of Clause No. 3.21(i) of the said lease only, the expression "Lessee" shall exclude FSI.

(iv) For the purpose of Clause No. 3.21(i) of the said lease, a Government Accommodation shall be deemed to be free standing if the same is erected and/or standing independently from any other buildings, structures or erections.

(v) In case no consensus is reached between the Lessee and FSI, the decision of the Director as to whether a Government Accommodation is free standing shall be conclusive and binding on the Lessee and FSI.

12 Clauses Nos. 3.24(a), 3.24(b), 3.24(c), 3.24(d) and 3.24(f) of the said lease stipulate that:

(a) In addition to the 2 spaces provided in accordance with Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease, the Lessee shall provide and maintain within the said land to the satisfaction of the Director:

(i) spaces for the parking of motor vehicles (excluding motor cycles and goods vehicles) licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the residents of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors and, unless the Director otherwise consents in writing, the number of spaces shall be 108 and except for the spaces reserved and designated in accordance with Clause No. 3.24(a)(v) of the said lease, each space shall, unless the Director otherwise consents in writing, have a minimum dimension of 2.5 metres in width and 5.0 metres in length with a minimum headroom of 2.4 metres;

(ii) 供停泊根據《道路交通條例》及其下的規例或任何修訂法例獲發牌並屬於「該土地」已建或擬建的建築物(只限於商業用途)的佔用人及其真正賓客和訪客的汽車(電單車和貨車除外)的停車位,除非另行獲得「署長」的書面同意,停車位的數目須為8而且除非另行獲得「署長」的書面同意,每個停車位的尺寸最少須為2.5米寬及5.0米長而樓底高度最少須為2.4米,根據「該租契」條款第3.24(a)(v)條保留及指定的停車位除外;

(iii) 供停泊根據《道路交通條例》及其下的規例或任何修訂法例獲發牌並屬於「該土地」已建或擬建的建築物的住客及其真正賓客和訪客的電單車的停車位,除非另行獲得「署長」的書面同意,停車位的數目須為40而且除非另行獲得「署長」的書面同意,每個停車位的尺寸最少須為1.0米寬及2.4米長而樓底高度最少須為2.4米;

(iv) 供停泊根據《道路交通條例》及其下的規例或任何修訂法例獲發牌並屬於「該土地」已建或擬建的建築物的住客及其真正賓客和訪客的輕型貨車的停車位,除非另行獲得「署長」的書面同意,停車位的數目須為12而且除非另行獲得「署長」的書面同意,每個停車位的尺寸最少須為3.5米寬及7.0米長而樓底高度最少須為3.6米;

(v) 在「該租契」條款第3.24(a)(i)條及第3.24(a)(ii)條下提供的停車位中,「承租人」須保留及指定由屋宇署可能要求及批准的停車位的數目,供根據《道路交通條例》及其下的規例及任何修訂法例界定的傷殘人士及屬於「該土地」已建或擬建的建築物的住客或佔用人及其真正賓客和訪客停泊汽車(上述所需保留及指定的停車位下稱「傷殘人士停車位」),而每個獲保留及批准的停車位須符合屋宇署或「署長」可能要求及批准的位置及尺寸;以及

(ii) spaces for the parking of motor vehicles (excluding motor cycles and goods vehicles) licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the occupiers of the building or buildings erected or to be erected on the said land to be used for commercial purposes only and their bona fide guests and visitors and, unless the Director otherwise consents in writing, the number of spaces shall be 8 and except for the spaces reserved and designated in accordance with Clause No. 3.24(a)(v) of the said lease, each space shall, unless the Director otherwise consents in writing, have a minimum dimension of 2.5 metres in width and 5.0 metres in length with a minimum headroom of 2.4 metres;

(iii) spaces for the parking of motor cycles licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the residents of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors and, unless the Director otherwise consents in writing, the number of spaces shall be 40 and each space shall, unless the Director otherwise consents in writing, have a minimum dimension of 1.0 metre in width and 2.4 metres in length with a minimum headroom of 2.4 metres;

(iv) spaces for the parking of light goods vehicles licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the residents of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors and, unless the Director otherwise consents in writing, the number of spaces shall be 12 and each space shall, unless the Director otherwise consents in writing, have a minimum dimension of 3.5 metres in width and 7.0 metres in length with a minimum headroom of 3.6 metres;

(v) out of the spaces provided under Clauses Nos. 3.24(a)(i) and 3.24(a)(ii) of the said lease, the Lessee shall reserve and designated such number of spaces for the parking of motor vehicles by disabled persons as defined in the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the residents or occupiers of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors (which spaces to be so reserved and designated are referred to as "the Parking Spaces for the Disabled Persons") as the Building Authority may require and approve and the location and dimension of each of the spaces so reserved and designated shall be as the Building Authority or the Director may require and approve; and

(vi) 供停泊根據《道路交通條例》及其下的規例或任何修訂法例獲發牌並屬於「該土地」已建或擬建的建築物的住客的真正賓客和訪客的汽車的額外停車位，除非另行獲得「署長」的書面同意，停車位的數目須為4，而且除非另行獲得「署長」的書面同意，每個停車位的尺寸最少須為2.5米寬及5.0米長而樓底高度最少須為2.4米。

(b) 根據「該租契」條款第3.21(a)(ii)條、第3.21(a)(iii)條、3.24(a)(i)條、第3.24(a)(ii)條、第3.24(a)(iii)條、第3.24(a)(iv)條、第3.24(a)(v)條及第3.24(a)(vi)條提供的停車位不得用於除上述各條所列之用途以外的任何其他用途。特此說明，上述停車位不得用作汽車存放、陳列或展覽，以作出售或其他用途或用作提供汽車清潔及美容服務。

(c) **(i)** 除了根據「該租契」條款第3.21(a)(ii)條及第3.21(a)(iii)條提供的兩個停車位外，「承租人」須以令「署長」滿意的方式在「該土地」內提供及維持4個供根據《道路交通條例》及其下的規例或任何修訂法例獲發牌的汽車作上落客貨用途的停車位及1個供垃圾收集車作裝卸用途的停車位。除非另行獲得「署長」的書面同意，上述供汽車作上落客貨用途及供垃圾收集車作裝卸用途的停車位的各自的數目不得變更。除非另行獲得「署長」的書面同意，每個上述供汽車作上落客貨用途的停車位的尺寸最少須為3.5米寬及11米長而樓底高度最少須為4.7米，而且該等停車位不得用作與「該土地」已建或擬建的建築物相關的汽車作上落客貨用途之外的任何其他用途。除非另行獲得「署長」的書面同意，每個上述供垃圾收集車作裝卸用途的停車位的尺寸最少須為5.0米寬及12米長而樓底高度最少須為4.5米，而且該等停車位不得用作與「該土地」已建或擬建的建築物相關的垃圾收集車作裝卸用途之外的任何其他用途。在所提供的4個用作汽車上落客貨用途的停車位中，2個停車位須供「該土地」已建或擬建的建築物內的住宅單位的住客及其真正賓客和訪客使用，而另外2個停車位則須供「該土地」已建或擬建只限於商業用途的建築物的佔用人及其真正賓客和訪客使用。

(vi) additional spaces for the parking of motor vehicles licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the bona fide guests, and visitors of the residents of the building or buildings erected or to be erected on the said land and, unless the Director otherwise consents in writing, the number of spaces shall be 4 and each space shall, unless the Director otherwise consents in writing, have a minimum dimension of 2.5 metres in width and 5.0 metres in length with a minimum headroom of 2.4 metres.

(b) The spaces provided in accordance with Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease and Clauses Nos. 3.24(a)(i), 3.24(a)(ii), 3.24(a)(iii), 3.24(a)(iv), 3.24(a)(v) and 3.24(a)(vi) of the said lease shall not be used for any purpose other than for the respective purposes set out in the said Clauses and in particular the said spaces shall not be used for the storage, display or exhibiting of motor vehicles for sale or otherwise or for the provision of car cleaning and beauty services.

(c) **(i)** In addition to the 2 spaces provided in accordance with Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease, the Lessee shall provide and maintain within the said land to the satisfaction of the Director 4 spaces for the loading and unloading of motor vehicles licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and 1 space for the loading and unloading of refuse collection vehicles. The respective number of spaces for the loading and unloading of motor vehicles and for the loading and unloading of refuse collection vehicles as aforesaid shall not be varied, unless the Director otherwise consents in writing. The spaces so provided for the loading and unloading of motor vehicles shall, unless the Director otherwise consents in writing, have a minimum dimension of 3.5 metres in width and 11 metres in length with a minimum headroom of 4.7 metres and such spaces shall not be used for any purpose other than for the loading and unloading of motor vehicles in connection with the building or buildings erected or to be erected on the said land. The space so provided for the loading and unloading of refuse collection vehicles shall, unless the Director otherwise consents in writing, have a minimum dimension of 5.0 metres in width and 12 metres in length with a minimum headroom of 4.5 metres and such space shall not be used for any purpose other than for the loading and unloading of refuse collection vehicles in connection with the building or buildings erected or to be erected on the said land. Out of the 4 spaces so provided for the loading and unloading of motor vehicles, 2 spaces shall be for the use of the residents of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors and the other 2 spaces shall be for the use of occupiers of the building or buildings erected or to be erected on the said land for commercial purposes only and their bona fide guests and visitors.

(ii) 儘管「該租契」條款第3.24(c)(i)條有所規定，根據「該租契」條款第3.24(c)(i)條提供以供根據《道路交通條例》及其下的規例或任何修訂法例獲發牌的汽車(垃圾收集車除外)用作上落客貨用途的停車位，可供屬於「該土地」已建或擬建的建築物的住客或佔用人及其真正賓客和訪客並按運輸署署長不時全權酌情批准的類型、時間及時段停泊根據《道路交通條例》及其下的規例及任何修訂法例獲發牌的汽車(上述作汽車上落客貨及停泊用途的停車位統稱「上落客貨停車位」)。

(d) 就計算「該租契」條款第3.14(a)條所指的總樓面面積而言，

(i) 以下的停車位不應該納入計算：

(I) 根據「該租契」條款第3.24(a)條提供並位於「該土地」地面水平以下的停車位，及位於「該土地」地面水平以下的「上落客貨停車位」；以及

(II) 根據「該租契」條款第3.21(a)(ii)條、第3.21(a)(iii)條及第3.24(c)(i)條提供並位於「該土地」地面水平或地面水平以下的停車位(「上落客貨停車位」除外)；

(ii) 倘若根據「該租契」條款第3.24(a)條提供的停車位及「上落客貨停車位」位於「該土地」地面水平或地面水平以上或根據「該租契」條款第3.21(a)(ii)條、第3.21(a)(iii)條及第3.24(c)(i)條提供的停車位(「上落客貨停車位」除外)位於「該土地」地面水平以上，該等停車位的百分之五十及為該等停車位而設的其他部分(包括但不限於升降機大堂、樓梯平台、行人通道、機動和流通區及機房)的百分之五十應該納入計算「該租契」條款第3.14(a)條所指的總樓面面積，而「署長」就該計算的決定為最終決定及對「承租人」具有約束力。

(f) 就「該租契」條款第3.24條而言，何謂「該土地」的地面水平或任何停車位是否處於地面水平、或在其上、或在其下將由「署長」決定，其決定為最終決定及對「承租人」具約束力。

(ii) Notwithstanding Clause No. 3.24(c)(i) of the said lease, the spaces provided in accordance with Clause No. 3.24(c)(i) of the said lease for the loading and unloading of motor vehicles (excluding refuse collection vehicles) licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation may be used for the parking of such types of motor vehicles licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation and belonging to the residents or occupiers of the building or buildings erected or to be erected on the said land and their bona fide guests and visitors, at such time and for such period as the Commissioner for Transport may from time to time at his sole discretion approve (which spaces to be used for the parking, loading and unloading of motor vehicles as aforesaid are collectively referred to as "the Parking, Loading and Unloading Spaces").

(d) For the purpose of calculating the total gross floor area stipulated in Clause No. 3.14(a) of the said lease,

(i) there shall not be taken in account:

(I) the spaces provided in accordance with Clause No. 3.24(a) of the said lease and the Parking, Loading and Unloading Spaces if they are provided below ground level; and

(II) the spaces provided in accordance with Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease and Clause No. 3.24(c)(i) of the said lease (except the Parking, Loading and Unloading Spaces) if they are provided at or below ground level;

(ii) if the spaces provided in accordance with Clause No. 3.24(a) of the said lease and the Parking, Loading and Unloading Spaces are provided at or above ground level or the spaces provided in accordance with Clauses Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease and Clause No. 3.24(c)(i) of the said lease (except the Parking, Loading and Unloading Spaces) are provided above ground level, 50% of such spaces together with 50% of the other areas including but not limited to lift lobbies, landings, pedestrian access routes, manoeuvring and circulation areas and plant rooms serving such spaces shall be taken into account for the calculation of the total gross floor area stipulated in Clause No. 3.14(a) of the said lease as to which the decision of the Director shall be final and binding on the Lessee.

(f) For the purpose of Clause No. 3.24 of the said lease, the decision of the Director as to what constitutes ground level or whether any space is at, above or below ground level shall be final and binding on the Lessee.

13 「該租契」條款第3.28條訂明：

(a) 除非事先獲得「署長」的書面同意，否則不得在附錄於「該租契」的圖則（下稱「附圖」）上以粉紅色加黑斜線及粉紅色加黑斜線加黑斑點顯示及標明為“W.W.R.”的全部範圍上、上方、下、之上、之下或之內（下稱「水務工程專用範圍」）興建、建築或放置任何建築物或構築物或為任何建築物或構築物而設的結構或支撐，但於「該租契」的日期時已於「水務工程專用範圍」上、上方、下、之上、之下或之內興建或建築或放置的食水管及海水管除外（上述構築物以下統稱「水務工程專用範圍構築物」）。「水務工程專用範圍構築物」於「附圖」上分別以藍色線及紅色線標明大約位置，以資識別。

(b) 除「水務工程專用範圍構築物」外，任何可能阻塞「該租契」條款第3.28(c)條所指的「水務工程裝置」或引致其超出荷載的物件或物料，不論性質為何，都不得放置於「水務工程專用範圍」之內。倘若「署長」認為（其意見為最終意見，並對「承租人」具約束力）「水務工程專用範圍」內有物件或物料可能會阻塞「水務工程裝置」或引致其超出荷載，「署長」有權以書面通知要求「承租人」以各方面均令「署長」滿意的方式自費拆卸或移除該等物件或物料，並恢復「水務工程專用範圍」的原狀。如「承租人」忽略或沒有在通知書訂明的限期內遵行有關要求，或情況緊急，「署長」可進行其認為必須的清除、拆卸及恢復原狀工程，「承租人」須按要求向政府支付該等工程的費用。

(c) 政府、「署長」及水務監督、獲其正式授權的人員、承辦商、獲許可人、被水務監督或政府或「署長」聘請的工人或其正式授權的承辦商或獲許可人，不論是否備有工具、設備、機器或汽車，均獲保留權利不受限制自由隨時進出、往返及或再經過「該土地」或其任何部分，以視察、鋪設、安裝、操作、保養、維修及翻新經過或通過「水務工程專用範圍」或其下面的任何或所有政府水管、閥、閥井或沙井及和政府總水管有關的裝置及所有其他服務（下稱「水務工程裝置」）。

13 Clause No. 3.28 of the said lease stipulates that:

(a) Except with the prior written consent of the Director, no building or structure or support for any building or structure shall be erected, constructed or placed on, over, under, above, below or within the areas shown coloured pink hatched black and pink hatched black stippled black and marked “W.W.R.” on the Plan annexed to the said lease (“the Plan”) (“the Waterworks Reserve Area”) other than the existing fresh water mains and salt water mains with the approximate location for the purposes of identification only as shown by blue lines and red lines respectively on the Plan which as at the date of the said lease are erected or constructed or placed on, over, under, above, below or within the Waterworks Reserve Area (which structures are collectively referred to as “the WRA Structures”).

(b) Except for the WRA Structures, no object or material of whatsoever nature which may obstruct access or cause excessive surcharge to the Waterworks Installation (referred to in Clause No. 3.28(c) of the said lease) shall be placed within the Waterworks Reserve Area. Where in the opinion of the Director (whose opinion shall be final and binding upon the Lessee), there are objects or material within the Waterworks Reserve Area which may obstruct access or cause excessive surcharge to the Waterworks Installation, the Director shall be entitled by notice in writing to call upon the Lessee, at the Lessee’s own expense and in all respects to the satisfaction of the Director, to demolish or remove such objects or material and to reinstate the Waterworks Reserve Area. If the Lessee shall neglect or fail to comply with such notice within the period specified therein, or as required in an emergency the Director may carry out such removal, demolition and reinstatement works as he may consider necessary and the Lessee shall pay to the Government on demand the cost of such works.

(c) There is reserved unto the Government, the Director and the Water Authority, its or their duly authorized officers, contractors, licensees, workmen whether employed by the Water Authority or Government or the Director or by their duly authorized contractors or licensees, whether with or without tools, equipment, machinery or motor vehicles the right of free and unrestricted ingress, egress and regress and at all times to, from and through the said land or any part thereof for the purposes of inspecting, laying, installing, operating, maintaining, repairing and renewing any or all of the Government water mains, valves, valve pits or chambers and the like relating to the Government water mains and all other services (“the Waterworks Installation”) running across, through or under the Waterworks Reserve Area.

(d) 倘若因為行使「該租契」條款第3.28(c)條下授予的權利而需要拆卸或清除「水務工程專用範圍構築物」或其任何部分，「承租人」須，應水務監督或「署長」的要求，於水務監督或「署長」施加的時限內，由「承租人」自費進行所需的拆卸或清除工程，並且確保所進行的工程在所有方面令水務監督或「署長」滿意。倘若「承租人」忽略或未能於水務監督或「署長」要求的時限內完成上述的拆卸或清除工程，水務監督或「署長」可立即執行和進行拆卸或清除工程，「承租人」須按水務監督或「署長」要求即時償還水務監督或「署長」因此產生的費用。除非事先獲得「署長」的書面同意，所有「水務工程專用範圍構築物」均不得修復，且不得於「水務工程專用範圍」之內興建或建築新的構築物替代「水務工程專用範圍構築物」或其任何一項或其任何部分。但倘若「署長」書面同意：

(i) 修復或建築或興建新的構築物代替「水務工程專用範圍構築物」，該修復及建築或興建工程由「承租人」出資負責；及

(ii) 興建或建築新的構築物替代「水務工程專用範圍構築物」，每項新興建或建築的替代構築物（就「該租契」條款第3.28條而言）須被視為其中一項「水務工程專用範圍構築物」。

(e) 「承租人」可經水務監督事先書面批准並符合水務監督施加的任何條件，以符合水務監督批准的標準、規格及設計的物料自費將「水務工程專用範圍構築物」改道到水務監督批准的位置及水平上，而該位置須在「附圖」上以粉紅色加黑交叉斜線顯示並標明為“New W.W.R.”的範圍內（下稱「新水務工程專用範圍」）。「承租人」須確保所進行的工程在所有方面能令水務監督滿意。在該改道工程完畢後，於「該租契」條款第3.28(a)條、第3.28(b)條、第3.28(c)條及第3.28(d)條對「水務工程專用範圍構築物」的提述須被理解及詮釋為指稱「新水務工程專用範圍」內被改道的構築物，而於「該租契」條款第3.28(a)條、第3.28(b)條、第3.28(c)條、第3.28(d)條及第3.28(g)條對「水務工程專用範圍」的提述須被理解及詮釋為指稱「新水務工程專用範圍」，並且就「該租契」條款第3.28(a)條、第3.28(b)條、第3.28(c)條、第3.28(d)條及第3.28(g)條須據此解釋。

(d) In the event that the demolition or removal of the WRA Structures or any part thereof is necessary for the purpose of exercising the rights conferred under Clause No. 3.28(c) of the said lease, the Lessee shall at its own expense if so required by the Water Authority or the Director carry out within such time limit as may be imposed by the Water Authority or the Director and in all respects to the satisfaction of the Water Authority or the Director such demolition or removal works. If the Lessee neglects or fails to carry out the aforesaid demolition or removal works within such time as required by the Water Authority or the Director, the Water Authority or the Director may forthwith execute and carry out the demolition or removal works and the Lessee shall on demand pay to the Water Authority or the Director the cost thereof. Except with the prior written consent of the Director, none of the WRA Structures may be reinstated or a new structure or structures erected or constructed within the Waterworks Reserve Area in substitution for the WRA Structures or any of them or any part of them but in the event of the Director consenting in writing to:

(i) reinstatement or construction or erection of a new structure or structures in substitution, the reinstatement and construction or erection shall be at the expense of the Lessee; and

(ii) a new structure or structures being erected or constructed in substitution, each substitute once erected or constructed shall (for the purpose of Clause No. 3.28 of the said lease) be deemed to be one of the WRA Structures.

(e) The Lessee may with the prior written approval of the Water Authority and in conformity with any condition imposed by the Water Authority, at the Lessee's own expense divert the WRA Structures to such location or locations and at such levels, with such materials as to such standards, specification and design as the Water Authority shall approve within the area shown coloured pink cross-hatched black and marked “New W.W.R.” on the Plan (“the New Waterworks Reserve Area”) and in all respects to the satisfaction of the Water Authority. Upon completion of the said diversion works, references to “WRA Structures” in Clauses Nos. 3.28(a), 3.28(b), 3.28(c) and 3.28(d) of the said lease shall be deemed to be read and construed as references to the diverted structures within the New Waterworks Reserve Area and references to “the Waterworks Reserve Area” in Clauses Nos. 3.28(a), 3.28(b), 3.28(c), 3.28(d) and 3.28(g) of the said lease shall be deemed to be read and construed as references to the New Waterworks Reserve Area, and Clauses Nos. 3.28(a), 3.28(b), 3.28(c), 3.28(d) and 3.28(g) of the said lease shall be construed accordingly.

(f) 政府、「署長」、水務署及「該租契」條款第3.28(b)條、第3.28(c)條及第3.28(d)條提及的任何類別的人士毋須對「承租人」為政府或上述人士行使「該租契」條款第3.28(b)條、第3.28(c)條及第3.28(d)條所賦予的權利所產生或附帶產生而對「承租人」造成或使「承租人」蒙受的任何損失、損害、滋擾或干擾承擔任何責任，以及「承租人」無權就任何上述損失、損害、滋擾或干擾向政府或上述人士提出索償。

(g) 除非事先獲得「署長」的書面同意，「水務工程專用範圍」內禁止植樹及進行地盤平整工程。

14 「該租契」條款第3.29*條訂明：

(a) 「承租人」現確認及接受在「該租契」簽訂當日，「該土地」及「該土地」的相鄰或毗連土地的地面水平之下有由中華電力有限公司(下稱「電力公司」)鋪設的若干輸電電纜(包括132千伏特及11千伏特的電纜，該等電纜的大概路線於「附圖」上以紫色線顯示並以 “CABLES” 標註，以資識別)(下稱「電纜」)以及在「該租契」條款第3.29(d)(i)條所定義的「電纜專用範圍」的地面水平、地面水平之下、地面水平之上或地面水平上面其他有關構築物、設施及裝置(以下統稱「電纜裝置」)。

(b) (i) 「承租人」須被視為已接受及滿意，在「該土地」存在「電纜」及「電纜裝置」的前提下，「該土地」在「該租契」簽訂當日的情況及狀況，「承租人」不得就此或為此作出或提出任何性質的反對或索償。

(ii) 政府毋須對因「電纜」及「電纜裝置」的存在或其他因「電纜」及「電纜裝置」引致或與其有關而產生對「承租人」或任何其他人士造成或使「承租人」或任何其他人士蒙受的任何損失、損害、滋擾、干擾或傷害承擔任何責任。以及「承租人」無權就任何上述損失、損害、滋擾、干擾或傷害向政府提出任何索償(不論是否因「電纜」及「電纜裝置」的存在直接或間接引致或與其存在有關的情況下產生)。

(f) The Government, the Director, the Water Authority and any of the classes of persons referred to in Clauses Nos. 3.28(b), 3.28(c) and 3.28(d) of the said lease shall have no liability whatsoever to the Lessee in respect of any loss, damage, nuisance or disturbance whatsoever caused to or suffered by the Lessee arising out of or incidental to the exercise by it or them of the rights conferred under Clauses Nos. 3.28(b), 3.28(c) and 3.28(d) of the said lease and no claim whatsoever shall be made against it or them by the Lessee in respect of any such loss, damage, nuisance or disturbance.

(g) Except with the prior written consent of the Director, tree planting and site formation shall be prohibited at the Waterworks Reserve Area.

14 Clause No. 3.29* of the said lease stipulates that:

(a) The Lessee hereby acknowledges and accepts that as at the date of the said lease, there are in existence some electricity transmission cables including cables of 132 kilovolts and 11 kilovolts below the ground level of the said land and the adjacent or adjoining land, the approximate alignments of which for identification purposes only are shown by violet lines and marked “CABLES” on the Plan (“the Cables”) together with other associated structures, facilities and installations on, below, above or over the ground level or levels of the Cable Reserve Area as defined in Clause No. 3.29(d)(i) of the said lease (hereinafter collectively referred to as “the Cable Installations”) laid by CLP Power Hong Kong Limited (“the Power Company”).

(b) (i) The Lessee shall be deemed to have accepted and have satisfied himself as to the state and condition of the said land as existing on the date of the said lease subject to the existence of the Cables and the Cable Installations and no objection or claim of whatsoever nature shall be made or raised by the Lessee in respect of or on account of the same.

(ii) The Government shall have no liability in respect of any loss, damage, nuisance, disturbance or injury whatsoever caused to or suffered by the Lessee or any other person by reason of the existence of the Cables and the Cable Installations or anything whatsoever arising therefrom or in connection therewith and no claim whatsoever shall be made against the Government by the Lessee in respect of any such loss, damage, nuisance, disturbance or injury whether arising directly or indirectly out of or in connection with the existence of the Cables and the Cable Installations.

(c) 「承租人」須自費令自己滿意「電纜」及「電纜裝置」的範圍，不得以任何方式拆除、損壞或干擾或容許他人以任何方式拆除、損壞或干擾「電纜」及「電纜裝置」或其任何部分(「署長」對何謂拆除、損壞或干擾為最終決定及對「承租人」具約束力)。任何對「電纜」及「電纜裝置」或其任何部分的拆除、損壞或干擾將由「電力公司」修復、彌補或補救，費用則由「承租人」負擔。「承租人」須在任何時候就「承租人」、其員工、代理、工人及承辦商對「電纜」及「電纜裝置」或其任何部分的拆除、損壞或干擾而引致(不論是直接或間接)或有關的一切責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟(不論任何及如何引致)向政府、其人員、代理、承辦商、工人及其他獲正式授權的人士作出彌償，並使其持續得到彌償。

(d) (i) 不得在「該土地」距離「電纜」中心線或「電纜裝置」外部表面1.5米範圍內的該等部分豎立或興建任何建築物或構築物或任何建築物或構築物的支撐物件或地基及種植任何樹木。上述「該土地」的部分於「附圖」上以粉紅色加黑斜線加黑斑點及粉紅色加黑斑點並以“CABLE RESERVE”標註(以下統稱「電纜專用範圍」)，以資識別。

(ii) 儘管「該租契」條款第3.29(d)(i)條有所規定，如得到「署長」的事先書面批准及受限於「署長」以其絕對酌情權施加的該等條款及條件，可於「電纜專用範圍」之上或上面豎立或興建任何建築物、構築物或任何建築物或構築物的支撐物件，惟「電纜專用範圍」由地面水平向上伸展之高度須有不少於5.1米的空間。

(e) 在展開距離「電纜」及「電纜裝置」所有方向3.0米以內的任何工程前，「承租人」須先行諮詢「署長」及「電力公司」，以確保任何該等工程不會損壞、干擾或危及「電纜」及「電纜裝置」的安全運作(「署長」對此的決定為最終決定)，同時如「署長」要求，「承租人」須自費就確保「電纜」及「電纜裝置」的安全運作採取「電力公司」要求的該等預防措施。

(c) The Lessee shall at his own expense satisfy himself as to the extent of the Cables and the Cable Installations and shall not demolish, damage or interfere with in any way or permit or suffer to be demolished, damaged or interfered with in any way the Cables and the Cable Installations or any part or parts thereof (the decision of the Director as to what constitutes demolition, damage or interference shall be final and binding upon the Lessee). Any demolition or damage of or interference with the Cables and the Cable Installations or any part or parts thereof will be reinstated, made good or rectified by the Power Company at the cost of the Lessee. The Lessee shall at all times indemnify and keep indemnified the Government, its officers, agents, contractors, workmen and other duly authorized personnel from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly or indirectly out of or in connection with any demolition or damage of or interference with the Cables and the Cable Installations or any part or parts thereof by the Lessee, his employees, agents, workmen and contractors.

(d) (i) No building or structure or support or foundation for any building or structure shall be erected or constructed on, and no tree shall be planted in those portions of the said land which are within a distance of 1.5 metres measured from the centre line of the Cables or from the outer surface of the Cable Installations and which portions of the said land are for identification purposes only shown coloured pink hatched black stippled black and pink stippled black and marked “CABLE RESERVE” on the Plan (hereinafter collectively referred to as “the Cable Reserve Area”).

(ii) Notwithstanding Clause No. 3.29(d)(i) of the said lease, with the prior written approval of the Director and subject to such terms and conditions as he may in his absolute discretion impose, building or buildings or structure or structures or support for any building or structure may be erected or constructed over or above the Cable Reserve Area provided that there is a clear space extending upwards from the ground level of the Cable Reserve Area to a height of not less than 5.1 metres.

(e) Prior to the commencement of any works whatsoever within a distance of 3.0 metres in all directions of the Cables and the Cable Installations, the Lessee shall consult the Director and the Power Company so as to ensure that any such works do not damage, interfere with or endanger the safe operation of the Cables and the Cable Installations (as to which the decision of the Director shall be conclusive) and if required by the Director, the Lessee shall, at his own expense, take such precautions as may be required by the Power Company to ensure the safe operation of the Cables and the Cable Installations.

(f) 「承租人」須遵行所有目前有效且與「電纜」及「電纜裝置」有關的條例、附例及規例及任何對其的修訂或替代的法例。

(g) 「承租人」須自費遵行機電工程署及所有其他有關政府和法定機構對於有關或鄰近「電纜」及「電纜裝置」的建築物或構築物的任何部分的興建(包括所用的建材)、維修及保養的要求。

(h) 就「該租契」條款第3.29條而言，「署長」就下列事宜的決定為最終決定及對「承租人」具約束力：

(i) 何謂「該土地」的地面或何謂「該租契」條款第3.29(a)條所指的「該土地」的相鄰或毗連土地；

(ii) 何謂「該租契」條款第3.29(d)(i)條所指的「電纜」中心線及「電纜裝置」外部表面；

(iii) 何謂「該租契」條款第3.29(d)(ii)條所指的「電纜專用範圍」的地面水平；以及

(iv) 何謂「該租契」條款第3.29(g)條所指的鄰近「電纜」及「電纜裝置」的建築物或構築物。

(i) 政府現保留一切權利將「電纜」及「電纜裝置」或其任何部分改道至「該土地」以外的位置，該改道將由「電力公司」或獲「電力公司」正式授權的人員、承辦商、代理或工人或政府進行。「承租人」須在「電力公司」要求時予以配合並為「電力公司」就「電纜」及「電纜裝置」的改道提供一切所需的協助。倘若「電纜」及「電纜裝置」在「署長」滿意的情況下改道至「該土地」以外的位置或從「該土地」移除或在各方面已然被廢棄，「承租人」可向「署長」申請解除「該租契」條款第3.29條下的限制及責任。在考慮該申請時，「署長」可全權酌情施加任何條款及條件。

(j) (i) 就對「電纜」及「電纜裝置」進行勘察、視察、維修、保養、改道、改善、更換或發展的工程以及根據「該租契」條款第3.29(c)條及3.29(i)條進行的勘察、視察、修復、彌補及糾正的工程或「署長」可全權酌情認為在「電纜專

(f) The Lessee shall comply with all Ordinances, bye-laws and regulations for the time being in force and relating to the Cables and the Cable Installations and any amendments or replacing legislation thereto.

(g) The Lessee shall at its own expense comply with all requirements of the Director of Electrical and Mechanical Services and all other relevant Government and statutory authorities in connection with the construction (including the materials to be used), repair and maintenance of any part or parts of the building or structure or buildings or structures connected or in close proximity to the Cables and the Cable Installations.

(h) For the purpose of Clause No. 3.29 of the said lease, the decision of the Director as to:

(i) what constitutes the ground level of the said land or any adjacent or adjoining land referred to in Clause No. 3.29(a) of the said lease;

(ii) what constitutes the centre line of the Cables and the outer surface of the Cable Installations referred to in Clause No. 3.29(d)(i) of the said lease;

(iii) what constitutes the ground level of the Cable Reserve Area referred to in Clause No. 3.29(d)(ii) of the said lease; and

(iv) what constitutes building or structure or buildings or structures in close proximity to the Cables and the Cable Installations referred to Clause No. 3.29(g) of the said lease

shall be final and binding upon the Lessee.

(i) The Government hereby reserves the full right to divert the Cables and the Cable Installations or any part or parts thereof to such location or locations outside the said land, such diversion to be carried out by the Power Company or the duly authorized officers, contractors, agents or workmen of the Power Company or the Government. The Lessee shall render all necessary assistance and cooperation to the Power Company when required by the Power Company in connection with the diversion of the Cables and the Cable Installations. In the event that the Cables and the Cable Installations are diverted outside the said land or removed from the said land or abandoned in all respects to the satisfaction of the Director, the Lessee may apply to the Director for the release of restrictions and obligations under Clause No. 3.29 of the said lease. In considering such application, the Director may impose any terms and conditions at his sole discretion.

(j) (i) For the purpose of carrying out survey, inspection, repair, maintenance, diversion, improvement, replacement, renewal or development works of the Cables and the Cable Installations and carrying out survey, inspection, reinstatement, making good and rectification works under Clauses Nos. 3.29(c) and 3.29(i) of the said lease or any other works which the Director may in

用範圍」須進行的任何其他工程的目的，「承租人」須允許「署長」、「電力公司」及其獲正式授權的人員、承辦商、代理、工人及獲上述任何或全部人士所授權的任何其他人士，不論是否備有工具、設備、裝備、機器或汽車，在免費及不受干擾的情況下，有權在「批租年期」期間不受限制自由隨時進出、往返及或再經過「該土地」或其任何部分及「該土地」已建或擬建的建築物或構築物。

(ii) 政府及獲其正式授權的人員、承辦商、代理及工人毋須對其行使「該租契」條款第3.29(c)條、3.29(i)條及3.29(j)(i)條所賦予的權利所產生或附帶產生而對「承租人」或任何其他人士造成或使「承租人」或任何其他人士蒙受的任何損失、損害、滋擾、干擾或傷害承擔任何責任，以及「承租人」無權就任何上述因行使「該租契」條款第3.29(c)條、3.29(i)條及3.29(j)(i)條所賦予的權利所產生或附帶產生的損失、損害、滋擾、干擾或傷害（不論是直接或間接）向政府及獲其正式授權的人員、承辦商、代理及工人提出索償。

(k) 如「署長」認為（其意見為最終及對「承租人」具約束力）在「電纜專用範圍」之內有任何建築物、構築物或任何建築物或構築物的支撐物件或地基可能會阻塞為進行「該租契」條款第3.29(c)條、3.29(i)條及3.29(j)(i)條訂明的工程而須通過的「電纜專用範圍」的通道，「署長」有權向「承租人」發出書面通知，要求「承租人」在「署長」指明的時限內自費以令「署長」在各方面滿意的方式，拆卸或移除該建築物、構築物或任何建築物或構築物的支撐物件或地基。如「承租人」忽略或沒有在通知書訂明的限期內遵行有關要求，或情況緊急，「署長」可進行其全權酌情認為必須的該等拆卸或移除工程，「承租人」須按要求向政府支付一筆相等於該等工程費用的款項，該筆款項將由「署長」決定，其決定為最終及對「承租人」具約束力。

*註：

根據一封日期為2022年11月23日由地政總署荃灣葵青地政處發出並在土地註冊處以註冊摘要編號22120901640011註冊的同意書，「該租契」條款第3.29條下的限制及責任已按照「該租契」條款第3.29(i)條的規定獲同意解除。

his absolute discretion consider necessary in the Cable Reserve Area, the Lessee shall permit the Director, the Power Company and their duly authorized officers, contractors, agents, workmen and any other persons authorized by any or all of them, with or without tools, equipment, plant, machinery or motor vehicles free of cost and charges and without any interruption, the right of free and unrestricted ingress, egress and regress to, from and through the said land or any part thereof and any building or buildings or structure or structures erected or to be erected thereon at all times throughout the Lease Term.

(ii) The Government and its duly authorized officers, contractors, agents and workmen shall have no liability in respect of any loss, damage, nuisance, disturbance or injury whatsoever caused to or suffered by the Lessee or any other persons whether arising out of or incidental to the exercise of the rights conferred under Clauses Nos. 3.29(c), 3.29(i) and 3.29(j)(i) of the said lease and no claim whatsoever shall be made by the Lessee against the Government and the duly authorized officers, contractors, agents and workmen of the Government in respect of any such loss, damage, nuisance, disturbance or injury whether arising directly or indirectly out of or incidental to the exercise of the rights conferred under Clauses Nos. 3.29(c), 3.29(i) and 3.29(j)(i) of the said lease.

(k) Where in the opinion of the Director (whose opinion shall be final and binding on the Lessee) there are building, structure or support or foundation for any building or structure within the Cable Reserve Area which may obstruct the access to the Cable Reserve Area for carrying out the works as stipulated in Clauses Nos. 3.29(c), 3.29(i) and 3.29(j)(i) of the said lease, the Director shall be entitled to call upon the Lessee by notice in writing, within such time limit as may be specified by the Director at the Lessee's own expense and in all respects to the satisfaction of the Director, to demolish or remove such building, structure or support or foundation for any building or structure. If the Lessee shall neglect or fail to comply with such notice within the time limit specified therein, or as required in an emergency, the Director may carry out such demolition or removal works as the Director may in his absolute discretion consider necessary and the Lessee shall pay to the Government on demand a sum equal to the cost of such works, such sum to be determined by the Director whose determination shall be final and binding on the Lessee.

*Note:

Pursuant to a Consent Letter dated 23rd November 2022 issued by the District Lands Office/Tsuen Wan and Kwai Tsing of the Lands Department and registered in the Land Registry by Memorial No. 22120901640011, consent has been given under Clause 3.29(i) of the said lease to release the restrictions and obligations under Clause 3.29 of the said lease.

15 「該租契」條款第4.2條訂明：

「承租人」須就任何違反「該租契」的條款和契諾所引致（不論是直接或間接引致的）或任何「署長」認為（其意見為最終決定並對「承租人」具約束力）因「該土地」的使用、「該土地」或其任何部分的建設或重建、在「該土地」進行的任何活動或「承租人」在「該土地」進行的任何其他工程（不論該等使用、建設或重建、活動或工程是否符合或違反「該租契」的條款和契諾）而對「該土地」相鄰或毗連土地或「該土地」造成的任何損壞或土壤和地下水污染所引致的一切責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何及如何引致）向政府作出彌償，並使政府持續得到彌償。

16 「該租契」條款第4.3條訂明：

不得於「該土地」豎立或建造墳墓或骨灰龕，亦不得於「該土地」安葬或存放任何人類骸骨或動物骸骨，而不論該骸骨是否存放在陶罐或骨灰甕內。

17 「該租契」條款第4.4條訂明：

除非獲「署長」事先書面同意，「承租人」不得削去、移走或後移任何相鄰或毗連「該土地」的政府土地或進行任何補強、填土或任何類型的斜坡護土工程。給予同意時，「署長」可憑其全權酌情權加入任何其認為合適的條款及條件，包括以他釐定的補地價批出額外政府土地作為「該土地」的延伸。

18 「該租契」條款第4.5條訂明：

(a) 如果任何土地存在或已經被削去、移走或後移或補強或填土或進行任何類型的斜坡護土工程，不論有否經「署長」預先書面同意，亦不論是在「該土地」內或任何政府土地內，旨在構建、平整或開發「該土地」或其中任何部分或「承租人」按「該租契」條款需要進行的任何其他工程或作任何其他用途，「承租人」必須自費進行與修建該等斜坡處理工程、護土牆或其他承托物、保護物、排水或附屬工程或其後必要的其他工程，以便保護與承托「該土地」和任何毗鄰或毗連政府土地或出租土地內的泥土，避免與防止今後發生任何塌方、山泥傾瀉或地陷。「承租人」必須在「批租年期」內自費維持「該土地」、斜坡處理工程、

15 Clause No. 4.2 of the said lease stipulates that:

The Lessee shall indemnify and keep indemnified the Government from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly or indirectly out of or in connection with any breach of the terms and covenants contained in the said lease or any damage or soil and groundwater contamination caused to adjacent or adjoining land or to the said land where such damage or soil and groundwater contamination has, in the opinion of the Director (whose opinion shall be final and binding on the Lessee), arisen out of any use of the said land or any development or redevelopment of the said land or part thereof or out of any activities carried out on the said land or out of any other works carried out thereon by the Lessee whether or not such use, development or redevelopment, activities or works are in compliance with the terms and covenants contained in the said lease or in breach thereof.

16 Clause No. 4.3 of the said lease stipulates that:

No grave or columbarium shall be erected or made on the said land, nor shall any human remains or animal remains whether in earthenware jars, cinerary urns or otherwise be interred therein or deposited thereon.

17 Clause No. 4.4 of the said lease stipulates that:

The Lessee shall not cut away, remove or set back any Government land adjacent to or adjoining the said land or carry out any building-up, filling-in or any slope treatment works of any kind whatsoever on any Government land except with the prior written consent of the Director who may, at his sole discretion, give his consent subject to such terms and conditions as he sees fit, including the grant of additional Government land as an extension to the said land at such premium as he may determine.

18 Clause No. 4.5 of the said lease stipulates that:

(a) Where there is or has been any cutting away, removal or setting back of any land, or any building-up or filling-in or any slope treatment works of any kind whatsoever, whether with or without the prior written consent of the Director, either within the said land or on any Government land, which is or was done for the purpose of or in connection with the formation, levelling or development of the said land or any part thereof or any other works required to be done by the Lessee under the said lease, or for any other purpose, the Lessee shall at its own expense carry out and construct such slope treatment works, retaining walls or other support, protection, drainage or ancillary or other works as shall or may then or at any time thereafter be necessary to protect and support such land within the said land and also any adjacent or adjoining Government or leased land and to obviate and prevent any falling away, landslip or subsidence occurring thereafter. The Lessee shall at all times throughout

護土牆或其他承托物、保護物、排水或附屬工程或其他工程於修繕妥當的狀態，並使「署長」滿意。

(b) 「該租契」條款第4.5(a)條的規定並沒有影響政府該等條件下的權利，特別是「該租契」條款第4.4條賦予政府的權利。

(c) 倘若因為任何構建、平整、開發或「承租人」進行其他工程或任何其他原因造成任何時候發生塌方、山泥傾瀉或地陷，不論發生在或來自「該土地」任何土地或任何毗鄰或毗連政府土地或出租土地，「承租人」須自費進行修復或彌補，使「署長」滿意，並須就所有凡因倒塌、山泥傾瀉或沉降而引致（不論是直接或間接引致的）或與倒塌、山泥傾瀉或沉降相關的所有責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何或如何引致）對政府作出彌償，並使政府持續得到彌償。

(d) 除了「該租契」規定對違返該等條款的任何其他權利或補償外，「署長」有權發出書面通知要求「承租人」進行、修建和保養「該土地」、斜坡處理工程、護土牆或其他承托物、保護物和排水或附屬工程或其他工程或還原及修復任何塌方、山泥傾瀉或地陷。如果「承租人」不理會或未能在通知指明的期限內，遵從該通知要求，並使「署長」滿意，「署長」可立即執行和進行任何必要的工程，「承租人」須按政府要求即時償還政府因此產生的費用，連同任何行政或專業費用及開支。

19 「該租契」條款第4.6條訂明：

未經「署長」的事先書面批准，不得在「該土地」使用碎石設備。

20 「該租契」條款第4.7條訂明：

如果在發展或重建「該土地」或其中任何部分時已安裝預應力地樁，則在其整個使用年期內，「承租人」須自費以令「署長」滿意的方式對預應力地樁進行定期保養及監察，並在「署長」不時依其絕對酌情認為需要時提供上述此類監察工程的報告和資料給「署長」，如「承租人」不理會或未能進行上述要求的定期監察工程，「署長」可隨即執行及進行所需的定期監察工程，而「承租人」須按要求時償還給政府該等工程的費用。

the Lease Term maintain at its own expense the said land, slope treatment works, retaining walls or other support, protection, drainage or ancillary or other works in good and substantial repair and condition to the satisfaction of the Director.

(b) Nothing in Clause No. 4.5(a) of the said lease shall prejudice the Government's rights under the said lease, in particular Clause No. 4.4 of the said lease.

(c) In the event that as a result of or arising out of any formation, levelling, development or other works done by the Lessee or owing to any other reason, any falling away, landslip or subsidence occurs at any time, whether in or from any land, within the said land or from any adjacent or adjoining Government or leased land, the Lessee shall at its own expense reinstate and make good the same to the satisfaction of the Director and shall indemnify and keep indemnified the Government from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly or indirectly out of or in connection with such falling away, landslip or subsidence.

(d) In addition to any other rights or remedies provided in the said lease for breach of any of the terms and covenants contained in the said lease, the Director shall be entitled by notice in writing to call upon the Lessee to carry out, construct and maintain the said land, slope treatment works, retaining walls, or other support, protection, and drainage or ancillary or other works or to reinstate and make good any falling away, landslip or subsidence, and if the Lessee shall neglect or fail to comply with the notice to the satisfaction of the Director within the period specified therein, the Director may forthwith execute and carry out any necessary works and the Lessee shall on demand repay to the Government the cost thereof, together with any administrative or professional fees and charges.

19 Clause No. 4.6 of the said lease stipulates that:

No rock crushing plant shall be permitted on the said land without the prior written consent of the Director.

20 Clause No. 4.7 of the said lease stipulates that:

Where prestressed ground anchors have been installed, upon development or redevelopment of the said land or any part thereof, the Lessee shall at its own expense carry out regular maintenance and regular monitoring of the prestressed ground anchors throughout their service life to the satisfaction of the Director and shall supply to the Director such reports and information on all such monitoring works as the Director may from time to time in his absolute discretion require. If the Lessee shall neglect or fail to carry out the required monitoring works, the Director may forthwith execute and carry out the monitoring works and the Lessee shall on demand repay to the Government the cost thereof.

21 「該租契」條款第4.8條訂明：

(a) 倘若來自「該土地」或受「該土地」任何發展項目影響的其他範圍的泥土、廢石方、瓦礫、建築廢料或建築材料（下稱「廢物」）被侵蝕、沖刷或傾倒到公共小巷或道路或排入道路暗渠、前灘或海床、污水渠、雨水渠、排水渠、明渠或其他政府物業(下稱「政府的物業」)，「承租人」須自費清理該等廢物並為對「政府的物業」所造成的任何損壞作出彌補。「承租人」須對上述的侵蝕、沖刷或傾倒而造成私人物業的任何損壞或滋擾所引致（不論是直接或間接引致的）或與上述的侵蝕、沖刷或傾倒而造成私人物業的任何損壞或滋擾相關的一切責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何或如何引致）對政府作出彌償，並使政府持續得到彌償。

(b) 儘管「該租契」條款第4.8(a)條有所規定，「署長」可以（但無義務）應「承租人」的要求在「政府的物業」清理廢物並對「政府的物業」所造成的任何損壞作出彌補，而「承租人」須應要求向政府支付有關的費用。

22 「該租契」條款第4.9條訂明：

「承租人」須在任何時候，特別是在任何建築、保養、翻新或維修工程（下稱「工程」）期間，採取或促使他人採取一切適當及充分的處理、技巧及預防措施，避免損壞、干擾或阻礙位於、跨越、低於或毗鄰「該土地」或其中部分的任何政府或其他現有排水渠、水道或渠道、總水管、道路、行人路、街道設施、污水渠、明渠、管道、電纜、電線、公用服務設施或任何其他工程或裝置（以下統稱「服務設施」）。「承租人」在進行上述任何工程之前，須進行或促使他人進行適當的調查及必要的查詢，確定任何「服務設施」的現況及水平位置，並須向「署長」提交處理任何可受「工程」影響的「服務設施」的書面建議，以待全面審批，及不得在取得「署長」對「工程」及上述建議作出的書面批准之前進行該等工程。「承租人」須履行「署長」於批准上述建議時對「服務設施」施加的任何要求和承擔符合該等要求支出的費用，包括任何所需的改道、重鋪或修復的費用。「承租人」必須自費支付在一切方面維修、彌補及修復因上述「工程」對「該土地」或其中部分或任何「服務設施」所造成的任何損壞、干擾或阻礙，使「署長」滿意（除非「署長」另作選擇，明渠、污水渠、雨水渠或總水管之修復須由「署長」進行，「承租人」須

21 Clause No. 4.8 of the said lease stipulates that:

(a) In the event of earth, spoil, debris, construction waste or building materials ("the waste") from the said land, or from other areas affected by any development of the said land being eroded, washed down or dumped onto public lanes or roads or into or onto road-culverts, foreshore or seabed, sewers, storm-water drains or nullahs or other Government properties ("the Government properties"), the Lessee shall at its own expense remove the waste from and make good any damage done to the Government properties. The Lessee shall indemnify and keep indemnified the Government from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly or indirectly out of or in connection with any damage or nuisance to private property caused by such erosion, washing down or dumping.

(b) Notwithstanding Clause No. 4.8(a) of the said lease, the Director may (but is not obliged to), at the request of the Lessee remove the waste from and make good any damage done to the Government properties and the Lessee shall pay to the Government on demand the cost thereof.

22 Clause No. 4.9 of the said lease stipulates that:

The Lessee shall take or cause to be taken all proper and adequate care, skill and precautions at all times, and particularly when carrying out construction, maintenance, renewal or repair work ("the Works"), to avoid causing any damage, disturbance or obstruction to any Government or other existing drain, waterway or watercourse, water main, road, footpath, street furniture, sewer, nullah, pipe, cable, wire, utility service or any other works or installations being or running upon, over, under or adjacent to the said land or any part thereof (hereinafter collectively referred to as "the Services"). The Lessee shall prior to carrying out any of the Works make or cause to be made such proper search and enquiry as may be necessary to ascertain the present position and levels of the Services, and shall submit its proposals for dealing with any of the Services which may be affected by the Works in writing to the Director for his approval in all respects, and shall not carry out any work whatsoever until the Director shall have given his written approval to the Works and to such aforesaid proposals. The Lessee shall comply with and at its own expense meet any requirements which may be imposed by the Director in respect of the Services in granting the aforesaid approval, including the cost of any necessary diversion, relaying or reinstatement. The Lessee shall at its own expense in all respects repair, make good and reinstate to the satisfaction of the Director any damage, disturbance or obstruction caused to the said land or any part thereof or any of the Services in any manner arising out of the Works (except for nullah, sewer, storm-water drain or water main, the making good of which shall be carried out by the Director, unless the Director elects otherwise, and the Lessee shall pay to the Government on demand the cost of such works). If the Lessee fails to carry out any such necessary diversion, relaying, repairing, making good and reinstatement of the said

在按要求時向政府支付該等工程費用）。如果「承租人」未能對「該土地」或其中部分或任何「服務設施」進行上述必要的改道、重鋪、維修、彌補及修復工程，並使「署長」滿意，「署長」可進行他認為必要的上述改道、重鋪、維修、修復或彌補工程，「承租人」須在被要求時向政府支付該等工程費用。

23 「該租契」條款第4.10條訂明：

(a) 「承租人」須自費建造與保養不論在「該土地」邊界內或政府土地上「署長」認為需要的排水渠及渠道，以便截斷與引導所有落在或流經「該土地」的暴雨或雨水到最接近的水道、集水井、渠道或政府雨水渠，以令「署長」滿意。「承租人」須對上述暴雨或雨水造成的任何損壞或滋擾而導致（不論是直接及間接導致的）或與上述暴雨或雨水造成的任何損壞或滋擾相關的一切責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何或如何引致）自行負責並向政府作出彌償，並使政府持續得到彌償。

(b) 連接「該土地」的任何排水渠和污水渠至政府的雨水渠及污水渠（如已建成及已啟用）的工程可由「署長」進行，但「署長」毋須就因此產生的任何損失或損害對「承租人」負責。「承租人」須在被要求時向政府支付上述連接工程的費用，或者該等連接工程亦可由「承租人」自費進行，並使「署長」滿意。在該種情況下，上述連接工程的任何一段若在政府土地內修建，必須由「承租人」自費保養，直至按要求時由「承租人」移交給政府，由政府出資負責以後的保養。「承租人」須在被要求時向政府支付有關上述連接工程的技術審核之費用。若「承租人」未能保養上述在政府土地內修建的任何一段連接工程，「署長」可進行他認為必要的保養工程，「承租人」須在被要求時向政府支付該等工程的費用。

24 「該租契」條款第5.3條訂明：

(a) 政府、任何毗連或鄰近土地或處所的承租人、租戶、佔用人和獲許可人或任何其他獲得任何上述人正式授權的人士均獲保留權利讓氣體、電力、淡水或鹹水、污物、污水、空氣、煙或其他排出物、電話、水、公用事業設施及其他服務，藉通過或經過「該土地」或其上面或下面或其任何部分的雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道（包括總水喉管）以往來該等毗連或鄰近土地或處所。

land or any part thereof or of any of the Services to the satisfaction of the Director, the Director may carry out any such diversion, relaying, repairing, making good or reinstatement as he considers necessary and the Lessee shall pay to the Government on demand the cost of such works.

23 Clause No. 4.10 of the said lease stipulates that:

(a) The Lessee shall construct and maintain at its own expense and to the satisfaction of the Director such drains and channels, whether within the boundaries of the said land or on Government land, as the Director may consider necessary to intercept and convey into the nearest stream-course, catchpit, channel or Government storm-water drain all storm-water or rain-water falling or flowing on to the said land, and the Lessee shall be solely liable for and shall indemnify and keep indemnified the Government from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly and indirectly out of or in connection with any damage or nuisance caused by such storm-water or rain-water.

(b) The works of connecting any drains and sewers from the said land to the Government storm-water drains and sewers, when laid and commissioned, may be carried out by the Director who shall not be liable to the Lessee for any loss or damage thereby occasioned and the Lessee shall pay to the Government on demand the cost of such connection works. Alternatively, the said connection works may be carried out by the Lessee at its own expense to the satisfaction of the Director and in such case any section of the said connection works which is constructed within Government land shall be maintained by the Lessee at its own cost and upon demand be handed over by the Lessee to the Government for future maintenance thereof at the expense of the Government and the Lessee shall pay to the Government on demand the cost of the technical audit in respect of the said connection works. The Director may, upon failure of the Lessee to maintain any section of the said connection works which is constructed within Government land, carry out such maintenance works as he considers necessary and the Lessee shall pay to the Government on demand the cost of such works.

24 Clause No. 5.3 of the said lease stipulates that:

(a) There is reserved unto the Government and the lessees, tenants, occupiers and licensees of any adjoining or neighbouring land or premises or any other persons duly authorized by any of them the right of passage of gas, electricity, fresh or salt water, soil, drainage, air, smoke or other effluent, telephone, water, utility, and other services to and from such adjoining or neighbouring land or premises through such gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) passing along, through, over, upon, under or in the said land or any part thereof.

(b) 政府、任何毗連或鄰近土地或處所的承租人、租戶、佔用人和獲許可人或任何其他獲得任何上述人士正式授權的人均獲保留權利隨時出入、經過和再經過「該土地」或其任何部分，以視察、保養、維修及翻新「該租契」條款第5.3(a)條所指通過或經過「該土地」或其上面或下面或其任何部分的雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道（包括總水喉管），以便讓氣體、電力、淡水或鹹水、污物、污水、空氣、煙或其他排出物、電話、水、公用事業設施及其他服務往來該等毗連或鄰近土地或處所，惟政府毋須對「承租人」因任何毗連或鄰近土地或處所的承租人、租戶、佔用人或獲許可人或任何其他獲得任何上述人士正式授權的人行使「該租契」條款第5.3(b)條所賦予的權利所產生或附帶產生而對「承租人」造成或使「承租人」蒙受的任何損失、損害、滋擾或干擾承擔任何責任，以及「承租人」無權就任何該等損失、損害、滋擾或干擾向政府提出索償。

(c) 「承租人」須以令「署長」滿意的方式自費維持、保養及維修「該租契」條款第5.3(a) 條所指的所有及任何雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道（包括總水喉管）。

25 「該租契」條款第5.5條訂明：

除非事先獲得「署長」的書面同意，否則「承租人」不得進行或允許或容許他人進行任何與已建或擬建於「該土地」的任何住宅單位有關的工程，包括但不限於拆卸或改動任何間隔牆、樓板、天台樓板或間隔結構，致使該單位內部連結及可通往建於或擬建於「該土地」的任何毗連或相鄰住宅單位。至於何謂使一個單位內部連結及可通往任何毗連或相鄰住宅單位的工程，「署長」的決定為最終決定，並對「承租人」具約束力。

註：

1. 自2022年7月1日起，運輸及房屋局局長已更改為房屋局局長。
2. 自2022年7月1日起，運輸及房屋局常任秘書長（房屋）已更改為房屋局常任秘書長。
3. 請查閱「該租契」全文及「該租契」附圖以了解上述條款及「該租契」中其他條款的全部詳情。「該租契」的全文可於觀塘開源道33號建生廣場一樓內之綠置居銷售小組開放時間內免費查閱。

(b) There is reserved unto the Government and the lessees, tenants, occupiers and licensees of any adjoining or neighbouring land or premises or any other persons duly authorized by any of them the right of free ingress, egress and regress to and from the said land or any part thereof for the purpose of inspecting, maintaining, repairing and renewing all and any of the said gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) referred to in Clause No. 5.3(a) of the said lease passing along, through, over, upon, under or in the said land or any part thereof through which gas, electricity, fresh or salt water, soil, drainage, air, smoke or other effluent, telephone, water, utility and other services pass to and from such adjoining or neighbouring land or premises provided that the Government shall have no liability in respect of any loss, damage, nuisance or disturbance whatsoever caused to or suffered by the Lessee arising out of or incidental to the exercise of the rights by the lessees, tenants, occupiers or licensees of any adjoining or neighbouring land or premises or any other persons duly authorized by any of them under Clause No. 5.3(b) of the said lease and no claim shall be made against the Government by the Lessee in respect of any such loss, damage, nuisance or disturbance.

(c) The Lessee shall at its own expense uphold, maintain and repair all and any of the said gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) referred to in Clause No. 5.3(a) of the said lease, all to be done to the satisfaction of the Director.

25 Clause No. 5.5 of the said lease stipulates that:

Except with the prior written consent of the Director, the Lessee shall not carry out or permit or suffer to be carried out any works in connection with any residential flat erected or to be erected on the said land, including but not limited to demolition or alteration of any partition wall or any floor or roof slab or any partition structure, which shall result in such flat being internally linked to and accessible from any adjoining or adjacent residential flat erected or to be erected on the said land. The decision of the Director as to what constitutes works resulting in a flat being internally linked to and accessible from any adjoining or adjacent residential flat shall be final and binding on the Lessee.

Notes :

1. Since 1 July 2022, the Secretary for Transport and Housing has been changed to the Secretary for Housing.
2. Since 1 July 2022, the Permanent Secretary for Transport and Housing (Housing) has been changed to the Permanent Secretary for Housing.
3. For full details of the above provisions and other provisions in the said lease, please refer to the said lease and the plan annexed thereto. Full script of the said lease is available for inspection free of charge during opening hours at the GSH Sales Unit on 1/F., Pioneer Place, 33 Hoi Yuen Road, Kwun Tong.

17 公共設施及公眾休憩用地的資料

Information on Public Facilities and Public Open Spaces

A 根據批地文件規定須興建並提供予政府或供公眾使用的任何設施

1. 政府、機構和社區設施

(i) 批地文件的有關條文

除在本節另有定義外，下述用詞的意義將等同於「批地文件的摘要」內該用詞的意義。請參閱「批地文件的摘要」。

i. 「該租契」條款第3.21(a)條至3.21(e)條及3.21(h)條至3.21(j)條訂明：

(a) 除「該租契」條款第3.21(b)及3.21(c)條另有規定外，「承租人」須自費及以在所有方面使社會福利署署長滿意及良好的工作方式於「該土地」興建、建造、提供及保養由政府、機構及社區設施組成的：

(i) 一間總樓面面積不少於390平方米的長者鄰舍中心；

(ii) 一間總樓面面積不少於170平方米的嚴重肢體傷殘人士綜合支援服務中心及一個供根據《道路交通條例》及其下的規例及任何修訂法例獲發牌的汽車上落客貨及停泊用途的停車位。該停車位的尺寸最少須為3米寬及8米長而樓底高度最少須為3.3米；

(iii) 一間總樓面面積不少於310平方米的特殊幼兒中心及一個供根據《道路交通條例》及其下的規例及任何修訂法例獲發牌的汽車上落客貨及停泊用途的停車位。該停車位的尺寸最少須為3米寬及8米長而樓底高度最少須為3.3米；以及

(iv) 一間總樓面面積不少於330平方米的早期教育及訓練中心；

（該房舍（包括根據「該租契」條款第3.21(b)條及3.21(c)條進行的更改、改動、加建、擴展或改善工程）連同其他「署長」完全酌情決定（其決定為最終決定及對「承租人」具約束力）為該房舍專屬的任何地方、設施、服務設施及裝置，下稱「政府房舍」）。就「該租契」條款第3.21(a)條而言，如何構成一間長者鄰舍中心、嚴重肢體傷殘人士綜合支援服務中心、特殊幼兒中心及早期教育及訓練中心由社會福利署署長決定，其決定為最終決定及對「承租人」具約束力。根據「該租契」條款第3.21(a)(ii)條及3.21(a)(iii)條提供的停車位須位於社會福利署署長以書面批准的位置及水平，並確保該設計和建造在所有方面能使社會福利署署長滿意。根據

A Any Facilities that are Required under the Land Grant to be Constructed and Provided for the Government, or for Public Use

1. 1. GOVERNMENT, INSTITUTION AND COMMUNITY FACILITIES

(i) Relevant Provisions of the Land Grant

Unless otherwise defined in this section, capitalized and other terms used in the following shall have the same meaning of such terms used in the Summary of Land Grant. Please refer to the Summary of Land Grant for reference.

i. Clauses Nos. 3.21(a) to 3.21(e) and 3.21(h) to 3.21(j) of the said lease stipulate that:

(a) Subject to Clause Nos. 3.21(b) and 3.21(c) of the said lease, the Lessee shall at its own expense and in all respects to the satisfaction of the Director of Social Welfare erect, construct, provide and maintain on the said land in a good workmanlike manner government, institution and community facilities comprising:

(i) One neighbourhood elderly centre having a total gross floor area of not less than 390 square metres;

(ii) One integrated support service centre for persons with severe physical disabilities having a total gross floor area of not less than 170 square metres with one space for the parking, loading and unloading of a motor vehicle licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation. The said space shall have a minimum dimension of 3 metres in width and 8 metres in length with a minimum headroom of 3.3 metres;

(iii) One special child care centre having a total gross floor area of not less than 310 square metres with one space for the parking, loading and unloading of a motor vehicle licensed under the Road Traffic Ordinance, any regulations made thereunder and any amending legislation. The said space shall have a minimum dimension of 3 metres in width and 8 metres in length with a minimum headroom of 3.3 metres; and

(iv) One early education and training centre having a total gross floor area of not less than 330 square metres;

(which accommodation (including such alterations, variations, additions, extensions or improvements thereto carried out pursuant to Clause Nos. 3.21(b) and 3.21(c) of the said lease) together with any other areas, facilities, services and installations exclusive thereto as the Director may at his absolute discretion determine (whose determination shall be conclusive and binding on the Lessee) is hereinafter collectively referred to as the "Government Accommodation"). For the purpose of Clause No. 3.21(a) of the said lease, the decision of the Director of Social Welfare as to what constitutes a neighbourhood elderly centre, integrated support service centre for persons with severe physical disabilities, special child care centre and early education and training centre shall be final and binding on the Lessee. The spaces provided under Clause Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease shall be located at such position and level as shall be approved in writing by the Director of Social Welfare and be designed and constructed in all respects to the

「該租契」條款第3.21(a)(ii)條及3.21(a)(iii)條提供的停車位的總樓面面積須按照「該租契」條款第3.24(d)條計算。

(b) 在整個「批租年期」內，「署長」以及依據《財政司司長法團條例》、任何其下的規例和任何修訂法例成立的名為財政司司長法團的單一法團（下稱「該法團」；如語意容許，亦包括其繼承人及受讓人）在根據「該租契」條款第3.21(d)條獲轉讓「政府房舍」後（就「該租契」條款第3.21(b)條而言，不包括其受讓人）將擁有全權及可無須經「承租人」贊同或批准：

(i) 改變或更改「政府房舍」或其任何部分的用途；

(ii) 更改「政府房舍」或其任何部分的總樓面面積；以及

(iii) 進行建築工程，包括但不限於「署長」認為為行使「該租契」條款第3.21(b)(i)及3.21(b)(ii)條賦予的權利而須進行的改建、變更、加建、擴展或改善工程，不論有關工程是否需要工具、裝備、設備及機械進行

現同意及聲明，政府、「署長」及「該法團」不須對「署長」或「該法團」為行使「該租契」條款第3.21(b)條賦予的權力所導致的或附帶的對「承租人」造成或使其蒙受的任何損失、損害、滋擾或干擾負上任何責任，而「承租人」亦不得就任何損失、損害、滋擾或干擾向政府、「署長」或「該法團」提出任何索償。

(c) 除「該租契」條款第3.21(b)條另有規定外，「承租人」根據「該租契」條款第3.21(d)條將「政府房舍」或其任何部分轉讓予「該法團」前，除非得到「署長」事先書面同意，否則「承租人」不得改變或更改「政府房舍」或其任何部分的用途或更改「政府房舍」或其任何部分的總樓面面積。

(d) 「承租人」須應「署長」的要求，自費而不收任何費用，以空置管有、無產權負擔或受制於現有租約或特許證或兩者（如有）的情況下，按「署長」指定的條款及條件，將「該租契」條款第3.21(e)條指明的不分割份數或其任何部分，連同獨有使用、佔用和享用「政府房舍」或其有關部分的權利，轉讓予「該法團」。

(e) 根據「該租契」條款第3.21(d)條轉讓予「該法團」的屬於整個「該土地」的不分割份數的數目將由「署長」按照「政府房舍」所佔的總樓面面積與所有已建或擬建於「該土地」內的建築物的總樓面面積的比例而訂定，「署長」就這方面訂定的數目為最終決定，並對「承租人」具約束力。

satisfaction of the Director of Social Welfare. The total gross floor area of the spaces provided in accordance with Clause Nos. 3.21(a)(ii) and 3.21(a)(iii) of the said lease shall be calculated in accordance with Clause No. 3.24(d) of the said lease.

(b) Throughout the Lease Term the Director and, in addition, upon assignment of the Government Accommodation to The Financial Secretary Incorporated, a corporation sole incorporated under and by virtue of the Financial Secretary Incorporation Ordinance, any regulations made thereunder and any amending legislation (hereinafter referred to as "FSI" which expression shall if the context permits include its successors and assigns) pursuant to Clause No. 3.21(d) of the said lease, FSI (which expression for the purposes of Clause No. 3.21(b) of the said lease shall not include its assigns) shall have the absolute right without the concurrence or approval of the Lessee:

(i) to alter or vary the use of the Government Accommodation or any part thereof;

(ii) to vary the gross floor area of the Government Accommodation or any part thereof;

(iii) to carry out such building works including but not limited to alterations, variations, additions, extensions or improvements as may be considered necessary by the Director with or without tools, equipment, plant and machinery to effect the right conferred under Clause Nos. 3.21(b)(i) and 3.21(b)(ii) of the said lease

and it is agreed and declared in the said lease that the Government, the Director and FSI shall have no liability for and no claim whatsoever shall be made against the Government, the Director or FSI in respect of any loss, damage, disturbance or nuisance whatsoever caused to or suffered by the Lessee arising out of or incidental to the exercise by the Director or FSI of the right conferred under Clause No. 3.21(b) of the said lease.

(c) Subject to Clause No. 3.21(b) of the said lease, prior to the Lessee's assignment of the Government Accommodation or any part thereof to FSI pursuant to Clause No. 3.21(d) of the said lease, the Lessee may not, except with the prior written consent of the Director, alter or vary the use of the Government Accommodation or any part thereof or vary the gross floor area of the Government Accommodation or any part thereof.

(d) The Lessee shall when called upon so to do by the Director assign to FSI, free of costs, at the expense of the Lessee, with vacant possession, free from encumbrances or subject to existing tenancies or licences or both (if any) and on such terms and conditions as may be specified by the Director, the undivided shares specified in Clause No. 3.21(e) of the said lease or any part thereof together with the right to the exclusive use, occupation and enjoyment of the Government Accommodation or such part thereof.

(e) The number of undivided shares in the whole of the said land to be assigned to FSI in accordance with Clause No. 3.21(d) of the said lease shall be determined by the Director having regard to the proportion which the gross floor area of the Government Accommodation shall bear to the gross floor area of all the buildings erected or to be erected within the said land. The determination of the Director in this respect shall be final and binding on the Lessee.

(h) 「署長」在「政府房舍」根據「該租契」條款第3.21(d)條轉讓之前，有權於任何時間要求，而「承租人」須按要求及「署長」可能認為合適的條款及條件將「政府房舍」或「署長」所要求的「政府房舍」的部分的空置管有權交予政府供其獨有使用、佔用和營運。

(i) (i) 受限於「該租契」條款第3.22(a)(ii)(I)條所述的「該法團」的任何分擔，「承租人」在整個「批租年期」期間須自費保養以下項目（以下統稱「該等項目」），並在所有方面令「署長」滿意：

(I) 非獨立式的「政府房舍」的外部飾面，及所有牆、柱、橫樑、天花板、天台樓板、行車道或樓板，以及任何其他「政府房舍」的、以內、周圍、內部、上方及以下的其他結構性元素；

(II) 所有為「政府房舍」及「該土地」上的發展項目的餘下部分而設的升降機、自動梯及樓梯；

(III) 構成為「政府房舍」及「該土地」上的發展項目的餘下部分而設的系統的一部分的所有屋宇設施裝置、設備及裝備（包括但不限於可攜及不可攜的防火裝置裝備）；

(IV) 所有為「政府房舍」及「該土地」上的發展項目的餘下部分而設的公共部分及設施。

(ii) 「承租人」須就「承租人」未有保養「該等項目」所引致（不論是直接或間接引致的）或與「承租人」未有保養「該等項目」相關的一切責任、索償、損失、損害、支出、費用、開支、要求、法律行動及訴訟（不論任何及如何引致）向政府及「該法團」作出彌償，並使政府及「該法團」持續得到彌償。

(iii) 僅就「該租契」條款第3.21(i)條而言，「承租人」一詞不包括「該法團」。

(iv) 就「該租契」條款第3.21(i)條而言，倘若「政府房舍」的興建及/或位置獨立於任何其他建築物、構築物或架設物，「政府房舍」須被視為獨立式。

(v) 倘若「承租人」及「該法團」沒有達成共識，「署長」就有關「政府房舍」是否獨立式的決定為最終決定及對「承租人」及「該法團」具約束力。

(h) The Director shall have the right to demand, at any time before the assignment of the Government Accommodation pursuant to Clause No. 3.21(d) of the said lease, delivery of vacant possession of the Government Accommodation or such part thereof as required by the Director and the Lessee shall upon such demand deliver the same to the Government for its exclusive use, occupation and operation upon such terms and conditions as the Director may consider appropriate.

(i) (i) The Lessee shall throughout the Lease Term at its own expense but subject to any contribution by FSI as referred to in Clause No. 3.22(a)(ii)(I) of the said lease and in all respects to the satisfaction of the Director maintain the following items ("the Items"):

(I) the external finishes of the Government Accommodation which is not free standing and the structure of all walls, columns, beams, ceilings, roof slabs, carriageway or floor slabs and any other structural elements of, in, around, within, above and below the Government Accommodation;

(II) all lifts, escalators and stairways serving the Government Accommodation and the remainder of the development on the said land;

(III) all building services installations, plant and equipment (including but not limited to portable and non-portable fire services installation equipment) forming part of the system serving the Government Accommodation and the remainder of the development on the said land;

(IV) all other common parts and facilities serving the Government Accommodation and the remainder of the development on the said land.

(ii) The Lessee shall indemnify and keep indemnified the Government and FSI from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly or indirectly out of or in connection with the failure of the Lessee to maintain the Items.

(iii) For the purpose of Clause No. 3.21(i) of the said lease only, the expression "Lessee" shall exclude FSI.

(iv) For the purpose of Clause No. 3.21(i) of the said lease, a Government Accommodation shall be deemed to be free standing if the same is erected and/or standing independently from any other buildings, structures or erections.

(v) In case no consensus is reached between the Lessee and FSI, the decision of the Director as to whether a Government Accommodation is free standing shall be conclusive and binding on the Lessee and FSI.

(j) 儘管「該租契」條款第3.21(d)條有所規定，「承租人」須應「署長」的要求，及按照社會福利署署長可能決定的其他條款及條件，以象徵式的租金將「政府房舍」或其任何部分分租予「該法團」或社會福利署署長不時提名的其他人士。

ii. 「該租契」條款第3.22(a)(ii)(I)條至3.22(a)(ii)(III)條訂明：

(a) (ii)「公契」須按「署長」批准或要求以指定形式及包括指定條款，其中特別包括以下條款：

(I) (A) 「該法團」作為「政府房舍」的業主須負責其保養及管理事宜，但無須負責保養及管理「該土地」上發展項目的其餘部分；

(B) 「該法團」作為「政府房舍」的業主須就實際供「政府房舍」使用或由該處的佔用人、其受僱人、承辦商、代理或訪客使用的設施或服務支付管理及保養費。然而，「該法團」的責任將由政府產業署署長或「署長」就此提名的其他人士釐定，且於任何情況下均不得超過根據「政府房舍」所佔總樓面面積與已建或擬建於「該土地」上的所有建築物的總樓面面積的比例計算的管理及保養費的百分比。有關的維修及管理費的繳付責任將由「政府房舍」或其有關部分的轉讓契據的日期或政府取得「政府房舍」或其有關部分之空置管有的日期（以較早發生者為準）起計。此外，除非及直至政府產業署署長或「署長」就此提名的其他人士已經以書面批准有關管理及保養費金額，「該法團」將無須對管理及保養費承擔繳付責任；以及

(C) 「該法團」作為「政府房舍」的業主無須就發展項目任何其他部分（不論是否「該租契」條款第3.22(a)(vi)條所指的「公用地方」或其他）攤付任何管理及保養費，亦無須就政府產業署署長或「署長」就此提名的人士認為並非直接服務或以其它方式惠及「政府房舍」的任何設施或服務的提供攤付任何管理及保養費；

(II)「該法團」無須繳付以下費用：

(A) 管理費按金；

(j) Notwithstanding Clause No. 3.21(d) of the said lease, the Lessee shall when called upon by the Director so to do underlet the Government Accommodation or any part thereof at nominal rent to FSI or such other person or persons as the Director of Social Welfare may nominate from time to time and on such other terms and conditions as may be determined by the Director of Social Welfare.

ii. Clauses Nos. 3.22(a)(ii)(I) to 3.22(a)(ii)(III) of the said lease stipulate that:

(a) (ii) the DMC must be in such a form and contain the provisions which the Director shall approve or require and in particular shall contain, inter alia, provisions to the following effect:

(I) (A) FSI as owner of the Government Accommodation shall be responsible for the maintenance and management thereof but not the remainder of the development on the said land;

(B) FSI as owner of the Government Accommodation shall be liable for payment of the management and maintenance charges only in respect of facilities or services which actually serve the Government Accommodation or are used by the occupier thereof, its servants, contractors, agents or visitors provided however that the liability of FSI shall be as determined by the Government Property Administrator or other person nominated by the Director for this purpose and in any event shall not exceed the proportion of the management and maintenance charges which the gross floor area of the Government Accommodation bears to the gross floor area of all the buildings erected or to be erected on the said land and shall only commence from the date of the Assignment or the date of taking over of vacant possession by the Government of the Government Accommodation or the relevant part(s) thereof, whichever is the earlier and provided further that FSI shall incur no liability for payment of any management and maintenance charges unless and until the amount of the same shall have first been approved in writing by the Government Property Administrator or other person nominated by the Director for this purpose; and

(C) FSI as owner of the Government Accommodation shall have no liability for any contribution towards any management and maintenance charges for any other part of the development (whether the Common Areas referred to in Clause No. 3.22(a)(vi) of the said lease or otherwise) or for the provision of facilities or services which do not, in the opinion of the Government Property Administrator or other person nominated by the Director for this purpose, directly serve or otherwise directly benefit the Government Accommodation;

(II) FSI shall not be liable for any payment of:

(A) management deposits;

(B) 資本設備基金，事前經由政府產業署署長或「署長」就此提名的其他人士批准而確實服務「政府房舍」或由該處佔用人、其受僱人、承辦商、代理或訪客使用的設施及服務相關的資本償還除外；

(C) 「政府房舍」相關的保險保費；

(D) 裝修泥頭清理費；以及

(E) 逾期未繳管理及保養費的罰款；

或同類付款；

(III) 「該法團」、其承租人、租戶、特許持有人、獲其授權的人士及「政府房舍」現任業主及佔用人擁有下列權利、特權及地役權的權益：

(A) 「政府房舍」享有庇護、支撐物及保護的權利；

(B) 讓氣體、電力、食水、污水、空調、電話及所有其他服務自由透過現時或於「批租年期」內於「該土地」的任何部分及「該土地」上的發展項目任何部分鋪設或越過的溝渠、污水管、排水渠、排煙管、管線、管道、水道、電纜、水管、電線及其他導體往來「政府房舍」的權利；

(C) 於任何時候全權酌情，自費改動、改道、更改、重鋪或還原任何「政府房舍」或其任何部分專用的服務與設施(下稱「政府房舍服務」)的權利，而無須向「承租人」支付任何費用。但是，在進行上述「政府房舍服務」的改動、改道、更改、重鋪或還原工程時必須採取適當及足夠的預防措施，以確保不會對「該土地」內及服務除「政府房舍」外「該土地」上發展項目的所有部分的該等服務及設施造成損壞；

(D) 為正確地使用及享用「政府房舍」或其任何部分的目的通行及再通行、進出、往返及使用「該租契」條款第3.22(a)(vi)條中所指的「公用地方」，以及使用和享用「該土地」或其任何部分內或「該土地」上發展項目的任何公用設施的權利；

(E) 在所有合理時間不論是否連同測量師、承辦商、工人及其他人，及不論是否攜帶工具、設備、裝備、物料、機器或汽車進入「該土地」或「該土地」上發展項目的任

(B) capital equipment fund except for the reimbursement of capital expenditure, as shall first be approved by the Government Property Administrator or other person nominated by the Director for this purpose, in respect of the facilities and services which actually serve the Government Accommodation or are used by the occupier thereof, its servants, contractors, agents or visitors;

(C) insurance premium in respect of the Government Accommodation;

(D) debris removal fee; and

(E) penalty charges on late payment of management and maintenance charges;

or payment of a like nature;

(III) FSI, its lessees, tenants, licensees and persons authorized by it and owner and occupier for the time being of the Government Accommodation shall have the benefit of the following rights, privileges and easements:

(A) the right of shelter support and protection for the Government Accommodation;

(B) the right of free passage and running of gas, electricity, water, sewage, air-conditioning, telephone and all other services from and to the Government Accommodation through the gutters, sewers, drains, flues, conduits, ducts, watercourses, cables, pipes, wires and other conducting media now or during the Lease Term laid on or running through any part of the said land and any part of the development on the said land;

(C) the right at its own cost to alter, divert, vary, relay or reinstate any of the services and facilities serving exclusively the Government Accommodation or any part thereof ("the Government Accommodation Services") at any time at its absolute discretion without any charge by the Lessee provided that proper and adequate care and precaution shall be taken during any alteration, diversion, variation, relaying or reinstatement works of the Government Accommodation Services so as to ensure that no damage is caused to those services and facilities within the said land and serving all those parts of the development on the said land other than the Government Accommodation;

(D) the right to go pass and repass over and along and to use the Common Areas referred to in Clause No. 3.22(a)(vi) of the said lease in connection with the proper use and enjoyment of the Government Accommodation or any part thereof and to use and receive the benefit of any common facilities within the said land or any part thereof or the development thereon;

(E) the right at all reasonable times with or without surveyors, contractors, workmen or others and with or without tools, plant, equipment, material, machinery or motor vehicles to enter upon the said land or any part of the development on the said land for the purposes of extending or carrying out maintenance, repair, addition and alteration works to the Government Accommodation or any part thereof and maintenance, repair, alteration, diversion, variation, relaying and reinstatement works to the Government Accommodation Services or any part thereof;

何部分的權利，以便於「政府房舍」或其任何部分擴建或進行保養、維修、加建及改建工程，以及進行「政府房舍服務」或其任何部分的保養、維修、改建、改道、更改、重鋪及還原工程；

(F) 遵照「署長」要求，享有暢通無阻進出「政府房舍」的通行權；

(G) 在「政府房舍」或其任何部分內、周圍及邊界上的牆、圓柱及其他結構組件安裝、建設、展示、陳列、保養、維修、拆除和更新招牌及廣告的專有權，及進入「該土地」或其任何部分或其上的發展項目任何部分的通行權，不論是否連同受僱人、工人及其他人，及不論是否攜帶工具、設備、裝備、機械、物料或汽車，以便檢驗、安裝、建設、展示、陳列、保養、維修、拆除及更新此等招牌及廣告；

(H) 固定於「政府房舍」的天台樓板、牆及其他結構組件上面、裏面或表面的照明管道、消防、通風及其他服務、設施、裝置、固定裝置、輔助工程，設備及物料的通行權；

(I) 改變及運行「政府房舍」或於「政府房舍」內、周圍、其範圍內、其上及其下的牆、圓柱、樑、天花、天台板、行車道或樓板及其他結構組件上或其任何部分獨有使用和享用的附加服務的權利，及「該土地」或「該土地」上的發展項目任何部分的相關通行權，不論是否連同受僱人、工人及其他人，及不論是否攜帶工具、設備、裝備、機械、物料或汽車；以及

(J) 「署長」視為必要或恰當的其他權利、特權及地役權。

(ii)「公契」的有關條文

除在本售樓說明書另有定義外，下述用詞的意義將等同於「公契」內該用詞的意義。請參閱「公契」。

i. 根據「公契」第一節第1條，以下用詞各自的定義如下：

「政府房舍」指包含現已或將會按照「該租契」條款第3.21(a)條於「該土地」及「屋苑」提供或建造的(i)「長者鄰舍中心」、(ii)「嚴重肢體傷殘人士綜合支援服務」、(iii)「特殊幼兒中心」及(iv)「早期教育及訓練中心」(包括該處按照「該租契」第3.21條之(b)及(c)款的規定進行的改

(F) the free and uninterrupted rights of way to and from the Government Accommodation as may be required by the Director;

(G) the exclusive right to install, erect, exhibit, display, maintain, repair, remove and renew signs and advertisements on the walls, columns and other structural elements of, within, around and on the boundary of the Government Accommodation or any part thereof as FSI shall deem fit and the right of access over the said land or any part thereof or any part of the development thereon with or without servants, workmen or others and with or without tools, plant, equipment, machinery, material or motor vehicles for the purposes of inspecting, installing, erecting, exhibiting, displaying, maintaining, repairing, removing and renewing such signs and advertisements;

(H) the right of access to the lighting conduits, such fire services, ventilation and other services, facilities, installations, fixtures, ancillary works, plants and materials fixed, on, in or to the roof slabs, walls and other structural elements of the Government Accommodation;

(I) the right to alter and run additional services to serve and benefit exclusively the Government Accommodation or any part thereof on the walls, columns, beams, ceilings, roof slabs, carriageway or floor slabs and other structural elements of, in, around, within, above and below the Government Accommodation and the related right of access over the said land or any part of the development on the said land with or without servants, workmen or others and with or without tools, plant, equipment, machinery, material or motor vehicles; and

(J) such other rights privileges and easements as may be deemed necessary or desirable by the Director.

(ii) Relevant Provisions of the Deed of Mutual Covenant ("DMC")

Unless otherwise defined in this sales brochure, capitalised and other terms used in the following shall have the same meaning of such terms used in the DMC. Please refer to the DMC for reference.

i. Pursuant to Clause 1 of Section I of the DMC, the following terms shall have the respective definitions as stated below:

"Government Accommodation" shall mean such part or parts of the Estate comprising (i) NEC; (ii) ISS; (iii) SCCC and (iv) EETC provided or constructed or to be provided or constructed within the said land and the Estate in accordance with Clause 3.21(a) of the said lease (including such alterations, variations, additions, extensions or improvements thereto carried out pursuant to sub-clauses (b) and (c) of Clause 3.21 of the said lease and together with any other areas, facilities, services and installations exclusive thereto from time to time as the Director of Lands may at his absolute discretion determine (whose determination shall be conclusive and binding on the Owners)) (such Government Accommodation, for identification purpose only, is/are shown coloured indigo on pages 1 and 2 of the plan(s) annexed to the DMC, the accuracy of such plan(s) has been certified by the Authorized Person);

動、改建、加建、擴建或改善工程，以及地政總署署長完全酌情決定（其決定為最終決定及對所有「業主」具約束力）為該處不時專用的任何其他地方、設施、服務及裝置）的該或該等「屋苑」之部分（該等「政府房舍」現於「公契」所夾附並經認可人士核實為準確的圖則第1及2頁以靛藍色顯示，以資識別）；

「該等項目」指「該租契」條款第3.21(i)(i)條中闡明定義的「該等項目」，包括(i)不是獨立式的「政府房舍」的外部飾面，及所有牆、柱、橫樑、天花板、天台樓板、行車道或樓板，以及任何其他「政府房舍」的、以內、周圍、內部、上方及以下的其他結構性元素；(ii)所有為「政府房舍」及「該土地」上的發展項目的餘下部分而設的升降機、自動梯及樓梯；(iii)構成為「政府房舍」及「該土地」上的發展項目的餘下部分而設的系統的一部分的所有屋宇設施裝置、設備及裝備(包括但不限於可攜及不可攜的防火裝置裝備)；及(iv)所有為「政府房舍」及「該土地」上的發展項目的餘下部分而設的公共部分及設施；

「長者鄰舍中心」指「該租契」條款第3.21(a)(i)條具體指明的長者鄰舍中心，並構成「政府房舍」的一部分；

「嚴重肢體傷殘人士綜合支援服務中心」指「該租契」條款第3.21(a)(ii)條具體指明的嚴重肢體傷殘人士綜合支援服務中心連同一個供一輛汽車上落客貨及停泊用途的停車位，並構成「政府房舍」的一部分；

「特殊幼兒中心」指「該租契」條款第3.21(a)(iii)條具體指明的特殊幼兒中心連同一個供一輛汽車上落客貨及停泊用途的停車位，並構成「政府房舍」的一部分；

「早期教育及訓練中心」指「該租契」條款第3.21(a)(iv)條具體指明的早期教育及訓練中心，並構成「政府房舍」的一部分。

ii. 根據「公契」第四節第16(a)條，「政府房舍」須由「政府房舍」的「業主」管理及保養。

iii. 根據「公契」第四節第16(b)條，儘管「公契」第四節第16(a)條有所規定，「經理人」須按「政府房舍」的「業主」的要求，對「政府房舍」獨有使用的服務、設施及裝置進行保養。但是，「政府房舍」的「業主」須付還「經理人」於進行該保養所支付的費用，前提是除非及直至「經理人」已遞交費用估算連同證明文件及「政府房舍」的「業主」認為必需的任何其他相關資料，而「政府房舍」的「業主」須已書面批准該費用估算及「經理人」將進行的保養工程，否則不得進行該保養。然而，「經理人」為履行「公契」第四節第16(b)條下的責任所引致的費用及支出需與「管理支出」分開，而不得影響該「管理支出」包括其他「業主」應繳的「經理人報酬」。

"Items" shall mean the Items as defined in Clause 3.21(i)(i) of the said lease which shall include (i) the external finishes of the Government Accommodation which is not free standing and the structure of all walls, columns, beams, ceilings, roof slabs, carriageway or floor slabs and any other structural elements of, in, around, within, above and below such Government Accommodation; (ii) all lifts, escalators and stairways serving the Government Accommodation and the remainder of the Estate; (iii) all building services installations, plant and equipment (including, but not limited to, portable and non-portable fire services installation equipment) forming part of the system serving the Government Accommodation and the remainder of the Estate; and (iv) all other common parts and facilities serving the Government Accommodation and the remainder of the Estate;

"Neighbourhood Elderly Centre" or **"NEC"** shall mean the neighbourhood elderly centre referred to in Clause 3.21(a)(i) of the said lease, and which forms part of the Government Accommodation;

"Integrated Support Service Centre for Persons with Severe Physical Disabilities" or **"ISS"** shall mean the integrated support service centre for persons with severe physical disabilities with one space for the parking, loading and unloading of a motor vehicle as referred to in Clause 3.21(a)(ii) of the said lease, and which said Integrated Support Service Centre for Persons with Severe Physical Disabilities or ISS forms part of the Government Accommodation;

"Special Child Care Centre" or **"SCCC"** shall mean the special child care centre with one space for the parking, loading and unloading of a motor vehicle as referred to in Clause 3.21(a)(iii) of the said lease, and which forms part of the Government Accommodation;

"**Early Education and Training Centre"** or "**EETC"** shall mean the early education and training centre referred to in Clause 3.21(a)(iv) of the said lease, forming part of the Government Accommodation.

ii. Pursuant to Clause 16(a) of Section IV of the DMC, the Government Accommodation shall be managed and maintained by the Owner of the Government Accommodation.

iii. Pursuant to Clause 16(b) of Section IV of the DMC, notwithstanding Clause 16(a) of Section IV of the DMC above, upon the request of the Owner of the Government Accommodation, the Manager shall undertake the maintenance of services, facilities and installations serving exclusively the Government Accommodation, provided that the Owner of the Government Accommodation shall reimburse the Manager with the costs expended in carrying out such maintenance, on condition that the maintenance shall not be carried out unless and until the Manager shall have submitted an estimate of costs together with supporting documents and any other relevant information that the Owner of the Government Accommodation considers necessary, and the Owner of the Government Accommodation shall have approved in writing the estimated costs and the maintenance work to be carried out by the Manager, and PROVIDED ALWAYS THAT the costs and expenses incurred by the Manager in carrying out the duties under Clause 16(b) of Section IV of the DMC shall be separated from the Management Expenses and shall not affect the Management Expenses including the manager's remuneration payable by the other Owners.

iv. 根據「公契」第四節第17條，「該等項目」須由「經理人」管理及保養。所有「業主」（作為「政府房舍」的「業主」的「該法團」除外）須就「經理人」未有管理及保養「該等項目」所引致或造成的一切任何責任、損害、支出、索償、開支、費用、要求、法律行動及訴訟向「該法團」及政府作出彌償，並使「該法團」及政府持續得到彌償。

v. 根據「公契」第六節第38(d)條，儘管「公契」第六節第38條之(a)款有所規定，由「政府房舍」被轉讓予「該法團」的日期（包括當天）或由政府取得「政府房舍」或其有關部分之空置管有的日期（包括當天）開始（以較早發生者為準），「該法團」須支付相關月費。然而，就直接服務、惠及或供該處的佔用人、其受僱人、承辦商、代理或訪客使用的「政府房舍」的設施、服務及「該等項目」而言，該費用的金額由政府產業署署長或地政總署署長就此提名的人士決定，但該責任不得超過根據「政府房舍」管理份數佔「屋苑」整體管理份數的比例計算的百分比。但是，除非及直至該金額已獲政府產業署署長或其代名人或其它由地政總署署長就此提名的人士書面批准，否則「該法團」不對任何月費承擔繳付責任。為免存疑，「公契」第六節第48(b)條並不受「公契」所述的任何事項影響。

vi. 根據「公契」第六節第48(a)條，儘管「公契」另有規定，「該法團」作為「政府房舍」的「業主」不須繳付以下費用：

(i) 「公契」第六節第35(a)條所指的管理費按金；

(ii) 「公契」第六節第35(b)條所指的「特別基金」及資本設備基金（如有），事前經由政府產業署署長或「署長」就此提名的其他人士決定及批准而確實服務「政府房舍」或由該處佔用人、其受僱人、承辦商、代理或訪客使用的設施及服務相關的資本償還除外，但該責任不得超過根據「政府房舍」管理份數佔「屋苑」整體管理份數的比例計算的百分比；

(iii) 「政府房舍」相關的保險保費；

(iv) 裝修泥頭清理費；

(v) 逾期或未繳管理及保養費的利息、罰款、收取管理及保養費之手續費等；

或同類付款。

vii. 根據「公契」第六節第48(b)條，為免存疑，除「該租契」條款第3.22(a)(ii)(I)條另有規定外，「該法團」作為「政府房舍」的「業主」，沒有責任攤付與「該土地」及「屋苑」其餘部分有關的任何管理及保養費用，尤其是沒有責任繳付「屋苑」的「公用地方與設施」及「該等項目」引起的任何管理及保

iv. Pursuant to Clause 17 of Section IV of the DMC, the Items shall be managed and maintained by the Manager. All Owners (save and except F.S.I. as the Owner of the Government Accommodation) shall indemnify and keep indemnified F.S.I. and the Government for all liabilities, damages, expenses, claims, costs, charges, demands, actions and proceedings of whatsoever nature arising out of or as a consequence of the failure of the Manager to manage and maintain the Items.

v. Pursuant to Clause 38(d) of Section VI of the DMC, notwithstanding the provisions of sub-clause (a) of Clause 38 of Section VI of the DMC, as from and including the date of assignment of the Government Accommodation to F.S.I., or the date of taking over of vacant possession by the Government of the Government Accommodation or the relevant part or parts thereof, whichever is the earlier, F.S.I. shall pay the monthly sum in respect thereof PROVIDED THAT the sum shall be as determined by the G.P.A. or such other person nominated by the Director of Lands for this purpose in respect of the facilities and services and the Items which directly serve or benefit the Government Accommodation or are used by the occupier thereof, its servants, contractors, agents or visitors but which liability shall not exceed the proportion that the number of Management Shares of the Government Accommodation bears to the total number of Management Shares of the Estate PROVIDED FURTHER THAT F.S.I. shall incur no liability for payment of any monthly sum unless and until the amount of the same shall have first been approved in writing by G.P.A. or its nominee or such other person nominated by the Director of Lands for this purpose. For the avoidance of doubt, nothing in the DMC shall prejudice Clause 48(b) of Section VI of the DMC.

vi. Pursuant to Clause 48(a) of Section VI of the DMC, notwithstanding anything to the contrary contained in the DMC, F.S.I. as the Owner of the Government Accommodation shall not be liable for any payment of:

(i) management fee deposits referred to in Clause 35(a) of Section VI of the DMC;

(ii) contribution to the Special Fund referred to in Clause 35(b) of Section VI of the DMC and capital equipment fund (if any) except for the reimbursement of capital expenditure, as shall first be determined and approved by G.P.A. or its nominee or such other person nominated by the Director of Lands for this purpose, in respect of the facilities and services which actually serve the Government Accommodation or are used by the occupier thereof, its servants, contractors, agents or visitors but which liability shall not exceed the proportion that the number of Management Shares of the Government Accommodation bears to the total number of Management Shares of the Estate;

(iii) insurance premium in respect of the Government Accommodation;

(iv) debris removal fees;

(v) interest, penalty, collection charges, etc. on late or default in payment of management fees and maintenance charges;

or payment of a like nature.

vii. Pursuant to Clause 48(b) of Section VI of the DMC, for the avoidance of doubt, save and except as provided under Clause 3.22(a)(ii)(I) of the said lease, F.S.I. as the Owner of the Government Accommodation shall not be liable to contribute towards any management and maintenance charges in respect of the remainder of the said land and the Estate and, in particular, shall not be liable for payment

養費用。「該法團」作為「政府房舍」的「業主」亦獲豁免遵從任何裝修規則（如有）及使用房委會（作為第一業主）或經理人提名的任何保養或服務承辦商。

viii. 根據「公契」第七節第63(a)條，儘管「公契」另有規定，「該法團」作為「政府房舍」的「業主」不須就「該土地」及「屋苑」的任何其他部分（不論是「公用地方與設施」或「該等項目」或其它）的攤付費用承擔責任，並無須對政府產業署署長或地政總署署長就此提名的人士認為並非直接服務或以其它方式直接惠及「政府房舍」的設施或服務的提供承擔責任。此外，「政府房舍」的「業主」無須對「該土地」及「屋苑」的任何其他部分（不論是「公用地方與設施」或「該等項目」或其它）的任何管理及保養費用承擔繳付的責任，除非及直至「政府房舍」的「業主」，或政府產業署署長或其代名人或地政總署署長就此提名的人士（倘若「政府房舍」的「業主」為「該法團」）事先書面批准該金額，惟「政府房舍」的「業主」的該責任不得超過「政府房舍」的「管理份數」數目對「屋苑」的總管理份數之比例。

ix. 根據「公契」附表二A部第4條：

(a) 「公契」豁免並保留給政府、地政總署署長及在「政府房舍」根據「該租契」條款第3.21(d)條轉讓予「該法團」（就「公契」附表二A部第4(a)條而言，不包括其受讓人）後，全權及可無須經「房委會」、「業主」及「經理人」贊同或批准或同意行使「公契」附表二A部第4(a)條所載的權利，即以其絕對酌情權於任何時候更改或修訂「政府房舍」或其任何部分的使用或總樓面面積，以及攜帶或不攜帶工具、設備、機械及機器進行建築工程（包括但不限於地政總署署長認為有需要進行的改建、變更、加建、擴展或改善工程）。政府、地政總署署長及「該法團」不須對地政總署署長或「該法團」為行使「公契」附表二A部第4(a)條賦予的權力所導致的或附帶的對「房委會」或任何「業主」或「經理人」造成或使其蒙受的任何損失、損害、滋擾或干擾負上任何責任，而「房委會」或任何「業主」亦不得就任何損失、損害、滋擾或干擾向政府、地政總署署長或「該法團」提出任何索償。

(b) 除上述的權利及特權外，「該法團」、其承租人、租戶、被許可人、獲其授權的人士及「政府房舍」現任業主及佔用人擁有下列權利、特權及地役權的權益：

(i) 「政府房舍」於任何時候享有庇護、支撐物及保護的權利；

of any management and maintenance charges whatsoever incurred in respect of the Common Areas and Facilities of the Estate and the Items. F.S.I. as the Owner of the Government Accommodation is also further exempted from any fitting out regulations (if any) and using any maintenance or service contractors nominated by the Authority (as first owner) or the Manager.

viii. Pursuant to Clause 63(a) of Section VII of the DMC, notwithstanding anything to the contrary herein contained in the DMC, F.S.I. as the Owner of the Government Accommodation shall have no liability for any contribution towards any management and maintenance charges for any other part of the said land and the Estate (whether the Common Areas and Facilities or the Items or otherwise) or for the provision of facilities or services which do not, in the opinion of G.P.A. or the person nominated by the Director of Lands for this purpose, directly serve or otherwise directly benefit the Government Accommodation, and the Owner of the Government Accommodation shall incur no liability for payment of any management and maintenance charges for any other part of the said land and the Estate (whether Common Areas and Facilities or the Items or otherwise) payable by it under the terms of the DMC, unless and until the amount of the same shall have first been approved in writing by the Owner of the Government Accommodation or, where the Owner of the Government Accommodation is F.S.I., by the G.P.A. or its nominee or such other person nominated by the Director of Lands for this purpose PROVIDED THAT such liability of the Owner of the Government Accommodation shall not exceed the proportion that the number of Management Shares of the Government Accommodation bears to the total number of Management Shares of the Estate.

ix. Pursuant to Clause 4 in Part A of the Second Schedule to the DMC:

(a) There is excepted and reserved unto the Government, the Director of Lands and, in addition, upon assignment of the Government Accommodation to F.S.I. pursuant to Clause 3.21(d) of the said lease, F.S.I. (which, for the purpose of Clause 4(a) in Part A of the Second Schedule to the DMC, shall not include its assigns) the absolute right to alter or vary, in his absolute discretion at any time, the use or the gross floor area of the Government Accommodation or any part thereof and to carry out such building works including, but not limited to, alterations, variations, additions, extensions or improvements as may be considered necessary by the Director of Lands, with or without tools, equipment, plant and machinery, to effect the right as aforesaid in Clause 4(a) in Part A of the Second Schedule to the DMC, without having to obtain the concurrence or approval or consent of the Authority, the Owners or the Manager. The Government, the Director of Lands and F.S.I. shall have no liability for and no claim whatsoever shall be made against the Government, the Director of Lands or F.S.I. in respect of any loss, damage, disturbance or nuisance whatsoever caused to or suffered by the Authority or any Owners or the Manager arising out of or incidental to the exercise by the Director of Lands or F.S.I. of the right referred to in Clause 4(a) in Part A of the Second Schedule to the DMC.

(b) In addition to the above rights and privileges, F.S.I., its lessees, tenants, licensees and persons authorized by it and the owner and occupier for the time being of the Government Accommodation shall have the benefit of the following rights, and privileges and easements:

(i) the right at all times of shelter, support and protection for the Government Accommodation;

(ii) 讓氣體、電力、食水、污水、空調、電話及所有其他服務任何時候自由透過現時或於批租年期內於「該土地」的任何部分及「屋苑」任何部分鋪設或越過的溝渠、污水管、排水渠、排煙管、管線、管道、水道、電纜、水管、電線及其他導體往來「政府房舍」的權利；

(iii) 於任何時候全權酌情，自費改動、改道、更改、重鋪或還原任何「政府房舍」或其任何部分專用的服務與設施(下稱「政府房舍服務」)的權利，而無須向「房委會」或「業主」支付任何費用，亦無須獲得「經理人」或「業主」任何批准或同意。但是，在進行上述「政府房舍服務」的改動、改道、更改、重鋪或還原工程時必須採取適當及足夠的預防措施，以確保不會對「該土地」內或其部分服務「屋苑」所有非「政府房舍」部分的服務及設施造成損壞；

(iv) 為正確地使用及享用「政府房舍」或其任何部分的目的通行及再通行、進出、往返及使用「公用地方與設施」或其任何部分，以及使用和享用「該土地」或其任何部分內或「屋苑」或其任何部分的任何公用設施的權利；

(v) 在所有合理時間不論是否連同測量師、承辦商、工人及其他人，及不論是否攜帶工具、機動汽車、設備、裝備、物料及機器進入「該土地」或「屋苑」的任何部分的權利，以便於「政府房舍」或其任何部分擴建或進行保養、維修、加建、改建及其他工程，以及進行「政府房舍服務」或其任何部分的保養、維修、增建、改建、改道、更改、重鋪及還原工程或其他工程；

(vi) 享有暢通無阻進出「政府房舍」的通行權；

(vii) 在「政府房舍」或其任何部分內、周圍及邊界上的牆、圓柱及其他結構組件安裝、建設、展示、陳列、保養、維修、拆除和更新招牌及廣告的專有權，及進入「該土地」或其任何部分或「屋苑」任何部分的通行權，不論是否連同受僱人、工人及其他人，及不論是否攜帶工具、機動汽車、設備、裝備、機械及物料，以便檢驗、安裝、建設、展示、陳列、保養、維修、拆除及更新此等招牌及廣告；

(viii) 固定於「政府房舍」的天台樓板、牆及其他結構組件上面、裏面或表面的照明管道、消防、通風及其他服務、設施、裝置、固定裝置、輔助工程，設備及物料的通行權；

(ii) the right at all times of free passage and running of gas, electricity, water, sewage, air-conditioning, telephone and all other services from and to the Government Accommodation through the gutters, sewers, drains, flues, conduits, ducts, watercourses, cables, pipes, wires and other conducting media now or during the said term of years laid on or running through any part of the said land and any part of the Estate;

(iii) the right, at its own cost, to alter, divert, vary, relay or reinstate any of the services and facilities serving exclusively the Government Accommodation or any part thereof (hereinafter referred to as "the Government Accommodation Services") at any time, at its absolute discretion, without any charge by the Authority or the Owners and without having to obtain the approval or consent of the Manager or the Owners PROVIDED THAT proper and adequate care and precaution shall be taken during any alteration, diversion, variation, relaying or reinstatement works of the Government Accommodation Services so as to ensure that no damage is caused to those services and facilities within the said land or any part thereof and serving all those parts of the Estate other than the Government Accommodation;

(iv) the right to go, pass and repass over and along and to use the Common Areas and Facilities or any part thereof in connection with the proper use and enjoyment of the Government Accommodation or any part thereof and to use and receive the benefit of any common facilities within the said land or any part thereof or any part of the Estate;

(v) the right at all reasonable times, with or without surveyors, contractors, workmen and others and with or without tools, motor vehicles, plant, equipment, material and machinery, to enter upon the said land or any part of the Estate for the purposes of extending or carrying out maintenance, repair, addition, alteration and other works to the Government Accommodation or any part thereof and maintenance, repair, addition, alteration, diversion, variation, relaying and reinstatement works or other works to the Government Accommodation Services or any part thereof;

(vi) the free and uninterrupted rights of way to and from the Government Accommodation;

(vii) the exclusive right to install, erect, exhibit, display, maintain, repair, remove and renew signs and advertisements on the walls, columns and other structural elements of, within, around and on the boundary of the Government Accommodation or any part thereof as F.S.I. shall deem fit and the right of access over the said land or any part thereof or any part of the Estate, with or without servants, workmen and others and with or without tools, motor vehicles, plant, equipment, machinery and material, for the purposes of inspecting, installing, erecting, exhibiting, displaying, maintaining, repairing, removing and renewing such signs and advertisements;

(viii) the right of access to the lighting conduits, such fire services, ventilation and other services, facilities, installations, fixtures, ancillary works, plants and materials fixed on, in or to the roof slabs, walls and other structural elements of the Government Accommodation;

(ix) 改變及運行「政府房舍」或於「政府房舍」內、周圍、其範圍內、其上及其下的牆、圓柱、樑、天花、天台板、行車道或樓板及其他結構組件上或其任何部分獨有使用和享用的附加服務的權利，及「該土地」或「屋苑」任何部分的相關通行權，不論是否連同受僱人、工人及其他人，及不論是否攜帶工具、機動汽車、設備、裝備、機械及物料；以及

(x) 根據「該租契」條款第3.22(a)(ii)(III)(J)條，地政總署署長視為必要或恰當的其他權利、特權及地役權。

(c) 任何根據「公契」附表二A部第4條行使的地役權、權利及特權不須受限於「經理人」或「業主」的任何准許、批准或同意。

x. 根據「公契」附表二B部第(a)條，各「不分割份數」及持有、使用、佔用和享用「屋苑」的有關部分的專有權是受限於「經理人」在發出通知書(緊急情況除外)後，於所有合理時間單獨或聯同代理人、測量師、工人及其他人等進入「屋苑」任何部分，以執行大廈或其任何部分(包括該「單位」本身)或任何「公用地方與設施」或上述範圍內任何污水渠、排水渠、水道、電纜、水管、泵、水缸、電線或服務設施或任何使用於或安裝於「該土地」及「屋苑」或其任何部分的全權及特權，以作為供「該土地」及「屋苑」享用的部分設施而非作為個別「業主」的個人目的或享受的任何其他器具、設備或服務之必要維修工程，或以消減任何上述範圍內的危害或滋擾，以及概括而言為行使「本公契」或「副公契」(如有)訂明「經理人」具有的權力與職能。然而，「經理人」施工時必須盡量減低滋擾，如有任何損壞則立刻修復，倘若因「經理人」、其工人、承辦商及代理人之疏忽、蓄意或刑事行為造成任何損壞「經理人」必須自費修妥，並須盡量減低滋擾。但是，如「經理人」根據「公契」附表二B部第(a)條行使其進入權只為保養及維修的目的進入有關「政府房舍」或其任何部分，「經理人」須獲得「該法團」或政府產業署署長或其代名人的事先批准(緊急狀況除外)，「經理人」須對任何由該進入對「政府房舍」造成的損壞而產生的所有費用及支出負責。

2. 排水渠及渠道

(i) 批地文件的有關條文

i 「該租契」條款第4.10條訂明：

(a) 「承租人」須自費建造與保養不論在「該土地」邊界內或政府土地上「署長」認為需要的排水渠及渠道，以便截斷與引導所有落在或流經「該土地」的暴雨或雨水到最接近的水道、集水井、渠道或政府雨水渠，以令「署長」滿意。「承租人」須對上述暴雨或雨水造成的任何損

(ix) the right to alter and run additional services to serve and benefit exclusively the Government Accommodation, or any part thereof, on the walls, columns, beams, ceilings, roof slabs, carriageway/floor slabs and other structural elements of, in, around, within, above and below the Government Accommodation and the related right of access over the said land or any part of the Estate, with or without servants, workmen and others and with or without tools, motor vehicles, plant, equipment, machinery and material; and

(x) such other rights, privileges and easements as may be deemed necessary or desirable by the Director of Lands as provided in Clause 3.22(a)(ii)(III)(J) of the said lease.

(c) Any exercise of the easements, rights and privileges under Clause 4 in Part A of the Second Schedule to the DMC shall not be subject to any permission, approval or consent of the Manager or the Owners.

x. Pursuant to Clause (a) in Part B of the Second Schedule to the DMC, each of the Undivided Shares and the exclusive right to hold use occupy and enjoy such part of the Estate is held subject to full right and privilege for the Manager, with or without agents, surveyors, workmen and others, at all reasonable times on notice (except in case of emergency) to enter into and upon any part of the Estate for the purposes of carrying out necessary repairs to the building or any part or parts thereof (including the Unit itself), or any of the Common Areas and Facilities, or any sewers, drains, water-courses, cables, pipes, pumps, tanks, wires or services therein, or any other apparatus, equipment or services used or installed for the benefit of the said land and the Estate or any part or parts thereof as part of the amenities thereof and not by any individual Owner for his own purposes or enjoyment, or to abate any hazard or nuisance and, generally, for the purpose of exercising the powers and functions of the Manager under the DMC or Sub-DMC (if any), causing as little disturbance as possible, and forthwith making good any damage caused thereby PROVIDED THAT the Manager shall, at its own costs and expenses, make good any damage caused thereby and shall be liable for the negligent, wilful or criminal acts of the Manager and its workmen, contractors and agents, and ensure that the least disturbance is caused AND PROVIDED FURTHER THAT, in case of the Manager exercising its right of entry into the Government Accommodation or any part thereof pursuant to Clause (a) in Part B of the Second Schedule to the DMC, such entry shall be for maintenance and repair purposes only and the Manager requires the prior approval of F.S.I. or G.P.A. or its nominee for any such entry (except in case of emergency) and the Manager shall be liable for all costs and expenses incurred for any damage caused to the Government Accommodation by such entry.

2. DRAINS AND CHANNELS

(i) Relevant Provisions of the Land Grant

i. Clause No. 4.10 of the said lease stipulates that:

(a) The Lessee shall construct and maintain at its own expense and to the satisfaction of the Director such drains and channels, whether within the boundaries of the said land or on Government land, as the Director may consider necessary to intercept and convey into the

壞或滋擾而導致（不論是直接及間接導致的）或與上述暴雨或雨水造成的任何損壞或滋擾相關的一切責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何或如何引致）自行負責並向政府作出彌償，並使政府持續得到彌償。

(b) 連接「該土地」的任何排水渠和污水渠至政府的雨水渠及污水渠（如已建成及已啟用）的工程可由「署長」進行，但「署長」毋須就因此產生的任何損失或損害對「承租人」負責。「承租人」須在被要求時向政府支付上述連接工程的費用，或者該等連接工程亦可由「承租人」自費進行，並使「署長」滿意。在該種情況下，上述連接工程的任何一段若在政府土地內修建，必須由「承租人」自費保養，直至按要求時由「承租人」移交給政府，由政府出資負責以後的保養。「承租人」須在被要求時向政府支付有關上述連接工程的技術審核之費用。若「承租人」未能保養上述在政府土地內修建的任何一段連接工程，「署長」可進行他認為必要的保養工程，「承租人」須在被要求時向政府支付該等工程的費用。

(ii) 「公契」的有關條文

i. 請參閱上文第A1(ii)x段。

ii. 根據「公契」第四節第20條第(j)項(1)款及(2)款，「經理人」有權力、職能和責任保持以下設施運作良好及修繕妥當：

(1) 現時或此後任何時間位於「屋苑」或相鄰土地中、下或內而乃完全或局部供「屋苑」各「業主」及佔用人共用的所有水泵、泵房、水缸、喉管、水管、污水渠、廁所、排水渠、水道、電纜、電線、器具與設備；

(2) 不論位於「該土地」邊界範圍內、相鄰土地上或政府土地上，按「該租契」規定須由「業主」建造和維修以令地政總署署長滿意的排水渠和渠道。

iii. 根據「公契」第四節第20條第(r)項，「經理人」有權力、職能和責任採取一切必要或適當的措施促使「業主」實施「該租契」，特別是按「該租契」規定並且（如適用）以令地政總署署長、渠務署署長或其他政府部門(視情況而定)滿意的方式視察、保養、維修、拆卸、清除、修復、豎立或興建「該土地」和任何毗鄰或毗連政府土地或出租土地內（如適用）的所有土地、「該租契」條款第3.17(a)條要求於「該土地」提供的露天空間、斜坡、斜坡處理工程、擋土結構、護土牆及其他承托物、保護物、排水、附屬及其他工程和構築物。

nearest stream-course, catchpit, channel or Government storm-water drain all storm-water or rain-water falling or flowing on to the said land, and the Lessee shall be solely liable for and shall indemnify and keep indemnified the Government from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly and indirectly out of or in connection with any damage or nuisance caused by such storm-water or rain-water.

(b) The works of connecting any drains and sewers from the said land to the Government storm-water drains and sewers, when laid and commissioned, may be carried out by the Director who shall not be liable to the Lessee for any loss or damage thereby occasioned and the Lessee shall pay to the Government on demand the cost of such connection works. Alternatively, the said connection works may be carried out by the Lessee at its own expense to the satisfaction of the Director and in such case any section of the said connection works which is constructed within Government land shall be maintained by the Lessee at its own cost and upon demand be handed over by the Lessee to the Government for future maintenance thereof at the expense of the Government and the Lessee shall pay to the Government on demand the cost of the technical audit in respect of the said connection works. The Director may, upon failure of the Lessee to maintain any section of the said connection works which is constructed within Government land, carry out such maintenance works as he considers necessary and the Lessee shall pay to the Government on demand the cost of such works.

(ii) Relevant Provisions of the DMC

i. Please see paragraph A1(ii)x above.

ii. Pursuant to Clauses 20(j)(1) and 20(j)(2) of Section IV of the DMC, the Manager shall have the powers, functions and obligations to keep in good repair and condition:

(1) all water pumps, pumphouses, tanks, mains pipes, sewers, lavatories, drains water-courses, cables, wires, apparatus and equipment which are now or may at any time hereafter be in under or within the Estate or the land adjacent thereto which are wholly or partly for the common use of the Owners and occupiers of the Estate;

(2) the drains and channels, whether within the boundaries of the said land or the land adjacent thereto or on Government land, which the Owners are required by the said lease to construct and maintain to the satisfaction of the Director of Lands.

iii. Pursuant to Clause 20(r) of Section IV of the DMC, the Manager shall have the powers, functions and obligations to take all steps necessary or expedient for compliance by the Owners with the said lease and, in particular, to inspect, maintain, repair, demolish, remove, reinstate, erect or construct, in accordance with the provisions of the said lease and (if applicable) to the satisfaction of the Director of Lands, Director of Drainage Services or other Government departments (as the case may be), all land, the open space(s) required to be provided under Clause 3.17(a) of the said lease, slopes, slope treatment works, earth-retaining structures, retaining walls and other support, protection, drainage, ancillary and other works and structures within the said land and also any adjacent or adjoining Government or leased land (if applicable).

iv. 根據「公契」第四節第20條第(az)項，「經理人」有權力、職能和責任以令地政總署署長滿意的方式建造和保養「該租契」條款第4.10(a)條所指的排水渠及渠道。

v. 根據「公契」第四節第20條第(ba)項，「經理人」有權力、職能和責任以令地政總署署長滿意的方式維持、保養及維修「該租契」條款第5.3(a)條所指的全部或任何雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道（包括總水喉管）。

vi. 根據「公契」第七節第54(a)(1)條第(iv)項，由「經理人」準備的周年財政預算的第一部分第一節應包括現已或將會為支撐「屋苑」而建造的地基、支柱及其他構築物（專為「住宅大廈」、「房屋委員會樓宇」或「政府房舍」而設者除外），以及位於「該土地」內或外專為「該土地」及／或「屋苑」提供服務（專為「住宅大廈」、「房屋委員會樓宇」或「政府房舍」而設者除外）或根據「該租契」規定需要維修的排水渠、溝渠、污水渠、水管、總水喉管和渠道及其他地方的維修費用與開支和所有其他費用與支出。

vii. 根據「公契」第七節第54(a)(1)條第(xix)項，由「經理人」準備的周年財政預算的第一部分第一節應包括製造、建造、修理和修改所有或任何「屋苑」或其任何與其它相鄰或毗鄰的樓宇共用的部分所需要的或所擁有的道路、巷道、行人道、渠道、籬笆及公用牆、化糞池、私人或公共污水渠及排水渠的成本及費用的合理份數及部分。

B 根據批地文件規定須由發展項目中的住宅物業的擁有人出資管理、營運或維持以供公眾使用的任何設施

公用事業設施或其他服務

(i) 批地文件的有關條文

i. 請參閱上文第A1(i)及A2(i)段。

ii. 「該租契」條款第5.3(a)及5.3(c)條訂明：

(a) 政府、任何毗連或鄰近土地或處所的承租人、租戶、佔用人和獲許可人或任何其他獲得任何上述人正式授權的人士均獲保留權利讓氣體、電力、淡水或鹹水、污物、污水、空氣、煙或其他排出物、電話、水、公用事業設施及其他服務，藉通過或經過「該土地」或其上面或下面或其任何部分的雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道（包括總水喉管）以往來該等毗連或鄰近土地或處所。

iv. Pursuant to Clause 20(az) of Section IV of the DMC, the Manager shall have the powers, functions and obligations to construct and maintain the drains and channels referred to in Clause 4.10(a) of the said lease, to the satisfaction of the Director of Lands.

v. Pursuant to Clause 20(ba) of Section IV of the DMC, the Manager shall have the powers, functions and obligations to uphold, maintain and repair all or any of the gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) referred to in Clause 5.3(a) of the said lease, to the satisfaction of the Director of Lands.

vi. Pursuant to Clause 54(a)(1)(iv) of Section VII of the DMC, the first section of the first part of the annual budget prepared by the Manager shall cover the costs and expenses of maintaining and all other expenses and outgoings payable in respect of the foundations, columns and other structures constructed or to be constructed for the support of the Estate (excluding those exclusively serving the Residential Blocks, the HA Accommodation or the Government Accommodation) and the drains, nullahs, sewers, pipes, watermains and channels and such other areas whether within or outside the said land serving the said land and/or the Estate (excluding those serving exclusively the Residential Blocks, the HA Accommodation or the Government Accommodation), or that are required to be maintained under the said lease.

vii. Pursuant to Clause 54(a)(1)(xix) of Section VII of the DMC, the first section of the first part of the annual budget prepared by the Manager shall cover the expenses for a reasonable share and proportion for and towards the costs and charges of making, building, repairing and amending all or any roads, lanes, pavements, channels, fences and party walls, cesspools, private or public sewers and drains requisite for or in or belonging to the Estate or any part thereof in common with other premises near or adjoining thereto.

B Any Facilities that are Required under the Land Grant to be Managed, Operated or Maintained for Public Use at the Expense of the Owners of the Residential Properties in the Development

UTILITY OR OTHER SERVICES

(i) Relevant Provisions of the Land Grant

i. Please see paragraphs A1(i) and A2(i) above.

ii. Clauses Nos. 5.3(a) and 5.3(c) of the said lease stipulate that:

(a) There is reserved unto the Government and the lessees, tenants, occupiers and licensees of any adjoining or neighbouring land or premises or any other persons duly authorized by any of them the right of passage of gas, electricity, fresh or salt water, soil, drainage, air, smoke or other effluent, telephone, water, utility, and other services to and from such adjoining or neighbouring land or premises through such gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) passing along, through, over, upon, under or in the said land or any part thereof.

(c) 「承租人」須以令「署長」滿意的方式自費維持、保養及維修「該租契」條款第5.3(a)條所指的所有及任何雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道(包括總水喉管)。

(ii)「公契」的有關條文

i. 請參閱上文第A1(ii)i至A1(ii)viii及A2(ii)段。

ii. 根據「公契」第十一節第98條,「業主」須按「該租契」條款第5.3(c)條以令地政總署署長滿意的方式自費維持、保養及維修所有及任何雨水渠、水管、電線、電纜、污水渠、排水渠、溝渠、暗渠、管道、煙道、導管、水路或水道(包括總水喉管)。

C 根據批地文件規定須由該項目中的住宅物業的擁有人出資管理、營運或維持以供公眾使用的任何休憩用地

不適用。

D 該項目所位於的土地中為施行《建築物(規劃)規例》(第123章,附屬法例F)第22(1)條而撥供公眾用途的任何部分

不適用。

(c) The Lessee shall at its own expense uphold, maintain and repair all and any of the said gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) referred to in Clause No. 5.3(a) of the said lease, all to be done to the satisfaction of the Director.

(ii) Relevant Provisions of the DMC

i. Please see paragraphs A1(ii)i to A1(ii)viii and A2(ii) above.

ii. Pursuant to Clause 98 of Section XI of the DMC, the Owners shall, at their own expense, uphold, maintain and repair, to the satisfaction of the Director of Lands, all and any of the gutters, pipes, wires, cables, sewers, drains, nullahs, culverts, ducts, flues, conduits, waterways or watercourses (including water mains) pursuant to Clause 5.3(c) of the said lease.


C Any Open Space that is Required under the Land Grant to be Managed, Operated or Maintained for Public Use at the Expense of the Owners of the Residential Properties in the Development

Not applicable.

D Any Part of the Land (on which the Development is Situated) that is Dedicated to the Public for the Purposes of Regulation 22(1) of the Building (Planning) Regulations (Cap. 123 sub. Leg. F)

Not applicable.

青富苑「該租契」附圖(摘錄)
Extract of Plan Annexed to the Lease of Ching Fu Court





圖例 NOTATION

	粉紅色加黑交叉斜線 Pink Cross-Hatched Black
	粉紅色加黑斜線 Pink Hatched Black
	粉紅色加黑斜線加黑斑點 Pink Hatched Black Stippled Black
	粉紅色加黑斑點 Pink Stippled Black
V	電纜 Cables
Blue	現存淡水水管 Existing Fresh Water Mains
R	現存鹹水水管 Existing Salt Water Mains
W.W.R.	水務工程專用範圍 Waterworks Reserve
NEW W.W.R.	新水務工程專用範圍 New Waterworks Reserve


政府屋宇—特殊幼兒中心及早期教育及訓練中心
Government Accommodation –
Special Child Care Centre and Early Education and Training Centre

地下低層1樓平面圖及部分平面圖
Lower Ground Floor 1 Floor Plan and Part Plan





指示圖 KEY PLAN





地下低層2樓樓梯出口部分平面圖
PART PLAN OF EXIT STAIR
AT LOWER GROUND FLOOR 2

比例尺 SCALE: 0 5 10 15 20 (米) (m)

政府屋宇—嚴重肢體傷殘人士綜合支援服務中心
Government Accommodation – Integrated Support Service Centre for Persons with Severe Physical Disabilities

地下低層2樓平面圖
Lower Ground Floor 2 Floor Plan







指示圖 KEY PLAN

政府屋宇—長者鄰舍中心
Government Accommodation – Neighbourhood Elderly Centre

地下低層3樓平面圖
Lower Ground Floor 3 Floor Plan



指示圖 KEY PLAN




政府屋宇—特殊幼兒中心及嚴重肢體傷殘人士綜合支援服務中心
Government Accommodation – Special Child Care Centre and Integrated Support Service Centre for Persons with Severe Physical Disabilities

地下平面圖
Ground Floor Plan

圖例 NOTATION

—·—·—	地界	Lot Boundary
	露天上落客貨停車位 (特殊幼兒中心及嚴重肢體傷殘人士綜合支援服務中心)	Open Parking, Loading/Unloading Spaces (Special Child Care Centre and Integrated Support Service Centre for Persons with Severe Physical Disabilities)
P	花槽	Planter



18 對買方的警告
Warning to Purchasers

1 在簽署買賣協議前，買方宜自行委聘屬意的律師行就與購買綠表置居計劃(綠置居)單位有關的事宜，例如轉讓限制、印花稅等，向買方提供意見，及代表他們辦理購買單位的手續。有關律師行能夠在購樓交易的每個階段向買方提供意見。

買方會在房委會的職員面前，簽署買賣協議。儘管如此，有關職員只會向買方詮釋買賣協議的內容，並見證其簽署買賣協議，但不會就買賣協議或與交易有關的任何其他事宜，向買方提供任何法律意見。

2 *如所購綠置居單位的售價為一百萬元以上*

買方必須自行委聘屬意的律師行代表他們辦理購買單位事宜。該律師行不可以是房委會為有關單位所委聘的律師行。

如所購綠置居單位的售價不超逾一百萬元

買方可：

- 自行委聘屬意的律師行代表他們辦理購買綠置居單位事宜；或
- 委聘房委會的代表律師行代表他們辦理購買綠置居單位事宜。

3 如買方自行委聘律師行代表他們辦理買賣交易，該律師行便能夠在購樓交易的每個階段向買方提供獨立意見，例如轉讓限制、印花稅等。買方須負責支付代表他們的律師的費用及開支。

如買方選擇委聘房委會的代表律師行代表他們辦理買賣交易，有關律師行將同時代表房委會及買方。買方須負責支付辦理買賣交易的所有律師的費用及開支。如買方委聘房委會的代表律師行同時代表買方行事，而房委會與買方之間出現利益衝突，房委會的代表律師行可能不能夠保障買方的利益；及買方可能要委聘一間獨立的律師行，如屬此情況，買方須支付的律師費用總數，可能高於如買方自一開始即委聘一間獨立的律師行便須支付的費用。

1 Before the signing of the ASP, all purchasers are urged to appoint a firm of solicitors of their choice to advise them on matters relating to the purchase of a flat under the GSH, such as alienation restrictions, stamp duties, etc., and to act for them in relation to their purchase of the flat. The firm of solicitors will be able to give advice to them at every stage of the purchase.

Although the purchasers will sign the ASP before the staff of the HA, the staff will only interpret the contents of the ASP to the purchasers and attest their signing of the ASP. The staff will not give the purchasers any legal advice on the ASP or any other matters in connection with the transaction.

2 *If the price of the GSH flat is over one million dollars*

Purchasers must appoint a separate firm of solicitors of their choice to act for them in relation to the transaction. Such firm of solicitors should not be the firm of solicitors appointed by the HA for the concerned flat.

If the price of the GSH flat does not exceed one million dollars

Purchasers may either:

- appoint a separate firm of solicitors of their choice to act for them in relation to the transaction; or
- appoint the HA's solicitors to act for them in relation to the transaction.


3 If the purchasers appoint a separate firm of solicitors to act for them in relation to the transaction, that firm of solicitors will be able to give independent advice, such as alienation restrictions, stamp duties, etc. to them at every stage of the purchase. The purchasers have to pay the legal costs and expenses of their own solicitors.


If the purchasers appoint the HA's solicitors to act for them in relation to the transaction, the solicitors will be acting jointly for the HA and the purchasers. Purchasers are required to pay all legal costs and expenses of the solicitors for completion of the sale and purchase. If a conflict of interest arises between the HA and the purchaser, HA's solicitors may not be able to protect the purchaser's interests; and the purchaser may have to instruct a separate firm of solicitors, in such case, the total solicitors' fees payable by the purchaser may be higher than the fees that would have been payable if the purchaser had instructed a separate firm of solicitors in the first place.

19 發展項目中的建築物的橫截面圖

Cross-section Plan of Building in the Development

A 座
Block A






指示圖 KEY PLAN


1. 毗連建築物的一段青衣路為香港主水平基準以上21.82米至23.23米。
   The part of Tsing Yi Road adjacent to the building is 21.82 metres to 23.23 metres above the Hong Kong Principal Datum.
2. 毗連建築物的一段青鴻路為香港主水平基準以上5.10米至5.60米。
   The part of Tsing Hung Road adjacent to the building is 5.10 metres to 5.60 metres above the Hong Kong Principal Datum.

圖例 NOTATION

—— - ——	發展項目的邊界	Boundary Line of the Development
▽	香港主水平基準 上高度(米)	Height (in metres) above the Hong Kong Principal Datum

A 座
Block A






指示圖 KEY PLAN


1. 毗連建築物的一段青衣路為香港主水平基準以上21.82米至23.23米。
   The part of Tsing Yi Road adjacent to the building is 21.82 metres to 23.23 metres above the Hong Kong Principal Datum.
2. 毗連建築物的一段青鴻路為香港主水平基準以上5.60米至6.20米。
   The part of Tsing Hung Road adjacent to the building is 5.60 metres to 6.20 metres above the Hong Kong Principal Datum.
3. 毗連建築物的一段青沙公路為香港主水平基準以上12.80米至16.30米。
   The part of Tsing Sha Highway adjacent to the building is 12.80 metres to 16.30 metres above the Hong Kong Principal Datum.

圖例 NOTATION

—— - ——	發展項目的邊界	Boundary Line of the Development
▽	香港主水平基準上高度(米)	Height (in metres) above the Hong Kong Principal Datum

B 座
Block B





指示圖 KEY PLAN

1. 毗連建築物的一段青衣路為香港主水平基準以上23.50米至24.65米。
   The part of Tsing Yi Road adjacent to the building is 23.50 metres to 24.65 metres above the Hong Kong Principal Datum.
2. 毗連建築物的一段青鴻路為香港主水平基準以上5.10米至5.62米。
   The part of Tsing Hung Road adjacent to the building is 5.10 metres to 5.62 metres above the Hong Kong Principal Datum.

圖例 NOTATION


—·—	發展項目的邊界	Boundary Line of the Development
▽	香港主水平基準上高度(米)	Height (in metres) above the Hong Kong Principal Datum

20 立面圖
Elevation Plan

A 座
Block A



南面立面圖"1"
South Elevation Plan "1"



指示圖 KEY PLAN

本圖所顯示的立面：

(1) 以2023年2月17日的該項目的經批准的建築圖則為基礎擬備；及

(2) 大致上與該項目的外觀一致。

The elevation shown on this plan:


(1) is prepared on the basis of the approved general building plans for the Development as of 17 February 2023; and

(2) is in general accordance with the outward appearance of the Development.

A 座
Block A



東面立面圖"2"
East Elevation Plan "2"



指示圖 KEY PLAN

本圖所顯示的立面：

(1) 以2023年2月17日的該項目的經批准的建築圖則為基礎擬備；及

(2) 大致上與該項目的外觀一致。


The elevation shown on this plan:

(1) is prepared on the basis of the approved general building plans for the Development as of 17 February 2023; and


(2) is in general accordance with the outward appearance of the Development

立面圖
Elevation Plan

B 座
Block B



東南面立面圖“1”
South East Elevation Plan “1”



指示圖 KEY PLAN

本圖所顯示的立面：

(1) 以2023年2月17日的該項目的經批准的建築圖則為基礎擬備；及


(2) 大致上與該項目的外觀一致。

The elevation shown on this plan:


(1) is prepared on the basis of the approved general building plans for the Development as of 17 February 2023; and

(2) is in general accordance with the outward appearance of the Development

B 座
Block B



東北面立面圖"2"
North East Elevation Plan "2"



指示圖 KEY PLAN

本圖所顯示的立面：

(1) 以2023年2月17日的該項目的經批准的建築圖則為基礎擬備；及

(2) 大致上與該項目的外觀一致。

The elevation shown on this plan:

(1) is prepared on the basis of the approved general building plans for the Development as of 17 February 2023; and

(2) is in general accordance with the outward appearance of the Development

21 發展項目中的公用設施的資料

Information on Common Facilities in the Development

		有上蓋遮蓋 Covered	無上蓋遮蓋 Uncovered	總面積 Total Area
住客會所（包括供住客使用的任何康樂設施） Residents' clubhouse (including any recreational facilities for residents' use)	平方米 sq.m.	不適用 Not applicable	不適用 Not applicable	不適用 Not applicable
	平方呎 sq.ft.	不適用 Not applicable	不適用 Not applicable	不適用 Not applicable
位於發展項目中的建築物的天台或在天台和最低一層住宅樓層之間的任何一層的、供住客使用的公用花園或遊樂地方（不論是稱為公用空中花園或有其他名稱） Communal garden or play area for residents' use on the roof, or on any floor between the roof and the lowest residential floor, of a building in the Development (whether known as a communal sky garden or otherwise)	平方米 sq.m.	不適用 Not applicable	441.7	441.7
	平方呎 sq.ft.	不適用 Not applicable	4,754	4,754
位於發展項目中的建築物的最低一層住宅樓層以下的、供住客使用的公用花園或遊樂地方（不論是稱為有蓋及園景的遊樂場或有其他名稱） Communal garden or play area for residents' use below the lowest residential floor of a building in the Development (whether known as a covered and landscaped play area or otherwise)	平方米 sq.m.	2,573.6	6,506.5	9,080.1
	平方呎 sq.ft.	27,702	70,036	97,738

註： 上述以平方呎列明之面積是以1平方米=10.764平方呎換算，並四捨五入至整數平方呎。

Note : The areas as specified above in square feet are converted at a rate of 1 square metre=10.764 square feet and rounded to the nearest whole square foot.

22 閱覽圖則及公契

Inspection of Plans and Deed of Mutual Covenant

1. 備有關於該發展項目的分區計劃大綱圖的文本供閱覽的互聯網網站的網址為 **www.ozp.tpb.gov.hk**。

2. 青富苑的公契在將住宅物業提供出售的日期的最新擬稿的文本存放在住宅物業的售樓處於開放時間內以供閱覽。

3. 無須為閱覽付費。

1. A copy of the Outline Zoning Plan relating to the Development is available at **www.ozp.tpb.gov.hk**.

2. A copy of the latest draft of the Deed of Mutual Covenant in respect of Ching Fu Court as at the date on which the residential property is offered to be sold is available for inspection during opening hours at the place at which the residential property is offered to be sold.

3. The inspection is free of charge.

1 外部裝修物料 EXTERIOR FINISHES

a	**外牆** External wall	髹上外牆漆。地下外牆局部鋪砌瓷磚。	Finished with external paint. Some finished with ceramic tiles at G/F.
b	**窗** Windows	客/飯廳選用鋁質窗框配有色玻璃或清玻璃，若玻璃片的任何一部分距離地板低於1.1米，該玻璃片則採用強化有色玻璃或強化清玻璃。 廚房選用鋁質窗框配清玻璃，若玻璃片的任何一部分距離地板低於1.1米，該玻璃片則採用強化清玻璃。 浴室選用鋁質窗框配壓花清玻璃，若玻璃片的任何一部分距離地板低於1.1米，該玻璃片則採用強化壓花清玻璃。 減音窗由一層鋁質趟窗框配強化清玻璃及一層鋁質窗框及可以用六角匙開啟的固定窗框配清玻璃窗組成，並設有吸音物料的鋁質疏孔面板。 固定窗選用鋁質窗框配清玻璃，可以用六角匙開啟。 有關裝設減音窗及/或固定窗之單位及有關窗戶的位置，請參閱第136-137頁。	Aluminium window frame fitted with tinted float glass or clear float glass for living/dining room. When any part of the glass panel is less than 1.1m above floor level, tempered tinted float glass or tempered clear float glass is used for such glass panel. Aluminium window frame fitted with clear float glass for kitchen. When any part of the glass panel is less than 1.1m above floor level, tempered clear float glass is used for such glass panel. Aluminium window frame fitted with clear patterned glass for bathroom. When any part of the glass panel is less than 1.1m above floor level, tempered clear patterned glass is used for such glass panel. Acoustic windows comprise of a layer of aluminium sliding window frame fitted with tempered clear float glass and a layer of aluminium window frame and fixed window frame openable with allen key fitted with clear float glass, as well as sound absorptive material cladded with aluminium lining panel with perforations. Fixed windows with aluminium window frame fitted with clear float glass openable with allen key. Please refer to pages 136–137 for flats installed with acoustic windows and/or fixed windows and the locations of such windows.
c	**窗台** Bay window	不適用	Not applicable
d	**花槽** Planter	不適用	Not applicable
e	**陽台或露台** Verandah or balcony	不適用	Not applicable
f	**乾衣設施** Drying facilities for clothing	客/飯廳部分窗外設有鋁質晾衣架。	Aluminium drying racks are fitted outside some of the windows of the living/dining room.

2 室內裝修物料 INTERIOR FINISHES

a	**大堂** Lobby	**地下主入口大堂：** 部分牆壁以瓷磚鋪砌及髹上外牆漆。地板以過底磚鋪砌。天花板髹上外牆漆。部分天花板設有鋁質天花及髹上外牆漆。 **標準樓層升降機大堂：** 部分牆壁髹上外牆漆。地板及牆腳線以過底磚鋪砌。天花板髹上外牆漆。	**Ground floor lobby:** Walls are partially finished with ceramic tiles and external paint. Floor is finished with homogeneous tiles. Ceiling is finished with external paint. Part of ceiling is fitted with aluminium suspended ceiling and external paint. **Typical floor lobby:** Walls are partially finished with external paint. Floor and skirting are finished with homogeneous tiles. Ceiling is finished with external paint.
b	**內牆及天花板** Internal wall and ceiling	客/飯廳的牆壁及天花板髹上乳膠漆。	Walls and ceiling of living/dining room are finished with emulsion paint.

2 室內裝修物料 INTERIOR FINISHES

c	**內部地板** Internal floor	客/飯廳的地板為混凝土搪平地台。所有單位並未設有牆腳線。	Floor of living/dining room is steel trowelled finish on concrete. No skirting is provided for all flats.
d	**浴室** Bathroom	牆壁以瓷磚鋪砌至窗頂及髹上乳膠漆至天花板。地板以過底磚鋪砌。天花板髹上乳膠漆。	Walls are finished with ceramic tiles up to top of the window and emulsion paint up to the ceiling. Floor is finished with homogeneous tiles. Ceiling is finished with emulsion paint.
e	**廚房** Kitchen	牆壁以瓷磚鋪砌至窗頂及髹上乳膠漆至天花板。地板以過底磚鋪砌。天花板髹上乳膠漆。灶台面為人造樹脂。	Walls are finished with ceramic tiles up to top of the window and emulsion paint up to the ceiling. Floor is finished with homogeneous tiles. Ceiling is finished with emulsion paint. Cooking bench top is fitted with polymer resin surface.

3 室內裝置 INTERIOR FITTINGS

a	**門** Doors	**單位大門：** 單位大門選用漆面實心木門配五金配件及防盜眼，並提供粉末塗料鐵閘配門鎖及門把手。 **浴室門：** 浴室門選用空心木門（一面漆面，一面膠板面）配五金配件。（A座的8號，9號，20號，21號，27號，28號，33號及34號單位除外；B座的4號，5號，16號，17號，27號，28號，33號和34號單位除外） A座的8號，9號，20號，21號，27號，28號，33號及34號單位；B座的4號，5號，16號，17號，27號，28號，33號和34號單位浴室門選用塑膠摺門配門鎖及門把手。 **廚房門：** 廚房門選用漆面實心木門配防火玻璃及五金配件。	**Flat entrance door:** Flat entrance door is made of paint finished solid timber door fitted with ironmongeries and door viewer. A metal gate finished with powder coating and fitted with lockset and handle is also provided. **Bathroom door:** Bathroom door is made of hollow timber finished with paint on one side and plastic laminate on the other and fitted with ironmongeries. (Except Flats 8, 9, 20, 21, 27, 28, 33 and 34 at Block A; Flats 4, 5, 16, 17, 27, 28, 33 and 34 at Block B) For bathroom door of Flats 8, 9, 20, 21, 27, 28, 33 and 34 at Block A; Flats 4, 5, 16, 17, 27, 28, 33 and 34 at Block B, plastic folding door fitted with lock and handle is provided. **Kitchen door:** Kitchen door is made of paint finished solid timber fitted with fire rated glazed panels and ironmongeries.
b	**浴室** Bathroom	裝置及設備包括搪瓷洗手盆、搪瓷水箱及坐廁、搪瓷廁紙斗、鍍鉻黃銅混合式面盆水龍頭、牆鏡、晾衣桿、以過底磚及人造麻石磚鋪砌的淋浴間、鍍鉻黃銅混合式花灑水龍頭及花灑套裝及浴簾桿。冷熱水供水系統採用銅喉管。	Fittings and equipment include vitreous china basin, vitreous china water closet and cistern, vitreous china toilet paper holder, chromium plated brass basin mixer, wall-mounted mirror, clothing drying rod, shower area finished with homogeneous tiles and artificial granite tiles, chromium plated brass shower mixer with shower set and curtain rail. Copper pipes are used for cold and hot water supply system.
c	**廚房** Kitchen	廚房設有不銹鋼洗滌盆、鍍鉻黃銅混合式洗滌盆水龍頭及面為人造樹脂的灶台。冷熱水供水系統採用銅喉管。	Kitchen is fitted with stainless steel sink unit, chromium plated brass sink mixer and cooking bench with polymer resin surface. Copper pipes are used for cold and hot water supply system.
d	**睡房** Bedroom	不適用	Not applicable
e	**電話** Telephone	客/飯廳設有一個電話插座。	One telephone outlet is provided in the living/dining room.
f	**天線** Aerials	客/飯廳設有電視/調頻收音機插座接收本地電視及電台節目，另有空間預留給電訊及廣播服務。部分單位設有一個空間預留給買方自行安裝電視/調頻收音機插座。有關插座及空間預留的數目，請參閱「住宅物業機電裝置數量說明表」。	TV/FM outlet(s) for local TV and FM radio programmes and reserved space(s) for telecommunications and broadcasting services are provided in the living/dinning room. One reserved space for installation of TV/FM outlet by purchasers is provided in some of the flats. For number of the outlets and reserved spaces, please refer to the "Schedule of Mechanical & Electrical Provisions of Residential Properties".

3 室內裝置 INTERIOR FITTINGS

g	**電力裝置** Electrical installations	各單位客/飯廳內均設有用戶總掣連配電箱。全屋電線導管均為隱藏式安裝。所有電插座均由漏電斷路器保護。有關電插座及接駁器的數目，請參閱「住宅物業機電裝置數量說明表」。	Consumer unit is provided in the living/dining room of each flat. All cable conduits are concealed. All socket outlets are protected by Residual Current Device. For number of socket outlets and connection units, please refer to the "Schedule of Mechanical & Electrical Provisions of Residential Properties".
h	**氣體供應** Gas supply	各單位煤氣供應接駁點設於廚房。 各單位廚房或浴室已預留即熱式氣體熱水爐安裝位置及相關隱藏式電線導管。有關熱水爐預留空間的位置，請參閱「住宅物業機電裝置數量說明表」。(買方須自行聘請合資格人員安裝氣體熱水爐)	Town gas supply connection point is provided in the kitchen of each flat. Reserved space for 'Instantaneous Gas' water heater and relevant concealed conduit for power are provided in the kitchen or bathroom of each flat. For location of the reserved space for water heater, please refer to the "Schedule of Mechanical & Electrical Provisions of Residential Properties". (Purchasers are required to employ a qualified person for installation of the town gas water heater.)
i	**洗衣機接駁點** Washing machine connection point	各單位廚房設有洗衣機來水及去水接駁點。	Water supply and drainage connection points for washing machine are provided in the kitchen of each flat.
j	**供水** Water supply	冷熱水供水系統採用銅喉管。所有水管均為外露。	Copper pipes are used for cold and hot water supply system. All water pipes are exposed.

4 雜項 MISCELLANEOUS

a	**升降機** Lift	八部「蒂森克虜伯」牌客用升降機(型號TH-HP61)服務A座 • 兩部升降機服務地下低層1樓及地下至11樓 • 三部升降機服務地下低層1樓、地下及12樓至27樓 • 三部升降機服務地下低層1樓、地下及28樓至40樓 八部「蒂森克虜伯」牌客用升降機(型號TH-HP61)服務B座 • 兩部升降機服務地下低層1樓及地下至12樓 • 三部升降機服務地下低層1樓、地下及13樓至27樓 • 三部升降機服務地下低層1樓、地下及28樓至40樓	**Eight "thyssenkrupp" passenger lifts (Model No. TH-HP61) serving Block A** • Two lifts serving LG1/F & G/F to 11/F • Three lifts serving LG1/F, G/F & 12/F to 27/F • Three lifts serving LG1/F, G/F & 28/F to 40/F **Eight "thyssenkrupp" passenger lifts (Model No. TH-HP61) serving Block B** • Two lifts serving LG1/F & G/F to 12/F • Three lifts serving LG1/F, G/F & 13/F to 27/F • Three lifts serving LG1/F, G/F & 28/F to 40/F

4 雜項 MISCELLANEOUS

b	**水錶、電錶及氣體錶** Water meter, electricity meter and gas meter	各單位的獨立水錶設於各樓層的水錶櫃內。各單位的獨立電錶設於各樓層的電錶房內。各單位廚房內均預留位置安裝煤氣錶(買方須自行申請安裝煤氣錶)。	Separate water meter for each flat is provided at the water meter cupboard on each floor. Separate electricity meter for each flat is provided at the electrical meter room on each floor. Space for town gas meter is provided in the kitchen of each flat. (Purchasers are required to make individual application for installation of town gas meter).
c	**信箱** Letter box	地下主入口大堂設有每戶專用的不銹鋼信箱。	Stainless steel letter box is provided for each flat at ground floor lobby.
d	**垃圾收集** Refuse collection	A座及B座的1樓至40樓公用地方設有垃圾及物料回收室和垃圾槽，於A座及B座地面設有垃圾及物料回收房，並於B座地面設有垃圾車專用車位及垃圾收集站中央處理垃圾。	Refuse storage and material recovery room with refuse chute is provided in the common area of 1/F to 40/F of Block A and Block B. Refuse storage and material recovery chamber is provided on ground level of Block A and Block B. Loading/unloading space reserved for refuse collection vehicle, and refuse collection point is provided on the ground level of Block B for centralised processing of refuse.

5 保安設施 SECURITY FACILITIES

	設有閉路電視監察系統監控升降機內，各地下大堂，各地下低層1樓大堂，各地下入口，各臨時庇護處，各頂層出口及外圍範圍狀況。閉路電視監控設備設於各住宅樓宇地下大堂保安護衛員櫃位內。	Closed Circuit Television (CCTV) System is provided for monitoring the situation of the lift cars, ground floor lobby, lower ground floor 1 lobby, ground floor entrances, temporary refuge spaces, exits to roof floor and external area. The monitoring equipment for CCTV system is provided at the guard counter on ground floor of each residential building.

6 設備 APPLIANCES

	不適用	Not applicable

賣方承諾如發展項目中沒有安裝指明的品牌名稱或產品型號的升降機或設備，便會安裝品質相若的升降機或設備。

The Vendor undertakes that if lifts or appliances of the specified brand name or model number are not installed in the Development, lifts or appliances of comparable quality will be installed.

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

A 座 BLOCK A

			樓層 Floor	1樓–40樓 1/F–40/F																
			單位 Flat	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
客/飯廳 Living/Dining Room	燈掣	Lighting Switch		2	2	2	3	3	3	2	2	2	2	3	4	3	2	2	2	3	3
	雙極開關掣	Double Pole Switch		1	1	1	2	2	2	1	1	1	1	2	3	2	1	1	1	2	2
	天花燈咀	Ceiling Lamp Holder		2	2	2	3	3	3	2	2	2	2	3	4	3	2	2	2	3	3
	13安培雙頭插座	13A Twin Socket Outlet		5	5	5	8	8	8	5	3	3	5	8	11	8	5	5	5	8	8
	電話插座	Telephone Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	電視/調頻收音機插座	TV/FM Outlet		2	2	2	2	2	2	2	1	1	2	2	2	2	2	2	2	2	2
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註1)	Connection Unit (Note 1)		1	1	1	2	2	2	1	1	1	1	2	3	2	1	1	1	2	2
	空間預留給電訊及廣播服務(註2)	Reserved Space for Telecommunications and Broadcasting Services (Note 2)		2	2	2	2	2	2	2	1	1	2	2	2	2	2	2	2	2	2
	空間預留給電視/調頻收音機插座(註3)	Reserved Space for TV/FM Outlet (Note 3)		0	0	0	1	1	1	0	0	0	0	1	1	1	0	0	0	1	1
	門鈴	Door Bell		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	門鈴按鈕	Door Bell Push Button		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	大門電話對講機	Doorphone Handset		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	用戶總掣連配電箱	Consumer Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
浴室 Bathroom	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		0	0	0	1	1	1	0	0	0	0	1	1	1	0	0	0	1	1
	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	2	2	2	1	1	1	1	2	2	2	1	1	1	2	2
	接駁器(註4)	Connection Unit (Note 4)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		0	0	0	1	1	1	0	0	0	0	1	1	1	0	0	0	1	1
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		0	0	0	1	1	1	0	0	0	0	1	1	1	0	0	0	1	1

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

A 座 BLOCK A

			樓層 Floor	1樓–40樓 1/F–40/F																
			單位 Flat	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
廚房 Kitchen	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培單頭插座	13A Single Socket Outlet		1	1	1	2	2	2	1	1	1	1	2	2	2	1	1	1	2	2
	13安培雙頭插座	13A Twin Socket Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		2	2	2	1	1	1	2	2	2	2	1	1	1	2	2	2	1	1
	2安培裝有熔斷器的接駁器連開關掣(註5)	2A Switched Fused Connection Unit (Note 5)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培裝有熔斷器的接駁器連開關掣(註6)	13A Switched Fused Connection Unit (Note 6)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註7)	Connection Unit (Note 7)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	煤氣供應接駁點	Town Gas Supply Connection Point		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機來水接駁點	Water Supply Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機去水接駁點	Drainage Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		1	1	1	0	0	0	1	1	1	1	0	0	0	1	1	1	0	0
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		1	1	1	0	0	0	1	1	1	1	0	0	0	1	1	1	0	0
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		1	1	1	0	0	0	1	1	1	1	0	0	0	1	1	1	0	0

註：
1. 安裝於客/飯廳之接駁器供冷氣機接駁之用。
2. 該空間預留給電訊及廣播服務，並蓋上空白蓋板。
3. 該空間預留給電視/調頻收音機插座，並蓋上空白蓋板供買方自行安裝有關插座。
4. 安裝於浴室之接駁器供抽氣扇接駁之用。
5. 安裝於廚房之2安培裝有熔斷器的接駁器連開關掣供抽油煙機接駁之用。
6. 安裝於廚房之13安培裝有熔斷器的接駁器連開關掣供洗衣機接駁之用。
7. 安裝於廚房之接駁器供抽氣扇接駁之用。
8. 該空間預留給煤氣熱水爐雙極開關掣，並蓋上空白蓋板標示“預留煤氣熱水爐雙極開關掣”供買方自行安裝。
9. 該空間預留給煤氣熱水爐接駁器，並蓋上空白蓋板標示“預留煤氣熱水爐接駁器”供買方自行安裝。
10. 該空間預留給買方自行安裝煤氣熱水爐。

Notes:
1. The Connection Unit(s) installed inside living/dining room is/are for connecting air conditioner(s).
2. The space(s) is/are reserved for telecommunications and broadcasting services and is/are covered with blank cover plate(s).
3. The space is reserved for installation of TV/FM outlet by purchasers and is covered with blank cover plate.
4. The Connection Unit installed inside bathroom is for connecting exhaust fan.
5. The 2A Switched Fused Connection Unit installed inside kitchen is for connecting range hood.
6. The 13A Switched Fused Connection Unit installed inside kitchen is for connecting washing machine.
7. The Connection Unit installed inside kitchen is for connecting exhaust fan.
8. The space is reserved for installation of double pole switch for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR DOUBLE POLE SWITCH OF TOWNGAS WATER HEATER”.
9. The space is reserved for installation of connection unit for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR CONNECTION UNIT OF TOWNGAS WATER HEATER”.
10. The space is reserved for installation of town gas water heater by purchasers.

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

A 座 BLOCK A

			樓層 Floor	1樓–40樓 1/F–40/F																
			單位 Flat	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
客/飯廳 Living/Dining Room	燈掣	Lighting Switch		2	2	2	2	3	3	4	2	2	2	2	4	4	2	2	2	2	4
	雙極開關掣	Double Pole Switch		1	1	1	1	2	2	3	1	1	1	1	3	3	1	1	1	1	3
	天花燈咀	Ceiling Lamp Holder		2	2	2	2	3	3	4	2	2	2	2	4	4	2	2	2	2	4
	13安培雙頭插座	13A Twin Socket Outlet		5	3	3	5	8	8	11	5	3	3	5	11	11	5	3	3	5	11
	電話插座	Telephone Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	電視/調頻收音機插座	TV/FM Outlet		2	1	1	2	2	2	2	2	1	1	2	2	2	2	1	1	2	2
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註1)	Connection Unit (Note 1)		1	1	1	1	2	2	3	1	1	1	1	3	3	1	1	1	1	3
	空間預留給電訊及廣播服務(註2)	Reserved Space for Telecommunications and Broadcasting Services (Note 2)		2	1	1	2	2	2	2	2	1	1	2	2	2	2	1	1	2	2
	空間預留給電視/調頻收音機插座(註3)	Reserved Space for TV/FM Outlet (Note 3)		0	0	0	0	1	1	1	0	0	0	0	1	1	0	0	0	0	1
	門鈴	Door Bell		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	門鈴按鈕	Door Bell Push Button		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	大門電話對講機	Doorphone Handset		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	用戶總掣連配電箱	Consumer Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
浴室 Bathroom	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		0	0	1	0	1	1	1	0	1	0	0	1	1	0	0	0	0	1
	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	2	1	2	2	2	1	2	1	1	2	2	1	1	1	1	2
	接駁器(註4)	Connection Unit (Note 4)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		0	0	1	0	1	1	1	0	1	0	0	1	1	0	0	0	0	1
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		0	0	1	0	1	1	1	0	1	0	0	1	1	0	0	0	0	1

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

A 座 BLOCK A

			樓層 Floor	1樓–40樓 1/F–40/F																
			單位 Flat	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
廚房 Kitchen	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培單頭插座	13A Single Socket Outlet		1	1	1	1	2	2	2	1	1	1	1	2	2	1	1	1	1	2
	13安培雙頭插座	13A Twin Socket Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		2	2	1	2	1	1	1	2	1	2	2	1	1	2	2	2	2	1
	2安培裝有熔斷器的接駁器連開關掣(註5)	2A Switched Fused Connection Unit (Note 5)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培裝有熔斷器的接駁器連開關掣(註6)	13A Switched Fused Connection Unit (Note 6)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註7)	Connection Unit (Note 7)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	煤氣供應接駁點	Town Gas Supply Connection Point		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機來水接駁點	Water Supply Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機去水接駁點	Drainage Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		1	1	0	1	0	0	0	1	0	1	1	0	0	1	1	1	1	0
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		1	1	0	1	0	0	0	1	0	1	1	0	0	1	1	1	1	0
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		1	1	0	1	0	0	0	1	0	1	1	0	0	1	1	1	1	0

註：
1. 安裝於客/飯廳之接駁器供冷氣機接駁之用。
2. 該空間預留給電訊及廣播服務，並蓋上空白蓋板。
3. 該空間預留給電視/調頻收音機插座，並蓋上空白蓋板供買方自行安裝有關插座。
4. 安裝於浴室之接駁器供抽氣扇接駁之用。
5. 安裝於廚房之2安培裝有熔斷器的接駁器連開關掣供抽油煙機接駁之用。
6. 安裝於廚房之13安培裝有熔斷器的接駁器連開關掣供洗衣機接駁之用。
7. 安裝於廚房之接駁器供抽氣扇接駁之用。
8. 該空間預留給煤氣熱水爐雙極開關掣，並蓋上空白蓋板標示“預留煤氣熱水爐雙極開關掣”供買方自行安裝。
9. 該空間預留給煤氣熱水爐接駁器，並蓋上空白蓋板標示“預留煤氣熱水爐接駁器”供買方自行安裝。
10. 該空間預留給買方自行安裝煤氣熱水爐。

Notes:
1. The Connection Unit(s) installed inside living/dining room is/are for connecting air conditioner(s).
2. The space(s) is/are reserved for telecommunications and broadcasting services and is/are covered with blank cover plate(s).
3. The space is reserved for installation of TV/FM outlet by purchasers and is covered with blank cover plate.
4. The Connection Unit installed inside bathroom is for connecting exhaust fan.
5. The 2A Switched Fused Connection Unit installed inside kitchen is for connecting range hood.
6. The 13A Switched Fused Connection Unit installed inside kitchen is for connecting washing machine.
7. The Connection Unit installed inside kitchen is for connecting exhaust fan.
8. The space is reserved for installation of double pole switch for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR DOUBLE POLE SWITCH OF TOWNGAS WATER HEATER”.
9. The space is reserved for installation of connection unit for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR CONNECTION UNIT OF TOWNGAS WATER HEATER”.
10. The space is reserved for installation of town gas water heater by purchasers.

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	3樓–40樓 3/F–40/F																
			單位 Flat	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
客/飯廳 Living/Dining Room	燈掣	Lighting Switch		2	3	2	2	2	2	4	2	2	2	2	3	4	3	2	2	2	2
	雙極開關掣	Double Pole Switch		1	2	1	1	1	1	3	1	1	1	1	2	3	2	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		2	3	2	2	2	2	4	2	2	2	2	3	4	3	2	2	2	2
	13安培雙頭插座	13A Twin Socket Outlet		5	8	5	3	3	5	11	5	5	5	5	8	11	8	5	3	3	5
	電話插座	Telephone Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	電視/調頻收音機插座	TV/FM Outlet		2	2	2	1	1	2	2	2	2	2	2	2	2	2	2	1	1	2
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註1)	Connection Unit (Note 1)		1	2	1	1	1	1	3	1	1	1	1	2	3	2	1	1	1	1
	空間預留給電訊及廣播服務(註2)	Reserved Space for Telecommunications and Broadcasting Services (Note 2)		2	2	2	1	1	2	2	2	2	2	2	2	2	2	2	1	1	2
	空間預留給電視/調頻收音機插座(註3)	Reserved Space for TV/FM Outlet (Note 3)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	0	0	0	0
	門鈴	Door Bell		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	門鈴按鈕	Door Bell Push Button		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	大門電話對講機	Doorphone Handset		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	用戶總掣連配電箱	Consumer Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
浴室 Bathroom	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	0	0	0	0
	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	2	1	1	1	1	2	1	1	1	1	2	2	2	1	1	1	1
	接駁器(註4)	Connection Unit (Note 4)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	0	0	0	0
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	0	0	0	0

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	3樓–40樓 3/F–40/F																
			單位 Flat	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
廚房 Kitchen	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培單頭插座	13A Single Socket Outlet		1	2	1	1	1	1	2	1	1	1	1	2	2	2	1	1	1	1
	13安培雙頭插座	13A Twin Socket Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		2	1	2	2	2	2	1	2	2	2	2	1	1	1	2	2	2	2
	2安培裝有熔斷器的接駁器連開關掣(註5)	2A Switched Fused Connection Unit (Note 5)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培裝有熔斷器的接駁器連開關掣(註6)	13A Switched Fused Connection Unit (Note 6)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註7)	Connection Unit (Note 7)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	煤氣供應接駁點	Town Gas Supply Connection Point		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機來水接駁點	Water Supply Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機去水接駁點	Drainage Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		1	0	1	1	1	1	0	1	1	1	1	0	0	0	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		1	0	1	1	1	1	0	1	1	1	1	0	0	0	1	1	1	1
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		1	0	1	1	1	1	0	1	1	1	1	0	0	0	1	1	1	1

註：
1. 安裝於客/飯廳之接駁器供冷氣機接駁之用。
2. 該空間預留給電訊及廣播服務，並蓋上空白蓋板。
3. 該空間預留給電視/調頻收音機插座，並蓋上空白蓋板供買方自行安裝有關插座。
4. 安裝於浴室之接駁器供抽氣扇接駁之用。
5. 安裝於廚房之2安培裝有熔斷器的接駁器連開關掣供抽油煙機接駁之用。
6. 安裝於廚房之13安培裝有熔斷器的接駁器連開關掣供洗衣機接駁之用。
7. 安裝於廚房之接駁器供抽氣扇接駁之用。
8. 該空間預留給煤氣熱水爐雙極開關掣，並蓋上空白蓋板標示“預留煤氣熱水爐雙極開關掣”供買方自行安裝。
9. 該空間預留給煤氣熱水爐接駁器，並蓋上空白蓋板標示“預留煤氣熱水爐接駁器”供買方自行安裝。
10. 該空間預留給買方自行安裝煤氣熱水爐。

Notes:
1. The Connection Unit(s) installed inside living/dining room is/are for connecting air conditioner(s).
2. The space(s) is/are reserved for telecommunications and broadcasting services and is/are covered with blank cover plate(s).
3. The space is reserved for installation of TV/FM outlet by purchasers and is covered with blank cover plate.
4. The Connection Unit installed inside bathroom is for connecting exhaust fan.
5. The 2A Switched Fused Connection Unit installed inside kitchen is for connecting range hood.
6. The 13A Switched Fused Connection Unit installed inside kitchen is for connecting washing machine.
7. The Connection Unit installed inside kitchen is for connecting exhaust fan.
8. The space is reserved for installation of double pole switch for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR DOUBLE POLE SWITCH OF TOWNGAS WATER HEATER”.
9. The space is reserved for installation of connection unit for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR CONNECTION UNIT OF TOWNGAS WATER HEATER”.
10. The space is reserved for installation of town gas water heater by purchasers.

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	3樓–40樓 3/F–40/F																
			單位 Flat	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
客/飯廳 Living/Dining Room	燈掣	Lighting Switch		3	3	3	2	2	2	4	2	2	2	2	4	4	2	2	2	2	4
	雙極開關掣	Double Pole Switch		2	2	2	1	1	1	3	1	1	1	1	3	3	1	1	1	1	3
	天花燈咀	Ceiling Lamp Holder		3	3	3	2	2	2	4	2	2	2	2	4	4	2	2	2	2	4
	13安培雙頭插座	13A Twin Socket Outlet		8	8	8	5	5	5	11	5	3	3	5	11	11	5	3	3	5	11
	電話插座	Telephone Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	電視/調頻收音機插座	TV/FM Outlet		2	2	2	2	2	2	2	2	1	1	2	2	2	2	1	1	2	2
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註1)	Connection Unit (Note 1)		2	2	2	1	1	1	3	1	1	1	1	3	3	1	1	1	1	3
	空間預留給電訊及廣播服務(註2)	Reserved Space for Telecommunications and Broadcasting Services (Note 2)		2	2	2	2	2	2	2	2	1	1	2	2	2	2	1	1	2	2
	空間預留給電視/調頻收音機插座(註3)	Reserved Space for TV/FM Outlet (Note 3)		1	1	1	0	0	0	1	0	0	0	0	1	1	0	0	0	0	1
	門鈴	Door Bell		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	門鈴按鈕	Door Bell Push Button		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	大門電話對講機	Doorphone Handset		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	用戶總掣連配電箱	Consumer Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
浴室 Bathroom	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		1	1	1	0	0	0	1	0	0	0	0	1	1	0	0	0	0	1
	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		2	2	2	1	1	1	2	1	1	1	1	2	2	1	1	1	1	2
	接駁器(註4)	Connection Unit (Note 4)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		1	1	1	0	0	0	1	0	0	0	0	1	1	0	0	0	0	1
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		1	1	1	0	0	0	1	0	0	0	0	1	1	0	0	0	0	1

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	3樓–40樓 3/F–40/F																
			單位 Flat	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
廚房 Kitchen	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培單頭插座	13A Single Socket Outlet		2	2	2	1	1	1	2	1	1	1	1	2	2	1	1	1	1	2
	13安培雙頭插座	13A Twin Socket Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	2	2	2	1	2	2	2	2	1	1	2	2	2	2	1
	2安培裝有熔斷器的接駁器連開關掣(註5)	2A Switched Fused Connection Unit (Note 5)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培裝有熔斷器的接駁器連開關掣(註6)	13A Switched Fused Connection Unit (Note 6)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註7)	Connection Unit (Note 7)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	煤氣供應接駁點	Town Gas Supply Connection Point		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機來水接駁點	Water Supply Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機去水接駁點	Drainage Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		0	0	0	1	1	1	0	1	1	1	1	0	0	1	1	1	1	0
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		0	0	0	1	1	1	0	1	1	1	1	0	0	1	1	1	1	0
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		0	0	0	1	1	1	0	1	1	1	1	0	0	1	1	1	1	0

註：
1. 安裝於客/飯廳之接駁器供冷氣機接駁之用。
2. 該空間預留給電訊及廣播服務，並蓋上空白蓋板。
3. 該空間預留給電視/調頻收音機插座，並蓋上空白蓋板供買方自行安裝有關插座。
4. 安裝於浴室之接駁器供抽氣扇接駁之用。
5. 安裝於廚房之2安培裝有熔斷器的接駁器連開關掣供抽油煙機接駁之用。
6. 安裝於廚房之13安培裝有熔斷器的接駁器連開關掣供洗衣機接駁之用。
7. 安裝於廚房之接駁器供抽氣扇接駁之用。
8. 該空間預留給煤氣熱水爐雙極開關掣，並蓋上空白蓋板標示“預留煤氣熱水爐雙極開關掣”供買方自行安裝。
9. 該空間預留給煤氣熱水爐接駁器，並蓋上空白蓋板標示“預留煤氣熱水爐接駁器”供買方自行安裝。
10. 該空間預留給買方自行安裝煤氣熱水爐。

Notes:
1. The Connection Unit(s) installed inside living/dining room is/are for connecting air conditioner(s).
2. The space(s) is/are reserved for telecommunications and broadcasting services and is/are covered with blank cover plate(s).
3. The space is reserved for installation of TV/FM outlet by purchasers and is covered with blank cover plate.
4. The Connection Unit installed inside bathroom is for connecting exhaust fan.
5. The 2A Switched Fused Connection Unit installed inside kitchen is for connecting range hood.
6. The 13A Switched Fused Connection Unit installed inside kitchen is for connecting washing machine.
7. The Connection Unit installed inside kitchen is for connecting exhaust fan.
8. The space is reserved for installation of double pole switch for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR DOUBLE POLE SWITCH OF TOWNGAS WATER HEATER”.
9. The space is reserved for installation of connection unit for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR CONNECTION UNIT OF TOWNGAS WATER HEATER”.
10. The space is reserved for installation of town gas water heater by purchasers.

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	1樓–2樓 1/F–2/F													
			單位 Flat	1	2	3	4	5	6	7	8	9	10	11	12	13	20	21
客/飯廳 Living/Dining Room	燈掣	Lighting Switch		2	3	2	2	2	2	4	2	2	2	2	3	4	3	3
	雙極開關掣	Double Pole Switch		1	2	1	1	1	1	3	1	1	1	1	2	3	2	2
	天花燈咀	Ceiling Lamp Holder		2	3	2	2	2	2	4	2	2	2	2	3	4	3	3
	13安培雙頭插座	13A Twin Socket Outlet		5	8	5	3	3	5	11	5	5	5	5	8	11	8	8
	電話插座	Telephone Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	電視/調頻收音機插座	TV/FM Outlet		2	2	2	1	1	2	2	2	2	2	2	2	2	2	2
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註1)	Connection Unit (Note 1)		1	2	1	1	1	1	3	1	1	1	1	2	3	2	2
	空間預留給電訊及廣播服務(註2)	Reserved Space for Telecommunications and Broadcasting Services (Note 2)		2	2	2	1	1	2	2	2	2	2	2	2	2	2	2
	空間預留給電視/調頻收音機插座(註3)	Reserved Space for TV/FM Outlet (Note 3)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	1
	門鈴	Door Bell		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	門鈴按鈕	Door Bell Push Button		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	大門電話對講機	Doorphone Handset		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	用戶總掣連配電箱	Consumer Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
浴室 Bathroom	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	1
	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	2	1	1	1	1	2	1	1	1	1	2	2	2	2
	接駁器(註4)	Connection Unit (Note 4)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	1
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		0	1	0	0	0	0	1	0	0	0	0	1	1	1	1

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	1樓–2樓 1/F–2/F													
			單位 Flat	1	2	3	4	5	6	7	8	9	10	11	12	13	20	21
廚房 Kitchen	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培單頭插座	13A Single Socket Outlet		1	2	1	1	1	1	2	1	1	1	1	2	2	2	2
	13安培雙頭插座	13A Twin Socket Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		2	1	2	2	2	2	1	2	2	2	2	1	1	1	1
	2安培裝有熔斷器的接駁器連開關掣(註5)	2A Switched Fused Connection Unit (Note 5)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培裝有熔斷器的接駁器連開關掣(註6)	13A Switched Fused Connection Unit (Note 6)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註7)	Connection Unit (Note 7)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	煤氣供應接駁點	Town Gas Supply Connection Point		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機來水接駁點	Water Supply Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機去水接駁點	Drainage Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		1	0	1	1	1	1	0	1	1	1	1	0	0	0	0
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		1	0	1	1	1	1	0	1	1	1	1	0	0	0	0
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		1	0	1	1	1	1	0	1	1	1	1	0	0	0	0

註：
1. 安裝於客/飯廳之接駁器供冷氣機接駁之用。
2. 該空間預留給電訊及廣播服務，並蓋上空白蓋板。
3. 該空間預留給電視/調頻收音機插座，並蓋上空白蓋板供買方自行安裝有關插座。
4. 安裝於浴室之接駁器供抽氣扇接駁之用。
5. 安裝於廚房之2安培裝有熔斷器的接駁器連開關掣供抽油煙機接駁之用。
6. 安裝於廚房之13安培裝有熔斷器的接駁器連開關掣供洗衣機接駁之用。
7. 安裝於廚房之接駁器供抽氣扇接駁之用。
8. 該空間預留給煤氣熱水爐雙極開關掣，並蓋上空白蓋板標示“預留煤氣熱水爐雙極開關掣”供買方自行安裝。
9. 該空間預留給煤氣熱水爐接駁器，並蓋上空白蓋板標示“預留煤氣熱水爐接駁器”供買方自行安裝。
10. 該空間預留給買方自行安裝煤氣熱水爐。

Notes:
1. The Connection Unit(s) installed inside living/dining room is/are for connecting air conditioner(s).
2. The space(s) is/are reserved for telecommunications and broadcasting services and is/are covered with blank cover plate(s).
3. The space is reserved for installation of TV/FM outlet by purchasers and is covered with blank cover plate.
4. The Connection Unit installed inside bathroom is for connecting exhaust fan.
5. The 2A Switched Fused Connection Unit installed inside kitchen is for connecting range hood.
6. The 13A Switched Fused Connection Unit installed inside kitchen is for connecting washing machine.
7. The Connection Unit installed inside kitchen is for connecting exhaust fan.
8. The space is reserved for installation of double pole switch for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR DOUBLE POLE SWITCH OF TOWNGAS WATER HEATER”.
9. The space is reserved for installation of connection unit for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR CONNECTION UNIT OF TOWNGAS WATER HEATER”.
10. The space is reserved for installation of town gas water heater by purchasers.

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	1樓–2樓 1/F–2/F													
			單位 Flat	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
客/飯廳 Living/Dining Room	燈掣	Lighting Switch		2	2	2	4	2	2	2	2	4	4	2	2	2	2	4
	雙極開關掣	Double Pole Switch		1	1	1	3	1	1	1	1	3	3	1	1	1	1	3
	天花燈咀	Ceiling Lamp Holder		2	2	2	4	2	2	2	2	4	4	2	2	2	2	4
	13安培雙頭插座	13A Twin Socket Outlet		5	5	5	11	5	3	3	5	11	11	5	3	3	5	11
	電話插座	Telephone Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	電視/調頻收音機插座	TV/FM Outlet		2	2	2	2	2	1	1	2	2	2	2	1	1	2	2
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註1)	Connection Unit (Note 1)		1	1	1	3	1	1	1	1	3	3	1	1	1	1	3
	空間預留給電訊及廣播服務(註2)	Reserved Space for Telecommunications and Broadcasting Services (Note 2)		2	2	2	2	2	1	1	2	2	2	2	1	1	2	2
	空間預留給電視/調頻收音機插座(註3)	Reserved Space for TV/FM Outlet (Note 3)		0	0	0	1	0	0	0	0	1	1	0	0	0	0	1
	門鈴	Door Bell		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	門鈴按鈕	Door Bell Push Button		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	大門電話對講機	Doorphone Handset		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	用戶總掣連配電箱	Consumer Unit		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
浴室 Bathroom	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		0	0	0	1	0	0	0	0	1	1	0	0	0	0	1
	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		1	1	1	2	1	1	1	1	2	2	1	1	1	1	2
	接駁器(註4)	Connection Unit (Note 4)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		0	0	0	1	0	0	0	0	1	1	0	0	0	0	1
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		0	0	0	1	0	0	0	0	1	1	0	0	0	0	1

住宅物業機電裝置數量說明表
Schedule of Mechanical & Electrical Provisions of Residential Properties

B 座 BLOCK B

			樓層 Floor	1樓–2樓 1/F–2/F													
			單位 Flat	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
廚房 Kitchen	燈掣	Lighting Switch		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	抽氣扇開關掣	Switch for Exhaust Fan		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	天花燈咀	Ceiling Lamp Holder		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培單頭插座	13A Single Socket Outlet		1	1	1	2	1	1	1	1	2	2	1	1	1	1	2
	13安培雙頭插座	13A Twin Socket Outlet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	2安培裝有熔斷器的接駁器	2A Fused Connection Unit		2	2	2	1	2	2	2	2	1	1	2	2	2	2	1
	2安培裝有熔斷器的接駁器連開關掣(註5)	2A Switched Fused Connection Unit (Note 5)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	13安培裝有熔斷器的接駁器連開關掣(註6)	13A Switched Fused Connection Unit (Note 6)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	接駁器(註7)	Connection Unit (Note 7)		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	煤氣供應接駁點	Town Gas Supply Connection Point		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機來水接駁點	Water Supply Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	洗衣機去水接駁點	Drainage Connection Point for Washing Machine		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	空間預留給煤氣熱水爐雙極開關掣(註8)	Reserved Space for Double Pole Switch for Town Gas Water Heater (Note 8)		1	1	1	0	1	1	1	1	0	0	1	1	1	1	0
	空間預留給煤氣熱水爐接駁器(註9)	Reserved Space for Connection Unit for Town Gas Water Heater (Note 9)		1	1	1	0	1	1	1	1	0	0	1	1	1	1	0
	空間預留給煤氣熱水爐(註10)	Reserved Space for Town Gas Water Heater (Note 10)		1	1	1	0	1	1	1	1	0	0	1	1	1	1	0

註：
1. 安裝於客/飯廳之接駁器供冷氣機接駁之用。
2. 該空間預留給電訊及廣播服務，並蓋上空白蓋板。
3. 該空間預留給電視/調頻收音機插座，並蓋上空白蓋板供買方自行安裝有關插座。
4. 安裝於浴室之接駁器供抽氣扇接駁之用。
5. 安裝於廚房之2安培裝有熔斷器的接駁器連開關掣供抽油煙機接駁之用。
6. 安裝於廚房之13安培裝有熔斷器的接駁器連開關掣供洗衣機接駁之用。
7. 安裝於廚房之接駁器供抽氣扇接駁之用。
8. 該空間預留給煤氣熱水爐雙極開關掣，並蓋上空白蓋板標示“預留煤氣熱水爐雙極開關掣”供買方自行安裝。
9. 該空間預留給煤氣熱水爐接駁器，並蓋上空白蓋板標示“預留煤氣熱水爐接駁器”供買方自行安裝。
10. 該空間預留給買方自行安裝煤氣熱水爐。

Notes:
1. The Connection Unit(s) installed inside living/dining room is/are for connecting air conditioner(s).
2. The space(s) is/are reserved for telecommunications and broadcasting services and is/are covered with blank cover plate(s).
3. The space is reserved for installation of TV/FM outlet by purchasers and is covered with blank cover plate.
4. The Connection Unit installed inside bathroom is for connecting exhaust fan.
5. The 2A Switched Fused Connection Unit installed inside kitchen is for connecting range hood.
6. The 13A Switched Fused Connection Unit installed inside kitchen is for connecting washing machine.
7. The Connection Unit installed inside kitchen is for connecting exhaust fan.
8. The space is reserved for installation of double pole switch for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR DOUBLE POLE SWITCH OF TOWNGAS WATER HEATER”.
9. The space is reserved for installation of connection unit for town gas water heater by purchasers and is covered with cover plate marked “RESERVED FOR CONNECTION UNIT OF TOWNGAS WATER HEATER”.
10. The space is reserved for installation of town gas water heater by purchasers.

24 服務協議
Service Agreements

不適用　Not applicable

25 地稅
Government Rent

賣方須就住宅物業繳付地稅直至及包括該住宅物業轉讓予買方的轉讓契據日期，或如該住宅物業空置管有權交予買方的日期較轉讓契據的日期遲，則直至及包括空置管有權交予買方的當日，但須以下列條件為前提：在該住宅物業轉讓予買方的轉讓契據日期的14個工作日後，賣方無須就繳付該住宅物業的地稅負上責任。

The Vendor is liable for the Government rent payable for the residential property up to and inclusive of the date of assignment of the residential property to the purchaser, or the date on which vacant possession of the residential property is given to the purchaser if that is later than the date of assignment, provided that the Vendor shall not be liable for the Government rent payable for the residential property for more than 14 working days after the date of assignment of the residential property to the purchaser.

26 買方的雜項付款
Miscellaneous Payments by Purchaser

賣方並無為住宅物業繳交水、電力及氣體的按金，因此，在向買方交付住宅物業在空置情況下的管有權時，買方無須向賣方補還水、電力及氣體的按金。

在交付時，買方無須向賣方支付清理廢料的費用。

註：在交付時，買方須根據公契向發展項目的管理人（而非賣方）支付清理廢料的費用，款額不超過管理人所釐定一個月的管理費。而如賣方已支付清理廢料的費用，買方須向賣方補還該筆費用，補還款額由賣方全權釐定但不超過管理人所釐定一個月的管理費。

The Vendor has not paid any deposits for water, electricity and gas for the residential property. As such, on the delivery of the vacant possession of the residential property to the purchaser, the purchaser is not liable to reimburse the Vendor for the deposits for water, electricity and gas.

On that delivery, the purchaser is not liable to pay to the Vendor a debris removal fee.

Note : On that delivery, the purchaser is liable to pay a debris removal fee to the Manager (not the Vendor) under the Deed of Mutual Covenant. The debris removal fee shall not exceed one month's management fee as determined by the Manager. Where the Vendor has paid that debris removal fee, the purchaser shall reimburse the Vendor for the same. The amount of reimbursement shall be determined at the sole discretion of the Vendor but shall not exceed one month's management fee as determined by the Manager.

27 欠妥之處的保養責任期
Defects Liability Warranty Period

買方如在該住宅物業買賣成交日期後的一年內，向賣方發出書面通知，賣方須自費並在合理切實可行的範圍內，盡快把住宅物業、裝置、裝修物料或設備的欠妥之處作出補救（買方的行為或疏忽而導致的欠妥之處，則不在此列）。

The Vendor shall, at its own cost and as soon as reasonably practicable after receipt of a written notice served by the purchaser within one year after the date of completion of the sale and purchase, remedy any defects to the residential property, or the fittings, finishes or appliances, caused otherwise than by the act or neglect of the purchaser.

28 斜坡維修
Maintenance of Slopes

1. 根據批地文件的規定，該發展項目中的住宅物業的擁有人須自費維修斜坡。

A 有關規定的條款

(i)「該租契」（見批地文件的摘要內的定義）條款第3.3條訂明：

「承租人」（見批地文件的摘要內的定義）須不時及在此後的所有時間在每當有需要或情況要求時妥善及足夠地自費管理、修理、維護、支持、保養、鋪設、清洗、刷淨、清潔、清空、改動及保持「該土地」（見批地文件的摘要內的定義）及現有或其後任何時間位於「該土地」的樓宇或物業單位及所有其他架設物及建築物，所有「該土地」內的山坡上，擋土結構和護土牆，及所有屬於和以任何形式屬於或附屬於「該土地」或任何位於其上之樓宇、物業單位、架設物及建築物的牆、堤岸、路塹、籬笆、溝渠、路軌、電燈、行人道、水廁、洗滌槽、排水渠及水道，並且全面執行需要及必須的所有修葺、清洗及修改工程，一切必須達致令「署長」（見批地文件的摘要內的定義）滿意為止。

(ii)「該租契」條款第4.5(a)條、第4.5(c)條及第4.5(d)條訂明：

(a) 如果任何土地存在或已經被削去、移走或後移或補強或填土或進行任何類型的斜坡護土工程，不論有否經「署長」預先書面同意，亦不論是在「該土地」內或任何政府土地內，旨在構建、平整或開發「該土地」或其中任何部分或「承租人」按「該租契」條款需要進行的任何其他工程或作任何其他用途，「承租人」必須自費進行與修建該等斜坡處理工程、護土牆或其他承托物、保護物、排水或附屬工程或其後必要的其他工程，以便保護與承托「該土地」和任何毗鄰或毗連政府土地或出租土地內的泥土，避免與防止今後發生任何塌方、山泥傾瀉或地陷。「承租人」必須在「批租年期」內自費維持「該土地」、斜坡處理工程、護土牆或其他承托物、保護物、排水或附屬工程或其他工程於修繕妥當的狀態，並使「署長」滿意。

(c) 倘若因為任何構建、平整、開發或「承租人」進行其他工程或任何其他原因造成任何時候發生塌方、山泥傾瀉或地陷，不論發生在或來自「該土地」任何土地或任何毗鄰或毗連政府土地或出租土地，「承租人」須自費進行修復或彌補，使「署長」滿意，並須就所有凡因倒塌、山泥傾瀉或沉降而引致（不論是直接及間接引致的）或與倒塌、山泥傾瀉或沉降相關的所有責任、索償、損失、損害、支出、費用、要求、法律行動及訴訟（不論任何或如何引致）對政府作出彌償，並使政府持續得到彌償。

1. The land grant requires the owners of the residential properties in the Development to maintain slopes at their own cost.

A Terms of the Requirement

(i) Clause No. 3.3 of the said lease (as defined in the Summary of Land Grant) stipulates that:

The Lessee (as defined in the Summary of Land Grant) shall from time to time and at all times hereafter, when where and as often as need or occasion shall require, at the Lessee's own proper costs and charges well and sufficiently manage, repair, uphold, support, maintain, pave, purge, scour, cleanse, empty, amend and keep the said land (as defined in the Summary of Land Grant) and the messuage or tenement, messuages or tenements and all other erections and buildings now or which may at any time hereafter be standing upon the said land, all the slopes, earth-retaining structures and retaining walls within the said land and all the walls, banks, cuttings, hedges, ditches, rails, lights, pavements, privies, sinks, drains and watercourses thereunto belonging and which shall in any-wise belong or appertain unto the said land or any of the said messuages, tenements, erections and buildings in, by and with all and all manner of needful and necessary reparations, cleansings and amendments whatsoever the whole to be done to the satisfaction of the Director (as defined in the Summary of Land Grant).

(ii) Clause Nos. 4.5(a), 4.5(c) and 4.5(d) of the said lease stipulate that:

(a) Where there is or has been any cutting away, removal or setting back of any land, or any building-up or filling-in or any slope treatment works of any kind whatsoever, whether with or without the prior written consent of the Director, either within the said land or on any Government land, which is or was done for the purpose of or in connection with the formation, levelling or development of the said land or any part thereof or any other works required to be done by the Lessee under the said lease, or for any other purpose, the Lessee shall at its own expense carry out and construct such slope treatment works, retaining walls or other support, protection, drainage or ancillary or other works as shall or may then or at any time thereafter be necessary to protect and support such land within the said land and also any adjacent or adjoining Government or leased land and to obviate and prevent any falling away, landslip or subsidence occurring thereafter. The Lessee shall at all times throughout the Lease Term maintain at its own expense the said land, slope treatment works, retaining walls or other support, protection, drainage or ancillary or other works in good and substantial repair and condition to the satisfaction of the Director.

(c) In the event that as a result of or arising out of any formation, levelling, development or other works done by the Lessee or owing to any other reason, any falling away, landslip or subsidence occurs at any time, whether in or from any land, within the said land or from any adjacent or adjoining Government or leased land, the Lessee shall at its own expense reinstate and make good the same to the satisfaction of the Director and shall indemnify and keep indemnified the Government from and against all liabilities, claims, losses, damages, expenses, charges, costs, demands, actions and proceedings whatsoever and howsoever arising whether directly and indirectly out of or in connection with such falling away, landslip or subsidence.

(d) 除了「該租契」規定對違反該等條款的任何其他權利或補償外，「署長」有權發出書面通知要求「承租人」進行、修建和保養「該土地」、斜坡處理工程、護土牆或其他承托物、保護物和排水或附屬工程或其他工程或還原及修復任何塌方、山泥傾瀉或地陷。如果「承租人」不理會或未能在通知指明的期限內，遵從該通知要求，並使「署長」滿意，「署長」可立即執行和進行任何必要的工程，「承租人」須按政府要求即時償還政府因此產生的費用，連同任何行政或專業費用及開支。

(d) In addition to any other rights or remedies provided in the said lease for breach of any of the terms and covenants contained in the said lease, the Director shall be entitled by notice in writing to call upon the Lessee to carry out, construct and maintain the said land, slope treatment works, retaining walls, or other support, protection, and drainage or ancillary or other works or to reinstate and make good any falling away, landslip or subsidence, and if the Lessee shall neglect or fail to comply with the notice to the satisfaction of the Director within the period specified therein, the Director may forthwith execute and carry out any necessary works and the Lessee shall on demand repay to the Government the cost thereof, together with any administrative or professional fees and charges.

B **每名擁有人均須分擔維修工程的費用。**


B **Each of the owners is obliged to contribute towards the costs of the maintenance works.**

C **顯示該斜坡及已經或將會在該發展項目所位於的土地之內或之外建造的任何護土牆或有關構築物的圖則：**

C **A plan showing the slope and the retaining wall or related structures constructed, or to be constructed, within or outside the land on which the Development is situated :**

圖例 NOTATION

	地界	Lot Boundary
	斜坡	Slope



D **根據「公契」，該發展項目的管理人獲擁有人授權進行維修工程。**

「公契」的有關條文

除在售樓說明書另有定義外，下述用詞的意義將等同於「公契」內該用詞的意義。請參閱「公契」。

(i) 根據「公契」第四節第20條第(r)項，「經理人」有權力、職能和責任採取一切必要或適當的措施促使「業主」履行「該租契」，特別是按「該租契」規定視察、保養、維修、拆卸、清理、修復、搭建或建築一切土地、按「該租契」第3.17(a)條要求提供的露天空間、斜坡、斜坡護土工程、護土構築物、護土牆及其他承托物、防護、排水和在「該土地」及任何毗鄰或毗連政府土地或出租土地（如適用）的附屬及其他工程及構築物，達至地政總署署長、渠務署署長或其他「政府」部門（視情況而定）滿意（如適用）。

(ii) 根據「公契」第四節第20條第(ad)項，「經理人」有權力、職能和責任（如適用）委聘具適當資格的人士，按照「該租契」之條款及「斜坡維修指南」、「斜坡維修手冊」和按照有關「政府」部門不時發出有關維修斜坡、護土牆及其他構築物的全部指引，視察、保養及維修「斜坡結構」，令其維持在良好和修繕妥當的狀況，並就有關「斜坡結構」進行一切必要的工程。為免存疑，「公契」中聲明「屋苑」各「業主」有責任自費按照「該租契」及「斜坡維修指南」及「斜坡維修手冊」及上述指引，負責保養「斜坡結構」和進行任何與「斜坡結構」有關一切工程。倘「經理人」盡力後仍未能向上述所有「業主」收取工程所需之全部費用，有關責任將由各「屋苑」「業主」承擔，「經理人」毋須承擔個人責任執行「該租契」之有關規定。「經理人」如執行保養和修繕工程所合法招致或將會招致之一切費用，概由「業主」承擔並向「經理人」繳付。如已成立「業主立案法團」，「業主立案法團」具有「公契」第四節第20條第(ad)項所訂之權限和權力。

(iii) 根據「公契」第四節第20條第(av)項，「經理人」有權力、職能和責任保養「該土地」、斜坡護土工程、護土牆或其他承托物、防護、排水或附屬或「該租契」條款第4.5(a)條所指的其它工程，令其維持在良好和修繕妥當的狀況，令地政總署署長滿意。

(iv) 根據「公契」第七節第54(a)(1)條第(v)項，周年財政預算的第一部分第一節應包括（如適用）「斜坡結構」的相關視察、維修和保養費用與開支，以及根據

D **Under the Deed of Mutual Covenant ("DMC"), the manager of the Development has the owners' authority to carry out the maintenance works.**

Relevant Provisions of the DMC

Unless otherwise defined in this sales brochure, capitalised and other terms used in the following shall have the same meaning of such terms used in the DMC. Please refer to the DMC for reference.

(i) Pursuant to Clause 20(r) of Section IV of the DMC, the Manager shall have the powers, functions and obligations to take all steps necessary or expedient for compliance by the Owners with the said lease and, in particular, to inspect, maintain, repair, demolish, remove, reinstate, erect or construct, in accordance with the provisions of the said lease and (if applicable) to the satisfaction of the Director of Lands, Director of Drainage Services or other Government departments (as the case may be), all land, the open space(s) required to be provided under Clause 3.17(a) of the said lease, slopes, slope treatment works, earth-retaining structures, retaining walls and other support, protection, drainage, ancillary and other works and structures within the said land and also any adjacent or adjoining Government or leased land (if applicable).

(ii) Pursuant to Clause 20(ad) of Section IV of the DMC, the Manager shall have the powers, functions and obligations (if applicable) to engage suitably qualified personnel to inspect, keep and maintain in good and substantial repair and condition and carry out any necessary works in respect of the Slope Structures, in accordance with the provisions of the said lease and in accordance with the Slope Maintenance Guidelines and the Slope Maintenance Manual and all guidelines issued from time to time by the appropriate Government departments regarding the maintenance of slopes, retaining walls and other structures. For the avoidance of doubt, it is declared in the DMC that the onus is on the Owners of the Estate, at their own expense, to maintain and carry out all works in respect of the Slope Structures in accordance with the said lease and the Slope Maintenance Guidelines and the Slope Maintenance Manual and the guidelines aforesaid, and the Manager shall not be personally liable for carrying out any such requirements of the said lease, which shall remain the responsibility of the Owners of the Estate, if the Manager, having used all reasonable endeavours, has not been able to collect the costs of the required works from all of the aforesaid Owners. The Owners shall pay to the Manager all costs lawfully incurred or to be incurred by the Manager in carrying out any such maintenance and repair works as aforesaid. The Owners' Corporation, if formed, shall also have the authority and power mentioned in Clause 20(ad) of Section IV of the DMC.

(iii) Pursuant to Clause 20(av) of Section IV of the DMC, the Manager shall have the powers, functions and obligations to maintain the said land, slope treatment works, retaining walls or other support, protection, drainage or ancillary or other works referred to in Clause 4.5(a) of the said lease in good and substantial repair and condition, to the satisfaction of the Director of Lands.

(iv) Pursuant to Clause 54(a)(1)(v) of Section VII of the DMC, the first section of the first part of the annual budget shall cover (if applicable) the costs and expenses in connection with the inspection, keeping and maintenance of the Slope Structures and the costs and expenses of all slope treatment works and other support or protection works for protection and support of the said land or any part

「該租契」的條款(如有)和按照「斜坡維修指南」及「斜坡維修手冊」或有關「政府」部門不時發出有關維修斜坡、護土牆及相關構築物的其他指引規定保護和支撐需要保護及支撐的「該土地」或其任何部分或任何相鄰或毗連土地而進行的所有斜坡護土工程及其他支撐或保護工程的費用與開支。

(v) 根據「公契」附表三第26條，「業主」應自費保養及進行所有「該租契」下及根據「斜坡維修指南」及「斜坡維修手冊」要求的有關「斜坡結構」的工作。香港房屋委員會須於「公契」日期的一個月內將「斜坡維修手冊」的完整副本存放於「屋苑」的管理處，以供所有「業主」免費檢閱及於支付合理費用後影印。所有收取的費用將全部撥入「特別基金」。

2. 該發展項目中的住宅物業的擁有人自費就發展項目維修任何斜坡的承諾

不適用。

thereof or any adjacent or adjoining land that are required to be protected and supported under the provisions of the said lease (if any) and in accordance with the Slope Maintenance Guidelines and Slope Maintenance Manual or other guidelines issued from time to time by the appropriate Government departments regarding the maintenance of slopes, retaining walls and related structures.

(v) Pursuant to Clause 26 of the Third Schedule to the DMC, the Owners shall, at their own expenses, maintain and carry out all works in respect of the Slope Structures as required by the said lease and in accordance with the Slope Maintenance Guidelines and the Slope Maintenance Manual. The Hong Kong Housing Authority shall deposit a full copy of the Slope Maintenance Manual in the management office of the Estate within one month after the date of the DMC for inspection by all Owners free of charge and taking copies upon payment of a reasonable charge. All charges received shall be credited to the Special Fund.

2. Undertaking by owners of the residential properties to maintain any slope in relation to the Development at the owner's own cost

Not applicable.

29 批地文件修訂
Modification of Land Grant

不適用　Not applicable

30 申請建築物總樓面面積寬免的資料

Information in Application for Concession on Gross Floor Area of Building

獲寬免總樓面面積的設施分項

於印製售樓說明書前呈交予並已獲房屋局常任秘書長辦公室的獨立審查組(前運輸及房屋局常任秘書長(房屋)辦公室的獨立審查組)(下稱「獨立審查組」)批准的一般建築圖則上有關總樓面面積寬免的分項的最新資料，請見下表。直至最終修訂圖則於就該發展項目發出佔用許可證前呈交予並獲「獨立審查組」批准前，以下分項資料仍可能有所修改。

Breakdown of GFA Concessions Obtained for All Features

Latest information on breakdown of GFA concessions as shown on the general building plans submitted to and approved by the Independent Checking Unit (ICU) of the Office of the Permanent Secretary for Housing (formerly, the Independent Checking Unit of the Office of the Permanent Secretary for Transport and Housing (Housing)) prior to the printing of the sales brochure is tabulated below. The breakdown of GFA concessions may be subject to further changes until final amendment plans are submitted to and approved by the ICU prior to the issuance of the Occupation Permit for the Development.

		面積(平方米) Area (m^2)
根據《建築物(規劃)規例》第23(3)(b)條不計算的總樓面面積 DISREGARDED GFA UNDER BUILDING (PLANNING) REGULATIONS 23(3)(b)		
1	停車場及上落客貨地方(公共交通總站除外) Carpark and loading/unloading area excluding public transport terminus	2,187.702
2	機房及相類設施 Plant rooms and similar services	
2.1	所佔面積受相關《認可人士、註冊結構工程師及註冊岩土工程師作業備考》或規例限制的強制性設施或必要機房，例如升降機機房、電訊及廣播設備室、垃圾及物料回收房等。 Mandatory feature or essential plant room, area of which is limited by respective Practice Notes for Authorised Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) or regulation, such as lift machine room, telecommunications and broadcasting equipment (TBE) room, refuse storage and material recovery chamber, etc.	1,420.730
2.2	所佔面積不受任何《認可人士、註冊結構工程師及註冊岩土工程師作業備考》或規例限制的強制性設施或必要機房，例如僅供消防裝置及設備佔用的房間、電錶房、電力變壓房、食水及鹹水缸等。 Mandatory feature or essential plant room, area of which is NOT limited by any PNAP or regulation, such as room occupied solely by fire services installations (FSI) and equipment, meter room, transformer room, potable and flushing water tank, etc.	6,170.062
2.3	非強制性或非必要機房，例如空調機房、風櫃房等。 Non-mandatory or non-essential plant room, such as air-conditioning plant room, air handling unit (AHU) room, etc.	不適用 Not applicable
根據聯合作業備考第1及第2號提供的環保設施 GREEN FEATURES UNDER JOINT PRACTICE NOTES 1 AND 2		
3	露台 Balcony	不適用 Not applicable
4	加闊的公用走廊及升降機大堂 Wider common corridor and lift lobby	不適用 Not applicable
5	公用空中花園 Communal sky garden	不適用 Not applicable
6	隔聲鰭 Acoustic fin	6.630

申請建築物總樓面面積寬免的資料
Information in Application for Concession on Gross Floor Area of Building

		面積(平方米) Area (m^2)
根據聯合作業備考第1及第2號提供的環保設施 GREEN FEATURES UNDER JOINT PRACTICE NOTES 1 AND 2		
7	翼牆、捕風器及風斗 Wing wall, wind catcher and funnel	不適用 Not Applicable
8	非結構預製外牆 Non-structural prefabricated external wall	2,012.668
9	工作平台 Utility platform	不適用 Not Applicable
10	隔音屏障 Noise barrier	不適用 Not Applicable
適意設施 AMENITY FEATURES		
11	供保安人員和管理處員工使用的櫃枱、辦公室、儲物室、警衛室和廁所、業主立案法團辦公室 Counter, office, store, guard room and lavatory for watchman and management staff, Owners' Corporation Office	255.950
12	住宅康樂設施，包括僅供康樂設施使用的中空、機房、游泳池的濾水器機房、有蓋人行道等 Residential recreational facilities including void, plant room, swimming pool filtration plant room, covered walkway, etc. serving solely the recreational facilities	不適用 Not applicable
13	有上蓋的園景區及遊樂場 Covered landscaped and play area	1,068.356
14	橫向屏障/有蓋人行道、花棚 Horizontal screens/covered walkways, trellis	494.510
15	擴大升降機井道 Larger lift shaft	739.795
16	煙囪管道 Chimney shaft	不適用 Not applicable
17	其他非強制性或非必要機房，例如鍋爐房、衛星電視共用天線房 Other non-mandatory or non-essential plant room, such as boiler room, satellite master antenna television (SMATV) room	不適用 Not applicable
18	強制性設施或必要機房所需的管槽、氣槽 Pipe duct, air duct for mandatory feature or essential plant room	745.532
19	非強制性設施或非必要機房所需的管槽、氣槽 Pipe duct, air duct for non-mandatory or non-essential plant room	2.314

		面積(平方米) Area (m^2)
適意設施 AMENITY FEATURES		
20	環保系統及設施所需的機房、管槽及氣槽 Plant room, pipe duct, air duct for environmentally friendly system and feature	不適用 Not applicable
21	複式住宅單位及洋房的中空 Void in duplex domestic flat and house	不適用 Not applicable
22	伸出物，如空調機箱及伸出外牆超過750毫米的平台 Projections such as air-conditioning box and platform with a projection of more than 750mm from the external wall	不適用 Not applicable
其他項目 OTHER EXEMPTED ITEMS		
23	庇護層，包括庇護層兼空中花園 Refuge floor including refuge floor cum sky garden	不適用 Not applicable
24	其他伸出物 Other projections	不適用 Not applicable
25	公共交通總站 Public transport terminus	不適用 Not applicable
26	共用構築物及樓梯 Party structure and common staircase	不適用 Not applicable
27	僅供獲接納不計入總樓面面積的樓層使用的樓梯、升降機槽及垂直管道的水平面積 Horizontal area of staircase, lift shaft and vertical duct solely serving floor accepted as not being accountable for GFA	不適用 Not applicable
28	公眾通道 Public passage	不適用 Not applicable
29	因建築物後移導致的覆蓋面積 Covered set back area	不適用 Not applicable
額外總樓面面積 BONUS GFA		
30	額外總樓面面積 Bonus GFA	不適用 Not applicable

註： 上述表格是根據屋宇署所發出的《認可人士、註冊結構工程師及註冊岩土工程師作業備考》ADM-2規定的要求而制訂的。屋宇署會按實際需要不時更改有關要求。

Note: The above table is based on the requirements as stipulated in the Practice Note for Authorised Persons, Registered Structural Engineers and Registered Geotechnical Engineers ADM-2 issued by the Buildings Department. The Buildings Department may revise such requirements from time to time as appropriate.

有關建築物的環境評估



Environmental Assessment of the Building



發展項目的公用部分的預計能量表現或消耗

於印製售樓說明書前呈交予「獨立審查組」發展項目的公用部分的預計能量表現或消耗的最近期資料(見附表)。

第I部分 Part I		
提供中央空調 Provision of Central Air Conditioning	否 NO	
提供具能源效益的設施 Provision of Energy Efficient Features	是 YES	
擬安裝的具能源效益的設施 Proposed Energy Efficient Features	1. 二級光度照明控制系統 2. 發光二極管照明燈具 3. 升降機電動機設置再生動力裝置	Two-level Lighting Control System LED Bulkhead Light Fitting Regenerative Power of Lift System

Estimated Energy Performance or Consumption for the Common Parts of the Development

Latest information on the estimated energy performance or consumption for the common parts of the Development as submitted to the ICU prior to the printing of the sales brochure (see tables).

第II部分 : 擬興建樓宇/部分樓宇預計每年能源消耗量(註1)
Part II : The Predicted Annual Energy Use of the Proposed Building / Part of Building (Note 1)

位置 Location	使用有關裝置的內部樓面面積(平方米) Internal Floor Area Served (m^2)	基線樓宇(註2)每年能源消耗量 Annual Energy Use of Baseline Building (Note 2)		擬興建樓宇每年能源消耗量 Annual Energy Use of Proposed Building	
		電力 千瓦小時/平方米/年 **Electricity** kWh/m^2/annum	煤氣/石油氣 用量單位/平方米/年 **Town Gas/LPG** unit/m^2/annum	電力 千瓦小時/平方米/年 **Electricity** kWh/m^2/annum	煤氣/石油氣 用量單位/平方米/年 **Town Gas/LPG** unit/m^2/annum
有使用中央屋宇裝備裝置(註3)的部分 Area Served by Central Building Services Installation (Note 3)	18,720	85.6	不適用 Not applicable	31.9	不適用 Not applicable

第III部分： 以下裝置乃按機電工程署公布的相關實務守則設計
Part III : The Following Installations are Designed in Accordance with the Relevant Codes of Practices Published by the Electrical & Mechanical Services Department (EMSD)

裝置類型 Type of Installations	是 YES	否 NO	不適用 Not applicable
照明裝置 Lighting Installations	✓		
空調裝置 Air Conditioning Installations	✓		
電力裝置 Electrical Installations	✓		
升降機及自動梯的裝置 Lift & Escalator Installations	✓		
以總能源為本的方法 Performance-based Approach		✓	

註：

1. 一般而言，一棟樓宇的預計“每年能源消耗量”愈低，其節約能源的效益愈高。如一棟樓宇預計的“每年能源消耗量”低於該樓宇的“基線樓宇每年能源消耗量”，則代表預計該樓宇的能源應用較其基線樓宇有效，削減幅度愈大則代表有關樓宇能源節約的效益愈高。

   預計每年能源消耗量[以耗電量（千瓦小時/平方米/年）及煤氣/石油氣消耗量（用量單位/平方米/年）計算]，指將發展項目的每年能源消耗總量除以使用有關裝置的內部樓面面積所得出的商，其中：

   (a) “每年能源消耗量”與綠建環評新建建築（2.0先導版本）第5節中的「年能源消耗」具有相同涵義；及

   (b) 樓宇、空間或單位的“內部樓面面積”，指外牆及/或共用牆的內壁之內表面起量度出來的樓面面積。

2. “基線樓宇”與綠建環評新建建築（2.0先導版本）附錄9中的“基準建築物模式”具有相同涵義。

3. “中央屋宇裝備裝置”與機電工程署發出的《屋宇裝備裝置能源效益實務守則》（2018年版）中的涵義相同。

Notes :

1. In general, the lower the predicted “Annual Energy Use” of the building, the more efficient of the building in terms of energy use. For example, if the predicted “annual energy use of proposed building” is less than the predicted “annual energy use of baseline building”, it means the predicted use of energy is more efficient in the proposed building than in the baseline building. The larger the reduction, the greater the efficiency.

   The predicted annual energy use, in terms of electricity consumption (kWh/m^2/annum) and town gas/LPG consumption (unit/m^2/annum), of the Development by the internal floor area served, where:

   (a) “total annual energy use” has the same meaning of “annual energy use” under Section 5 of the BEAM Plus for New Buildings (Version 2.0 Pilot); and

   (b) “internal floor area”, in relation to a building, a space or a unit means the floor area of all enclosed space measured to the internal faces of enclosing external and/or party walls.

2. “Baseline Building” has the same meaning as “Baseline Building Model” under Appendix 9 of the BEAM Plus for New Buildings (Version 2.0 Pilot).

3. “Central Building Services Installation” has the same meaning as that in the Code of Practice for Energy Efficiency of Building Services Installation (2018 edition) issued by the Electrical and Mechanical Services Department.

31 有關資料
Relevant Information

A 交通噪音

青富苑受道路交通噪音影響。為改善情況，該發展項目將設置下列設施：

隔聲鰭

A座1樓至17樓的26號及27號單位的外牆將裝設隔聲鰭（有關隔聲鰭的位置請參閱第20頁及24頁的樓面平面圖）。隔聲鰭屬公契內定義的「住宅大廈公用地方與設施」的一部分，須由青富苑住宅物業的業主出資管理及維修。

減音窗及固定窗

部分青富苑單位裝設有減音窗及/或固定窗（不能開啓）。（有關裝設有減音窗及/或固定窗之單位及窗戶的位置請參閱第136及137頁的參考圖）。青富苑的公契有以下關於減音窗及/或固定窗的規定（註）：

- 青富苑裝設有減音窗之單位的業主不得干擾、改動、變更或拆除該些裝設在其單位內的減音窗（根據公契規定作保養、維修或更換除外）。
- 房委會須在管理處內提供有關安裝、保養、更換或維修減音窗的圖則及方法供青富苑業主於日常辦公時間內免費查閱。裝設於任何單位內的減音窗的保養、更換或維修工作須由有關單位的業主自費根據房委會提供的圖則及方法內所列明的標準及規格進行。有關單位的業主須以適當的物料及委任合資格的承辦商以進行有關的保養、更換或維修工作。
- 除進行保養、更換或維修工作外，固定窗須在任何時間保持關閉及鎖上以緩解噪音。裝設於任何住宅單位內的固定窗的保養、更換或維修工作須由有關住宅單位的業主自費進行。

註：有關公契條款只供參考，並以公契的全文為準。公契的全文可於房委會綠置居銷售小組辦事處開放時間內免費查閱。

A Traffic Noise

Ching Fu Court is subject to road traffic noise. In order to improve the condition, the following facilities will be provided in the Development:

Acoustic Fins

Acoustic fins will be installed at the external wall of Flat 26 and Flat 27 of Block A from 1/F to 17/F. (Please refer to the floor plans on page 20 and page 24 for the location of the acoustic fins). The acoustic fins form part of the Residential Block Common Areas and Facilities as defined under the Deed of Mutual Covenant (DMC) and shall be managed and maintained by owners of residential properties in Ching Fu Court at their own expense.

Acoustic Windows and Fixed Windows

Acoustic windows and/or fixed windows (not openable) are installed in some of the flats in Ching Fu Court. (Please refer to the reference plans on pages 136 and 137 for flats installed with acoustic windows and/or fixed windows and the locations of such windows). The DMC of Ching Fu Court contains the following provisions relating to acoustic windows and/or fixed windows (Note):

- Subject to any maintenance, repair or replacement in accordance with the requirements set out in the DMC, no owner of those units in Ching Fu Court installed with acoustic windows and/ or the fixed windows shall tamper, alter, vary or remove the acoustic windows and/or the fixed windows installed in his unit.
- The HA shall provide the drawings and methodology for the installation, maintenance, replacement or repair of the acoustic windows and/or fixed windows at the management office for inspection by the owners of Ching Fu Court free of charge during normal business hours. The maintenance, replacement or repair of any of the acoustic windows and/or fixed windows installed in any unit shall be made by the owner of relevant unit at his own costs in accordance with the standards and specifications set out in such drawings and methodology. The owners of such units shall use appropriate materials and appoint qualified contractors for carrying out such maintenance, replacement or repair.
- The fixed windows shall be kept closed and locked at all times for noise mitigation purpose except for maintenance, replacement or repair. The maintenance, replacement or repair of any of the fixed windows installed in any residential unit shall be made by the owner of relevant residential unit at his own costs.

Note: The concerned provisions in the DMC are for reference only and are subject to the full script of the DMC. Full script of the DMC is available for inspection free of charge during opening hours at the office of the Green Form Subsidised Home Ownership Scheme (GSH) Sales Unit of the HA.

B 裝修須知

在進行有關裝修工程時，須遵守《建築物條例》及有關規例的規定。特別當工程涉及鋪設/重新鋪設地台批盪超過25毫米、或加建/改建牆間隔（除非加建或改建的牆間隔是按照青富苑樓宇設計所預定的核准間隔牆示意圖上所有的規定進行），必須符合《建築物（小型工程）規例》的現行監管程序。有關小型工程監管制度的詳情，可瀏覽屋宇署的相關網頁或諮詢專業人士。有關在進行裝修時須注意的事項及青富苑樓宇設計所預定的核准間隔牆示意圖，可參閱青富苑裝修指引。有關裝修指引會於物業交吉時提供予買方。

C 樓宇結構安全保證

香港房屋委員會（房委會）根據以下條文及註釋，向業主(註1)提供樓宇結構安全保證。

保證期

房委會會給予青富苑為期十年的樓宇結構安全保證。

青富苑的十年樓宇結構安全保證期由樓宇的佔用許可證的發出日期起計。

保證範圍

房委會保證樓宇的整體結構穩定完整，並在十年結構安全保證期內，負責任何或所有結構構件(註3)所需的全部結構修葺工作(註2)，包括修葺混凝土剝落及出現裂縫的地方，以維持樓宇(註5)整體結構穩定完整(註4)。

本保證並不包括以上保證範圍以外的修葺，例如：

i. 與樓宇整體結構穩定完整無關的損壞，包括天花滲水、窗戶滲水、牆身滲水、批盪裂縫、牆壁磚和地面磚損毀，以及其他的損壞；
ii. 在結構上把單位改建、加建或改變原有用途；或因不適當使用而對樓宇所造成的損壞；以及
iii. 下列任何一項特別風險對樓宇造成的損壞：
   - 任何氣體燃料爆炸所造成的損壞；
   - 戰爭、火災、地震或山泥傾瀉造成的損壞；
   - 房委會負責範圍以外的人士作出的行為或疏忽。

B Points to Note for Fitting Out

When carrying out decoration works, the requirements of the Buildings Ordinance and its relevant legislations should be complied with. In particular, when works involve laying/re-laying floor screed that is more than 25mm thick, or making additions/alterations to wall partitions (unless these additions or alterations are in full compliance with all the requirements on the indicative approved floor plan with partition wall layout for wall partitions in Ching Fu Court), the prevailing control procedures under the Building (Minor Works) Regulation must be complied with. For details of the Minor Works Control System, please visit the relevant webpages of the Buildings Department or consult a professional. For matters regarding the carrying out of decoration works and for the indicative approved floor plan with partition wall layout for wall partitions in Ching Fu Court, please refer to the Guide for Decoration Works for Ching Fu Court, which will be made available to the purchaser on the delivery of vacant possession of the property.

C Structural Safety Guarantee

The Hong Kong Housing Authority (HA) will provide Structural Safety Guarantee (SSG) to the owners (Note 1) in accordance with the following provisions and explanatory notes.

Guarantee Period

The SSG given by the HA to Ching Fu Court is valid for a period of 10 years.

The 10-year period of the SSG for Ching Fu Court counts from the date of issue of the Occupation Permit for the building.

Coverage

The HA guarantees the structural stability and integrity of the building as a whole within the guarantee period of 10 years and undertakes all structural repairs (Note 2), including repair to concrete spalling and cracking, to any or all of the structural components (Note 3) deemed necessary to uphold the overall structural stability and integrity (Note 4) of the building (Note 5).

Works of repairs not falling within the above-defined scope shall not be covered by this structural guarantee, for example:

i. Water seepage through ceilings, windows or walls, cracks in plaster and rendering, defects in wall and floor tiling and any other defects not related to the structural stability and integrity of the building;
ii. Defects arising from structural alterations, additions or changes within flats or improper usage of the building; and
iii. Defects arising from the following special risks, including:
   - explosions caused by inflammable gas;
   - outbreak of war, fire, earthquake or landslide;
   - acts or omission of a person for whom the HA is not responsible.

業主責任

為確保房委會能落實並履行此保證的義務，有關業主須准許房委會或獲房委會授權的任何人員，在出示授權證明下，於合理時間進入有關樓宇及樓宇範圍的任何建築物視察或進行有關檢驗和修葺工程。

若業主在保證期內察覺房委會須根據此保證進行有關的結構修葺工作，業主必須以第一時間及早通知房委會，否則房委會難以履行此保證的義務。

Owners' Responsibility

To ensure that the HA can implement and perform its obligations under SSG, owners shall allow the HA or its authorised personnel, upon production of their authorisation proof, to enter the premises concerned or any part thereof at reasonable times for inspection or carrying out related inspection and repair works.

Within the guarantee period, if the owners note that it is necessary for the HA to carry out structural repairs under SSG, they must inform the HA in the first instance. Otherwise, the HA may not be able to fulfil its obligations under SSG.

註：

1. 「業主」指合乎本保證所保障之住宅樓宇的法定業主。
2. 在進行結構修葺工程時，房委會只負責使單位受影響部分回復到樓宇落成時的原有標準。
3. 「結構構件」指建築結構圖上清楚列明的構件（如支柱、橫樑、受力牆壁及地台），而沒有列明的混凝土架或牆（如冷氣機罩/台、部分外牆、內部間隔牆等）都不在本保證範圍內。
4. 「結構穩定完整」指樓宇的結構及地基足以承受設計上負重及承托力的要求。
5. 「樓宇」不包括一切於外圍的工程及於外圍範圍內的地下水管、污水渠、道路、地面，以及一切設施。

Notes:

1. "Owners" refers to the legitimate owners of the domestic flats protected by this guarantee.
2. While carrying out the repair works, the HA is only responsible for reinstating the affected parts of the flats to the original standard at the time when the building was completed.
3. "Structural components" refers to the components (for example, columns, beams, load bearing walls and floor slabs) as specified clearly on the building structural plan. Concrete racks or walls not specified (for example, air-conditioner hoods/platforms, some external walls and internal partition walls, etc.) are not covered by this structural guarantee.
4. "Structural stability and integrity" refers to the load bearing capacity of the building's foundation and structure as required by the design.
5. "Building" excludes exterior works and subterranean water pipes, sewers, roads, ground surfaces and all other facilities in the external area.

D 轉讓限制

(a) 在簽署轉讓契據前，買方不得把單位轉讓予其他人士或機構。若買方要求撤銷買賣協議，且獲房委會同意，房委會有權保留一筆相等於售價百分之五的款額，作為同意撤銷買賣協議買方應付的代價。此外，撤銷買賣協議受買賣協議的條款限制，包括買方須向房委會支付或償付與撤銷買賣協議有關或其引致的一切法律費用、收費及代付費用（如有印花稅，此項亦包括在內）。

(b) 若買方成為業主後轉讓或出租其單位，須按照轉讓契據的條款和政府租契所載的條款、契諾及條件處理。房委會不會回購或提名買家（居者有其屋計劃（居屋）第二市場除外）購買蝶翠苑/青富苑單位，而下列轉讓限制將適用於有關單位的業主：

(i) 由房委會首次將單位售予業主的轉讓契據（下稱「首次轉讓契據」）日期起計兩年內：

- 業主須在無需繳付補價的情況下，在居屋第二市場以不高於列於首次轉讓契據的原來買價（註）出售單位予房委會提名的綠表買家。

(ii) 由首次轉讓契據日期起計第三至第十年內：

- 業主須在無需繳付補價的情況下，在居屋第二市場按業主自行議定的價格出售單位予房委會提名的綠表買家。

(iii) 由首次轉讓契據日期起計十年後：

- 業主可在無需繳付補價的情況下，在居屋第二市場按業主自行議定的價格出售單位予房委會提名的綠表買家。
- 業主亦可在繳付補價後於公開市場出售單位。
- 業主須繳付的補價，是根據屆時該單位並無轉讓限制的市值，按照該單位首次轉讓契據中所訂明的最初市值與原來買價（註）的差額計算。換句話說，補價相等於原來買價（註）的折扣，化為現值計算。
- 有關補價程序，請瀏覽房委會/房屋署網站 **(www.housingauthority.gov.hk)** 。

D Alienation Restrictions

(a) The flat shall not be assigned by the purchaser to any other person or organisation before executing the Deed of Assignment. If a purchaser requests for cancelling the Agreement for Sale and Purchase (ASP) where the HA agrees to the same, the HA shall be entitled to retain a sum equivalent to 5% of the purchase price as consideration for his agreeing to cancel the ASP. Besides, the cancellation of the ASP is subject to the provisions of the ASP including the purchaser being required to pay or reimburse the HA for all legal costs, charges and disbursements (including stamp duty, if any) in connection with or arising from the cancellation of the ASP.

(b) A purchaser who wishes to assign or let the flat after becoming an owner will be subject to the terms of the Deed of Assignment and the terms, covenants and conditions contained in the Government lease. For Dip Tsui Court / Ching Fu Court, the HA will not buy back or nominate a buyer (except Home Ownership Scheme (HOS) Secondary Market) to buy the flats, and the following alienation restrictions will apply to the owners:

(i) Within the first two years from the date of the first Deed of Assignment of the flat from the HA to an owner (the first assignment):

- The owner has to sell the flat in the HOS Secondary Market to a Green Form buyer nominated by the HA without payment of premium and at a price not more than the original purchase price (Note) under the first assignment.

(ii) From the third to the tenth year from the date of the first assignment:

- The owner has to sell the flat in the HOS Secondary Market to a Green Form buyer nominated by the HA without payment of premium and at his/her own negotiated price.

(iii) After ten years from the date of the first assignment:

- The owner may sell the flat in the HOS Secondary Market to a Green Form buyer nominated by the HA without payment of premium and at his/her own negotiated price.
- The owner may also sell the flat in the open market after payment of premium.
- The premium which the owner is required to pay is calculated based on the prevailing market value of the flat without alienation restrictions, and the difference between the original purchase price (Note) of the flat and its initial market value as specified in the first assignment. In other words, the premium is calculated by applying the discount of the original purchase price (Note) to the prevailing market value.
- Please refer to the HA/HD website **(www.housingauthority.gov.hk)** for details of the premium payment procedures.

(c) 買方須注意，在計算購樓時的折扣率所沿用的最初市值，是根據買方簽訂買賣協議時的市值。本銷售計劃單位的售價一經訂定，於銷售期間將維持不變，而訂定售價的時間和簽訂買賣協議的時間一般約有數個月的差距。在這期間，單位的市值可能會隨市況的轉變而調整。因此，買方簽訂買賣協議時的確實折扣率或會與訂定售價時的折扣率有所不同。補價款項將以簽訂買賣協議時確實的折扣率計算。

(d) 任何違反與單位有關的買賣協議的任何條款或條件或違反單位的轉讓契據內的任何契諾所作出的按揭、其他押記、轉讓或其他讓與、連同任何關於如此按揭、押記、轉讓或以其他方式讓與的協議（下稱「非法讓與」），根據《房屋條例》（第283章）第17B條均屬無效。任何人就其單位作出非法讓與即屬犯罪，將面臨《房屋條例》（第283章）第27A條下之刑罰。

(c) Purchasers should take note that the initial market value used to calculate the discount at the time of purchase is the market value prevailing at the date of the ASP. The sale price of flats in the current sale exercise, once fixed, will remain unchanged throughout the sale period. As there is normally a time lag of a few months between the fixing of the sale price and the signing of the ASP, during which the market value of a flat may fluctuate according to the market conditions, the actual discount rate at the time of signing the ASP may be different from that when the sale price was fixed. The actual discount at the time of signing the ASP will be adopted for calculation of the premium.


(d) Any purported mortgage, other charge, assignment or other alienation, together with any agreement so to mortgage, charge, assign or otherwise alienate in breach of any term or condition of the ASP or any covenant in the Deed of Assignment of the flat ("unlawful alienation") shall be void under Section 17B of the Housing Ordinance (Cap. 283). Any person committing unlawful alienation of his/her flat commits an offence and will be subject to criminal sanction under Section 27A of the Housing Ordinance (Cap. 283).

註：
原來買價相等於售價，是指首次轉讓契據中所列明的單位購買價。

Note :
Original purchase price is equal to the sale price and means the price of the flat as specified in the first assignment.

32 參考圖
Reference Plan

施工中的參考圖
Reference Plan for Works in Progress



比例尺 SCALE: 0 50 100 150 200 250 (米) (m)

N

青富苑
Ching Fu Court

圖例 NOTATION

污水處理廠及設施 Sewage Treatment Works and Facilities	社會福利設施 (包括老人中心及弱智人士護理院) Social Welfare Facilities (including an Elderly Centre and a Home for the Mentally Disabled)
市場 (包括濕貨市場及批發市場) A Market (including a Wet Market and a Wholesale Market)	體育設施 (包括運動場及游泳池) Sports Facilities (including a Sports Ground and a Swimming Pool)
發電廠 (包括電力分站) A Power Plant (including Electricity Sub-stations)	公園 A Public Park
公眾停車場 (包括貨車停泊處) A Public Carpark (including a Lorry Park)	公共交通總站 (包括鐵路車站) A Public Transport Terminal (including a Rail Station)
學校 (包括幼稚園) A School (including a Kindergarten)	公用事業設施裝置 A Public Utility Installation
油站 A Petrol Filling Station	貨物裝卸區 A Cargo Working Area
	施工中 Works in Progress

此參考圖參考日期為2024年1月4日之測繪圖(編號為T10-NE-B)製作，有需要處經修正處理。地圖由香港地理數據站提供，香港特別行政區政府為知識產權擁有人。

The Reference Plan is prepared with reference to Survey Sheet No. T10-NE-B dated 4 January 2024, with adjustments where necessary.

The map is provided by the Hong Kong GeoData Store and intellectual property rights are owned by the Government of the HKSAR.

註：

賣方建議買方到該發展項目作實地考察，以對該發展項目、其周邊地區環境及附近的公共設施有較佳的了解。


Note :

The Vendor advises purchasers to conduct on-site visit for a better understanding of the Development, its surrounding environment and the public facilities nearby.


青富苑A座單位的減音窗及固定窗的參考圖
Reference Plan for Acoustic Windows and Fixed Windows of Flats at Block A in Ching Fu Court

圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	減音窗	Acoustic Windows
	固定窗	Fixed Windows



青富苑B座單位的固定窗的參考圖
Reference Plan for Fixed Windows of Flats at Block B in Ching Fu Court



圖例 NOTATION

BATH	浴室	Bathroom
ELEC. METER ROOM	電錶房	Electrical Meter Room
HR	消防喉轆	Hose Reel
KIT	廚房	Kitchen
LIV/DIN	客/飯廳	Living/Dining Room
RS & MRR	垃圾及物料回收室	Refuse Storage and Material Recovery Room
W.M.C.	水錶櫃	Water Meter Cupboard
TELECOM & ELV ROOM	電訊及特低壓機房	Telecommunications and Extra Low Voltage Room
	固定窗	Fixed Windows

網址 WEBSITE

www.housingauthority.gov.hk/efas/2023/ChingFu

發展項目及其周邊地區日後可能出現改變。

There may be future changes to the Development and the surrounding areas.

印製日期：2020年4月20日

Printing Date: 20 April 2020

香港房屋委員會
Hong Kong Housing Authority